

Sycamore Creek Project Study Report



Prepared for
Santa Barbara County
Flood Control and
Water Conservation
District



Prepared By:



March 7, 2018

The Sycamore Creek Project Study Report has been prepared under the direction of Mohammed Wahiduzzaman and Thomas Conti, Registered Civil Engineers. The Registered Civil Engineer attests to the technical information contained herein and the engineering data upon which the recommendations, conclusions, and decisions are based.



Md. Wahiduzzaman

March 7, 2018

REGISTERED CIVIL ENGINEER

Date



Thomas Conti

March 7, 2018

REGISTERED CIVIL ENGINEER

Date





Table of Contents

Executive Summary i

 Project Sponsorship..... i

 Purpose i

 Goals of this Study..... i

 Key Factors ii

 Costs and Conclusions: v

Introduction 1

 Background 1

 Recent Project History 2

Target Conveyance 3

Sycamore Creek Watershed 5

 Project Study Area 6

 Floodplain Description 10

 Flood History 10

 Hydrology 10

Hydraulic Analysis 11

 Survey and Mapping..... 11

 Hydraulic Model 12

Geotechnical 13

 Regional Geology 13

 Geologic Units 13

 Record Soil Investigations 13

Preliminary Right of Way Analysis..... 15

Creek Configuration: 15

 Types of walls considered: 18

Conclusions and Recommendations 24





Appendix A – HEC-RAS Exhibits 25

Appendix B – Soil Investigation Logs and Testing 126

 Cabrillo Blvd 127

 US 101..... 130

 Punta Gorda Bridge Project..... 134

 Cacique and Soledad Bicycle and Pedestrian Bridges Project..... 163

 Mason Street Pedestrian Bridge Project..... 185

 Quinientos Street Bridge Replacement Project 201

 Montecito Street Bridge Replacement Project..... 221

Appendix C – Right of Way Exhibits..... 239

Appendix D – Channel Configuration Exhibits..... 246

Appendix E – Project Costs..... 253

References:..... 261





Executive Summary

Project Sponsorship

This report documents the findings of a hydraulic study for the Lower Sycamore Creek Watershed in Santa Barbara, CA. This study was undertaken by Bengal Engineering as a cooperative venture between the City of Santa Barbara (City) and the Santa Barbara County Flood Control and Water Conservation District (District); the study area is located within the jurisdictional City Limits; but both the City and the District have the authority to construct facilities for collection, control and discharge of stormwater in the community.

Purpose

The City and Caltrans have already completed key public works projects in the lower reach of Sycamore Creek to address flooding concerns or replace elderly bridges. Additional projects are currently under design. The City is also planning future projects which steps closer to improve flood control protection to the community.

The District knows that should the hydraulic analysis for each of these projects be undertaken individually, variables in project approach, professional judgement and engineering analysis are expected, and that these variables will be difficult to reconcile in a larger study of the watershed.

To alleviate these challenges, the District contracted Bengal Engineering to perform this study.

Bengal was selected because of our expertise in regional hydraulic modeling, knowledge of the engineering of nearby bridges, understanding of agency and community expectations, and our familiarity with both District and FEMA practices.

Goals of this Study

This Project Study Report defines:

- The target stream conveyance—the appropriate design flow for both engineering and planning purposes which heretofore has not been specified through a study such as this
- The appropriate locations / types for the channel walls
- locations where vegetated stream banks may be implemented
- Locations of real property conflicts
- Project costs, including right of way acquisitions





Key Project Data: Existing Lower Sycamore Creek

Item	Data
Sycamore Creek Watershed Area	2,600 acres
100-yr peak discharge	3,306 cfs*
50-yr peak discharge	2,942 cfs*
10-yr peak discharge	1,897 cfs*
Maximum Non-Damaging Discharge (at Zoo Bridge)**	1,100 cfs
Maximum Non-Damaging Discharge (at Indio Muerto Bridge)**	1,200 cfs

* Source: FEMA Flood Insurance Study (FIS)

** Maximum discharge prior to lateral spreading (overtopping)

Key Factors

Hydrology and Hydraulics:

While stand-alone projects built in past years haven't alleviated flooding by increased overall flood capacity of Lower Sycamore Creek, these project have provided building blocks. These past projects, plus the future projects mentioned herein will help achieve global improvements; For example, the Highway 101 Bridge over Sycamore Creek, constructed in 2010 is currently partially closed, intentionally, to limit flow because the adjacent channels cannot accommodate additional discharge as they exist. However in the future, when the remaining channel improvements are built, all the spans of the Hwy 101 bridge can be opened so that the completed system can work in unison.

Existing Restrictions

Even with the Highway 101 Bridge over Sycamore Cr. completed, the same bridges identified in previous studies remain problematic because these areas constrict flow.





Replacement Bridge Locations

Location	Limitations	Capacity (cfs)	Recommendation
Por La Mar Bridge 1	Two center piers and low soffit	1,800	Replace bridge with clear span
Por La Mar Bridge 2	Two center piers and low soffit	1,500	Replace bridge with clear span
S.B. Zoo	Two center piers and low soffit	1,100	Replace bridge with clear span
U.P.R.R. Bridge	Embankments	2,400	Vertical walls
Indio Muerto Street Bridge	Narrow bridge, Two center piers and low soffit	1,200	Replace bridge with clear span
Carpinteria Street Br	Two center piers and low soffit	2,600	Replace bridge with clear span

Undersized Channel Locations

Location	Limitations	Capacity (cfs)	Recommendation
Cabrillo Blvd to US 101	Narrow channel	1,300 to 1,800	Increase channel width to varying configuration depending on ROW impacts.
Indo Muerto to Cacique St	Narrow channel	1,200	Increase channel width to 60'. Predominantly vertical wall because of ROW impacts.





Planning Participants/Objectives:

A next step in the development of this project, beyond the scope of this Project Study Report, is form and coordinate a Consensus Group comprised of Federal and State regulatory agencies such as the Environmental Protection Agency, the U.S. Army Corps of Engineers, U.S. Fish and Wildlife Service, National Marine Fisheries Service, California Department of Fish and Wildlife, California Coastal Commission, Regional Water Quality Control Board, and other City Departments including Public Works, Parks including Creeks Division, and various City review and permitting bodies; community non-governmental and non-profit organizations, and the public at-large. This is the model approach successfully used by the Lower Mission Creek Project, in not only outreach and coordination but defining the following project activities:

- Provide increased flood protection along this reach of Sycamore Creek;
- Restore the native species of native riparian community along the project reach;
- Remove and suppress invasive non-native vegetation and replace with native plants;
- Enhance the aquatic habitat by changing the streambed characteristics;
- Define the project that is self-mitigating; and
- Achieved these objectives with a positive benefit to cost ratio

Reference: Santa Barbara Streams, Lower Mission Creek Flood Control Feasibility Study, U.S. Army Corps of Engineers, September 2000

As with the Lower Mission Creek Project, a goal with the Sycamore Creek Project will be to identify a self-mitigating project.





Costs and Conclusions:

Cost data was compiled for the final report in spring of 2018. Costs of construction and real property will likely fluctuate with time. These costs derived for the project are all encompassing not speculating how funding will be obtained nor who will be fiscally responsible for implementation.

Costs:

- Our estimate shows that 2/3 of the costs for hydraulic improvements on Sycamore Creek are bridge replacement.
- See appendix E for Anticipated Project Costs

Target Conveyance:

- The construction of the Highway 101 crossing at Sycamore Creek in 2010 now sets the capacity limits for Sycamore Creek. The Bridge was constructed with three “bays”. The three bays, if unobstructed, in combination would handle 3,000 cfs.

Real Property:

- Ahead of project implementation, the County and the City should consider purchasing parcels in conflict, which encroach into the creek.
- See appendix C Right of Way Exhibits

Preferred Wall Type:

- Pile wall systems have several advantages, too many to discuss (please see channel wall type selection section).





Introduction

The City of Santa Barbara (City) has completed several public works projects within the lower reach of Sycamore Creek. Several more are under design or planned for the future. Each of these projects has been undertaken with limited time, budget and scope to accommodate the needs of the individual projects.

This study evaluates the overall performance of the completed system. To do this, the District hired Bengal Engineering to create coordinated computer model (HEC-RAS) to analyze the performance of the stream. This model is used to evaluate the improvements made so far and determine “what remains to be done” to protect the community from flood flows. The result will deliver a project, which will allow for future FEMA Flood Insurance Revision Map (FIRM) revisions reducing the amount of residences in the 100 year flood plain.

This study also sets engineering guideline for this reach.

Report Goals

This Project Study Report defines:

- The target stream conveyance—the appropriate design flow
- The appropriate locations / types for the channel walls
- locations where vegetated stream banks may be implemented
- Locations of real property conflicts
- Project costs, including right of way acquisitions

Background

In 2003, the City and the District worked together to commission a *Flood Capacity Master Plan for Sycamore Creek (called “The 2003 Plan herein”)* dated November 21, 2003 prepared by Penfield and Smith to evaluate the existing capacity of the creek system and the capacity improvement potential of the system.

The 2003 Plan has served as a guide for projects in terms of potential conveyance goals, but did not specify a detailed configuration of much of the completed project and its associated impacts.





The City and District both recognized that the effectiveness of a long-term flood control project could be jeopardized by near-term project. Further these agencies recognized that if the projects were not coordinated to evaluate hydraulic performance as part of the whole, short term design features could be detrimental to the overall objective to protect the public as a system which would be completed in parts-and-pieces as advantages budgets and circumstances presented themselves. The 2003 Plan defined the stream conveyance capacity at 3,000 cubic feet per second (cfs). With this finding, public and private projects proceeded toward this objective.

Recent Project History

As anticipated in the development of the 2003 Plan significant development projects began breaking ground in 2007. The following is the known list of projects.

Completed Projects			
Year	Project	Design Intent	Lead Agency
2007	Mason Street Pedestrian Bridge	Provide pedestrian route over Sycamore Creek.	City of Santa Barbara
2010	Highway 101 Improvements from Olive Mill Road to Milpas Street	Highway 101 widening from Olive Mill Road to Milpas Street. This included Highway 101 Sycamore Creek Bridge.	Caltrans
2013	Lower Sycamore Creek Channel Widening and Punta Gorda Street Bridge Replacement	Replace the Punta Gorda Bridge over Sycamore Creek and complete channel widening downstream between Punta Gorda Street and US Highway 101.	City of Santa Barbara
2015	Cacique & Soledad Street Pedestrian/Bicycle & Corridor Improvements	Replace the pedestrian crossing on Cacique Street and place a new pedestrian crossing on Soledad Street over Sycamore Creek.	City of Santa Barbara





Active Projects			
2014	Quinientos Street Bridge Replacement	Replace the Quinientos Street Bridge over Sycamore Creek.	City of Santa Barbara
2015	Montecito Street Bridge Replacement and Pedestrian Improvements	Replace the Montecito Street Bridge and complete pedestrian improvements.	City of Santa Barbara

Future Projects			
TBD	Carpinteria Street Bridge Replacement	Highway Bridge Program Funded	City of Santa Barbara

Target Conveyance

The California Department of Transportation (Caltrans) completed various improvements to Highway 101 in 2009-2010. These improvements include widening of the vehicle travel way and replacement of the bridges over the creeks, including the Hwy 101 bridge at Sycamore Creek.


While the Caltrans project had funding for the transportation improvements (highway and bridge improvements), the Highway 101 widening project did not have the budget or scope to address the flood control capacity improvements in the channels outside of the State right-of-way.

This scenario--two agencies working together—a transportation department upgrading the roadway network -- a flood control agencies upgrading the flood protection system, is familiar to agency personnel in Santa Barbara. For example, across town on the Mission Creek, the District working with USACOE improved flood conveyance by designing channel improvements while the City of Santa Barbara, working with Caltrans Local Assistance, has been replacing the bridges using FHWA Highway Bridge Program money. The combined effort improves both the transportation system and the flood control facilities, sometimes building the projects at the same time.





In the case of the Hwy 101 bridge at Sycamore Creek, Caltrans engineers coordinated with the District, planning ahead for the future flood control project which would be built outside the Caltrans right-of-way. To accomplish this, Caltrans built a bridge which they anticipated would be large enough for the increased flows resulting from the future Sycamore creek improvements. But because of the limitations in the existing channel capacity outside of the State right-of-way, Caltrans engineers blocked two of the three-spans in the new bridge, on-purpose, to restrict flows until the channel improvements can be built by the District. Someday when the channel is improved, the “plugs” under the bridge will opened, and the system will function with joint benefits, like the Mission Creek Project.



The Bridge was constructed with three “bays”. The three bays, if unobstructed, in combination would handle 3,000 cfs. Due to the existing downstream capacity deficiencies of Sycamore Creek, Caltrans has limited capacity by only opening the center bay.





Sycamore Creek Watershed

Sycamore Creek is located within an alluvial coastal basin with the ground surface sloping gently from north to south. The project jurisdictional area is in the Eastside area of the City of Santa Barbara, CA. The relatively flat topography in the area is bisected by the active Sycamore Creek channel, which generally flows to the south. Sycamore Creek is an ephemeral, or intermittent, drainage along its length.

The Sycamore Creek Watershed (see figure 1) is relatively short in length. The upper portion of Lower Sycamore Creek is less urbanized in comparison to other watersheds in the Santa Barbara area. Upper Sycamore Creek originates in the Los Padres National Forest and contains five tributaries in the foothills: the main stem, beginning near Sheffield Reservoir, the Parma Park tributaries, Coyote Creek, Westmont Creek, and Chelham Creek, a tributary east of Westmont Drive. These tributaries converge adjacent to the intersection of Sycamore Canyon Road and Stanwood Drive in Sycamore canyon.

The creek then follows a narrow canyon to Alameda Padre Serra. The slope in this middle reach becomes less-steep as the creek traverses a medium-density residential area.

Downstream the creek drains into the lower reach floodplain areas which are highly-developed. This zone includes areas of significant historic flooding during large rain events. The slope in this reach becomes flatter as the creek empties into the ocean at East Beach, where a sandbar forms a small lagoon.

Area: Approximately 2,600 acres

- 20% under County jurisdiction
- 55% under City jurisdiction
- 25% under Los Padres National Forest Jurisdiction






Project Study Area

The Sycamore Creek area considered in this Project Study Report (see figure 2), begins at Yanonali Bridge and travels 1.1 miles to the Pacific Ocean, completely within the City of Santa Barbara jurisdiction. This area of Sycamore Creek is located in an urbanized area and retains a mostly natural streambed. Pipe and wire revetment bank protection is installed throughout much of this reach. Several bridges of various configurations also occur in this region.

The lowest portion(s) of Sycamore Creek (see figure 3), from Cabrillo Blvd. to the Pacific Ocean, is within the California Coastal Commissions (CCC) permit jurisdiction. This means projects south of Cabrillo Blvd. would be required to get a CCC permit. The section from Highway 101 to Cabrillo Blvd. is considered to be in the “appealable jurisdiction”, which means a public or private entity could request to the CCC that the project should obtain a CCC permit.





Sycamore Creek Watershed

FIGURE 1





REFERENCE:

U.S.G.S. Santa Barbara
7.5-Minute Quadrangle, 2015



1	2	3	1 San Marcos Pass
4	5	6	2 Little Pine Mountain
6	7	7	3 Hildreth Peak
7	8	8	4 Goleta
			5 Carpinteria

ADJOINING QUADRANGLES

ROAD CLASSIFICATION


Expressway	Local Connector
Secondary Hwy	Local Road
Ramp	4WD
Interstate Route	US Route
FS Primary Route	FS Passenger Route
	FS High Clearance Route
	State Route

Check with local Forest Service unit for current travel conditions and restrictions.







SANTA BARBARA, CA
2015

FIGURE 2





Legend

-  Coastal Zone Boundary
-  Creeks
-  City Limits
-  Appealable Jurisdiction I & III
-  Non Appealable Jurisdiction
-  California Coastal Commission Permit Jurisdiction

REFERENCE:

City of Santa Barbara Local Coastal Program Jurisdictional Boundaries

as Certified by California Coastal Commission on July 21, 1991
Map prepared by City of Santa Barbara, Planning Division, A/JN, TRB, 9/29/2014



FIGURE 3





Floodplain Description

Within the project limits, the Federal Emergency Management Agency (FEMA) defines floodplains for Sycamore Creek. A floodway is a portion of the base floodplain which must be kept free of encroachment. Floodways are a regulatory tool used to manage development in floodplains.

Flood History

Damaging floods in this area are reported to have occurred as early as 1862. Floods of sufficient magnitude to cause extensive damage along Lower Sycamore Creek occurred in 1862, 1909, 1914, 1927, 1938, 1962, 1966, 1967, 1969, 1971, 1995, 1998 and 2005.

The worst flooding in the area took place in 1969, 1971, 1995 and 1998. The storms in 1966 and 1969 caused considerable damage throughout the area due to flooding, erosion, and debris deposition.

During the 1995 floods, residents in the neighborhood adjacent to Sycamore Creek chopped holes through the wooden Caltrans sound wall along the highway in order to facilitate the passage of flood flows. The sound wall has since been replaced and now incorporates floodgates which allow flood flows to pass unobstructed.

Hydrology

The drainage area is located in a narrow coastal zone rising steeply to the crest of the Santa Ynez Mountains in a north-south direction. The mountains rise about 3,000-3,500 feet in less than 5 miles. The crest elevations of the drainage basin starts about 3,000 feet above mean sea level. In the upper reaches the stream has fairly steep gradients. In the lower reaches, on the alluvial plain below the foothills, slopes average approximately 150 vertical feet/mile.

The mountains above Santa Barbara provide significant orographic uplift and receive much higher precipitation than the coastal plain. The mean seasonal precipitation for the drainage area is approximately 18-inches-per-year along the coast and 30-inches-per-year in the mountains.

The majority of the precipitation occurs between November and April. Flooding typically occurs between December and March. The majority of the precipitation is a result of general winter storms associated with extra-tropical cyclones of North Pacific origin. The rainfall events that cause flooding in the Santa Barbara area are intense and are typical in coastal California. These floods are of a short duration, with extreme flooding lasting a few hours or less.





Sycamore Creek is a well-established channel that runs through the City of Santa Barbra. Increasing urbanization of the watershed during the historical period has contributed to increased run-off.

A Flood Insurance Study (FIS) was issued by FEMA. The 100-year discharge cited in the FIS for Sycamore Creek at De La Guerra Street was 3,306 ft³/sec.

Sycamore Creek Flood Frequency Summary

The FEMA Flood Insurance Study Statistical Frequency Analysis of Peak Flows are summarized below:

Percent Chance Exceedance	Return Period (yrs.)	Peak Discharge (ft ³ /sec)
.2	500	4,207
1	100	3,306
2	50	2,942
10	10	1,897

Hydraulic Analysis

The hydraulic analysis for the project reach was performed using the USACE HEC-River Analysis System (HEC-RAS) program, Version 5.0.0 (USACE, 2016).

The model was developed to reflect the existing conditions and all of proposed channel improvements along Sycamore Creek.

Survey and Mapping

From 2013 to 2017 various topographic surveys of the creek have been completed for projects initiated and managed by the City of Santa Barbara. Bengal Engineering obtained this available ground topography to use as a base creek topographic map or digital terrain map. This original digital terrain map was enhanced by additional field surveyed cross sections and merged with the Eastside base mapping for the City of Santa Barbara. This base mapping created the original digital model of the creek and its surrounding area.

After this base mapping was completed we have received the 2016 LIDR GIS data from the City of Santa Barbara. This new digital terrain model fits very well with our current HEC-RAS model and will be utilized for the final report comparison.





Hydraulic Model

The industry standard Hydrologic Engineering Center River Analysis System “HEC-RAS” program (version 5.0.3) was used to develop georeferenced stream station lines, cross section alignments and cross section profiles. The cross sections profiles were cut using the digital model surface.

This digital model formed the basis of the existing creek capacity to establish existing conditions. The model was collated with the recent FEMA FIRM panel 06083C1391H effective November 4, 2015 to match station for station with this FIRM map.

The proposed condition model required successive and selective runs to determine the creek improvements necessary for channel improvements that could contain the 3,000 cfs target conveyance set by the Highway 101 project.

Our analyses started at the Pacific Ocean working up the creek to target conveyance capacity through reconfiguring in the following order:

1. Structures within the local jurisdiction
2. Highway 101 (opening of the bays, one by one)
3. Evaluating and reconfiguring the channels where less-than-ideal capacity is creating overland flow

Results

The target conveyance analysis profiles, cross sections, and results are included in Appendix A.





Geotechnical

Regional Geology

The project area is located within the Western Transverse Ranges physiographic province of Southern California. This geologic province consists of a complex series of east-west trending mountain ranges and valleys. The structural orientation of this province is transverse to the general north-northwest structural trend of the other geologic provinces in California. The Western Transverse Ranges province extends from Ventura County west to Point Arguello, and is dominated by the east-west trending Santa Ynez Mountain Range. Cretaceous to Cenozoic sedimentary marine rocks and Miocene volcanic rocks dominate the Western Transverse Ranges region.

The project site is located within an elevated portion of the Santa Barbara coastal plain characterized by a gently undulating, but generally north to south sloping ground surface. It is thought the elevated nature of the plain is caused by tectonic uplift during the Quaternary age (Dibblee, 1986). The area is underlain by late Pleistocene-age older alluvium and Holocene-age alluvium over the south-dipping homoclinal structure of the Santa Ynez Mountains.

Geologic Units


The surficial geologic formations and major geologic structural features present in the general area of the project are shown on Figure 4, Local Geologic Map. The exposed formations in the immediate vicinity vary from Miocene-age to recent (i.e. Holocene) deposits. These deposits include the Monterey Formation (T_{mu}), upper and middle Pleistocene older alluvium (Q_{oa}), upper Pleistocene "intermediate" alluvial deposits (Q_{ia}), and recent alluvium (Q_a). The area is underlain by Holocene to upper Pleistocene age alluvium consisting of unconsolidated to slightly consolidated clay and, poorly to moderately sorted silt, sand and gravel deposits (Dibblee, 1986, Minor et al., 2009).

Record Soil Investigations

Bengal Engineering's scope did not include field soil investigations or recommendations for specific soil parameters to use in design.

Since the project is still in its infancy, the District preferred to gather the available boring logs from recent projects so this information will be handy when more engineering moves forward. See Appendix B for the boring logs.





Qe Estuarine deposits (Holocene)—Locally organic-rich clay, silt, and subordinate sand deposited primarily in peritidal environment in low-lying coastal areas of modern and historically active sloughs. Maximum thickness probably less than 20 m

Qac Alluvium and colluvium (Holocene and upper Pleistocene)—Poorly consolidated silt, sand, and gravel deposits of modern drainages and piedmont alluvial fans and floodplains. Exposed thickness generally less than 10 m

Qia Intermediate alluvial deposits (upper Pleistocene)—Weakly consolidated, stratified silt, sand, and gravel that form low, rounded, moderately dissected terraces and piedmont alluvial fans that rest at higher elevations than the modern coastal piedmont surface underlain by unit Qac. Thickness probably locally exceeds 20 m

Qoa Older alluvial deposits (upper and middle Pleistocene)—Moderately consolidated, crudely stratified, poorly sorted sand and sandstone, gravel, conglomerate, and breccia, and rare interbeds of clay, silt, and mudstone comprising proximal to distal facies of alluvial fans shed from the Santa Ynez Mountains. Unit forms dissected, gently south-sloping elevated terraces, interfluvial caps, and other erosional remnants as thick as 35 m

Reverse fault—Rectangles on apparent upthrown side

REFERENCE

GEOLOGIC MAP OF THE SANTA BARBARA COASTAL PLAIN AREA, SANTA BARBARA COUNTY, CALIFORNIA

By
 Scott A. Minor,¹ Karl S. Kellogg,¹ Richard G. Stanley,² Larry D. Gurrola,³ Edward A. Keller,⁴ and Theodore R. Brandt¹
 2009

FIGURE 4





Preliminary Right of Way Analysis

An intent of this Project Study Report is to preliminarily identify permanent property acquisitions that will be required to construct the project based on preliminary design presented herein. Final limits of acquisitions that will be subject to change and will be identified at final design. At that time, acquisitions will be defined as fee or easement. Temporary construction easements will also be identified at the time of final design.

All acquisitions will be in conformance with the law, including the State of California's Relocation Assistance and Real Property Acquisitions Guidelines found in Title 25, Division 1, Chapter 6, and Subchapter 1 of the California Code of Regulations.

See appendix C "Right of Way Exhibits" for areas of potential acquisitions. Please note the property mapping was generated from County GIS mapping. The exact areas quantified would be refined in final design when a licensed surveyor compiles survey boundary work.

Creek Configuration:

When looking at completing capacity improvements the project will ultimately be a balance between the project capacity improvement goals and restoration or enhancement of the natural creek corridor. The expectations will be high from the local environmental community to re-establish natural riparian corridors. The predominant accepted method to do establish a more natural creek corridor is to emulate a vegetated sloped creek bank. This will be difficult in Sycamore Creek because the urban encroachment.

Creek Configuration Methodology

In order to look at the proposed configuration we first had to understand the existing conditions. The first order of business was establishing the FEMA baseline from the November 4 of 2015 FIRM and correlating it with the topographic mapping. Once this was completed, we obtained the most current orthophotography available to overlay this for understanding possible conflicts.

After the mapping was established to understand any impacts, we input the HEC-RAS parameters on to the mapping to further validate possible conflicts. We then went to visit the sites of potential conflict to confirm the proximity to the proposed channel.

See appendix D "Channel Configuration Exhibits" for proposed Sycamore Creek improvements footprint.





Channel Wall Type Selection

The creek corridor is crowded by dense development. Today, single family homes, condominiums, apartment buildings, trailer parks, even the Santa Barbara Zoo are located near the top-of-bank. The creek is also crossed by City streets, the Hwy 101 or “the Crosstown Freeway” as well as the the Union Pacific Railroad.

Various utilities, both overhead and underground crisscross the project corridor.

In order to accommodate much of the existing development while increasing conveyance in certain areas by widening the creek, engineers anticipate that a mix of channel cross-section configurations will be needed. In places where there is more room available, the channel may be widen using vegetated side-slopes. In other areas, because of the close proximity of existing development, and because of the prohibitive cost to acquire right-of-way, vertical walls will likely be needed to widening the channel while also minimizing the project footprint.

At the time this report was created, the area of study had recently experienced a fair amount of redevelopment. For example, the Sycamore Creek Development on Punta Gorda Street (also known as the “Tiny Houses Project”) has replaced an old trailer park (2015). Nearby, the Puente Gordo Street Bridge has been replaced and portions of the downstream channel have been modified (2015).

Upstream at Indio Muerto Street a substantial housing complex was constructed on property previously occupied by smaller duplexes and workshops (2016).

Further upstream at Cacique Street, two larger mobile home parks have been the subject of recent discussion, even controversy, regarding future redevelopment. Projects such as these could affect the Lower Sycamore Creek Project and therefore the locations where either vertical channel walls or sloping channel banks will be located in the future.





At the time this report was prepared, engineers acknowledged development opportunities but did not study multiple scenarios for locations of vertical walls because of limited time and budget.

See the “Channel Configuration Exhibits” in this report for possible locations of the walls.

In this report, the key points for this topic include:

- A) the project will likely include vertical channel walls at various locations to accommodate the limited space available at those locations.
- B) Based on the existing information, Bengal provides a preliminary recommendation of the types of wall which hold promise for the project.
- C) Bengal has gathered the boring logs from various projects in anticipation of additional study of this important topic. Much work remains to be done.

Estimated Wall Heights for the Project at Various Locations

Location	Roadway Elevation*	Creek flowline Elevation *	Exposed Wall Height
Punta Gorda St.Br	20+/-	9'+/-	11'+/-
N. of Indio Muerto St.	28+/-	15'+/-	13'+/-
Cacique St. Br.	29'+/-	17'+/-	12'+/-
U/S of Carpinteria St. Br.	34'+/-	20'+/-	14'+/-
Quinientos St. Br	45'+/-	30'+/-	15'+/-
Mason Str. Br.	51+/-	36'+/-	15'+/-
Yanonali St. Br	60'+/-	50'+/-	10'+/-

*North American Vertical Datum 1988 (NAVD 88)





Types of walls considered:

1. Gravity Walls or Walls on Spread Footing Foundation

The use of walls which are supported by larger footings, such as a Gravity wall or spread footings face challenges making them generally unsuitable for this project. These challenges include:

- High ground water/ standing water the downstream reaches complicate construction of any alternative wall type. However attempting to build larger or spread footings in saturated soils presents construction hurdles which are more-easily avoided with piles.
- Use of a spread footing system will require a larger construction footprint and therefore more right-of-way compared to walls supported by piles
- This larger foundation footprint will also require more shoring and greater earthwork compared to walls supported by piles
- Typically, in order to save cost, material which is excavated on site, is used for backfill once wall is completed. Because the project has limited room to stockpile and perhaps dewater excavated material while also providing construction access, this wall type presents more logistical challenge for material handling than pile walls.
- Requires a large volume of material (specific to Gravity Wall).
- Appropriate for low walls or lightly loaded walls (specific to Gravity Walls).
- Length of construction will likely be longer than pile walls.





2. Sheet Pile Walls

We envision that the use of sheet piling may also face challenges, which include:

- Because of the height of the walls, ground anchors (tiebacks) may be needed. These will anchors would penetrating the private property behind the wall, likely generating greater challenges to acquire right-of-way in comparison to a wall system which doesn't require tiebacks.
- The construction of sheet pile walls present aesthetic challenges which could be controversial in an urban setting. Measures used to "hide" the wall could be expensive to implement and perhaps difficult to maintain.
- Steel sheet pile and could face limited service-life due to corrosion, especially in the downstream reach near the beach. Cost and effort to replace this sheet pile sometime in future could be substantial because effort for permitting and costs-for-construction have historically increased.
- Concerns with construction-generated vibration and "drivability" for sheet pile remain key questions to be investigated should this option be further considered.

3. Wall Supported on Driven Piles

At a different location, that is one one with greater distances to safeguard the existing buildings and underground infrastructure from vibration and noise, a foundation using driven piles could be an option.

But at this location:

- Driven piles raise liability concerns due to construction noise and vibration
- Overhead power lines raise immediate questions in terms of practicality.
- The variable geology in the region presents uncertainty and therefore likely greater geotechnical investigation.






4. Soil-Anchored Wall

An soil-anchored wall (also called a “Tieback wall”) includes a wall face supported by soil anchors penetrating the soil behind the wall .

Challenges envisioned for such a system in this project include:

- Soil-anchor walls present risk construction / performance challenges in the variable geology expected on this site. As the soil varies, so could the length and configuration of the tieback system
- The right-of-way behind the wall needed to accommodate the anchors could be difficult and expensive to obtain. Other systems do not require this space.
- Use of soil anchors in a flood wall the saturated soil which will occur during flood conditions presents an engineering challenge which may be difficult to overcome. Soil properties will change rapidly during sequential flooding / draw-down events.
- Should unforeseen geologic conditions be encountered which degrade the expected performance of the tiebacks, the project could be stalled while another solution is considered. Such a delay will be detrimental in such tight working conditions and construction periods.



Cross Section of a Tieback Wall






5. Mechanically Stabilized Earth Wall

Mechanically stabilized earth, also called “MSE walls”, are built by alternating vertical layers of proprietary soil reinforcement material with select backfill soil creating an engineered “layer cake” behind the wall.

The outer face of the wall is usually made from precast concrete panels which hook to the soil reinforcement in back of the wall facing via proprietary connections because many of these systems are patented.

Challenges envisioned with this system include:

- The use of MSE in a permanent flood-control project is non-standard application for this system. MSE walls are generally used in “dry” applications such as roadway embankments and site grading. This application allows the backfill “high and dry”, providing engineers more consistent soil properties for design.
- The reinforced backfill requires more right-of-way to accommodate the soil reinforcement behind the wall compared to some wall systems.
- More construction room is needed build MSE walls than some other systems.
- Accommodating surface drains / inlets from areas behind the walls could be difficult because of the reinforcing mats in the backfill and the openings in the MSE walls.
- Proprietary nature of these patented wall systems can present bidding and construction and issues in a competitive-bid project.



Cross Section of an MSE Wall






6. Secant Pile Walls


Secant pile walls constructed by series of drilling a series of overlapping holes which are filled with concrete to form a continuous wall system.

Bengal Engineering has designed these for the District on the Lower Mission Creek Project.

Advantages with this wall system will be discussed with the Soldier Pile alternative, below.



Plan-View of Bengal-Designed Secant Pile Wall: for the Mason St. Bridge



Example of Secant Pile Wall: Lower Mission Cr. at of Mason St. Bridge (Bengal Photo ©)






7. Soldier Pile Walls

Soldier pile walls are built by constructing a line of piles (like a line of “soldiers”) to support a wall which spans from pile-to-pile. The piles can be driven or cast-in-drilled-holes.

Bengal Engineering designed many such walls locally including those at Cota Street Bridge, Haley / De La Vina Street Bridge, and Cabrillo Blvd. Bridge.



Example of Soldier Pile Flood Wall: Lower Mission Cr. at Cabrillo Blvd. (Bengal Photo ©)

Advantages of Secant-Pile or Soldier Pile Wall system

We envision advantages for either system on the Sycamore Creek Project could include:

- Smaller construction footprint compared to many systems
- Less dewatering for excavation than many systems
- Less excavation / handling of excavated materials than many systems
- No need for tie backs, therefore less right-of-way acquisition cost
- Longer service life than some alternatives
- System allows decorative fascia which can vary
- Known local success
- Familiarity by District / City
- Likely lower cost





Conclusions and Recommendations

Our conclusions and recommendation are limited to the reach of Sycamore Creek from the Pacific Ocean to Alameda Padre Serra.

This limited study was completed by reviewing the available information about Sycamore Creek within the limits of the project study area.

This report provides practical considerations to these reaches of Sycamore Creek. But this report was prepared with limited time, budget and information. A project of this magnitude, spanning approximately 1.2 miles and 8 city blocks which are densely developed, will require significant environmental review and engineering analysis block-by-block.

While we stand by our conclusions and recommendations, new and additional information during detailed design may supersede some of our findings and conclusions.

Costs:

- Our estimate shows that 70 to 80% of the costs for hydraulic improvements on Sycamore Creek are bridge replacement.

Target Conveyance:

- The construction of the Highway 101 crossing at Sycamore Creek in 2010 now sets the capacity limits for Sycamore Creek. The Bridge was constructed with three "bays". The three bays, if unobstructed, in combination would handle 3,000 cfs.

Real Property:

- Ahead of project implementation, the County should consider purchasing parcels in conflict, which encroach into the creek.
- See appendix C Right of Way Exhibits

Preferred Wall Type:

- Pile wall systems have several advantages, too many to discuss (please see channel wall type selection section).







Appendix A – HEC-RAS Exhibits





River	Reach	River Sta	Profile	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Vel Chnl (ft/s)	Flow Area (sq ft)	Froude # Chl
Sycamore Creek	Reach-1	6503	55-year	3000.00	53.10	66.65	62.32	67.48	0.002145	8.04	729.73	0.41
Sycamore Creek	Reach-1	6473	Culvert									
Sycamore Creek	Reach-1	6446	55-year	3000.00	51.78	62.81	62.81	65.68	0.014451	13.62	237.74	0.91
Sycamore Creek	Reach-1	6219	55-year	3000.00	45.13	60.68	52.95	61.39	0.001742	6.80	479.73	0.32
Sycamore Creek	Reach-1	6200	Bridge									
Sycamore Creek	Reach-1	6167	55-year	3000.00	47.44	58.79	56.58	60.29	0.004490	10.31	388.59	0.59
Sycamore Creek	Reach-1	5836	55-year	3000.00	44.10	55.69	55.36	57.89	0.010820	11.90	252.53	0.93
Sycamore Creek	Reach-1	5490	55-year	3000.00	39.00	47.35	47.35	49.89	0.076117	12.78	234.73	1.00
Sycamore Creek	Reach-1	5212	55-year	3000.00	35.31	44.81	39.81	45.32	0.001489	5.71	525.43	0.33
Sycamore Creek	Reach-1	5185	Bridge									
Sycamore Creek	Reach-1	5142	55-year	3000.00	35.65	44.44	40.21	45.04	0.001931	6.23	481.28	0.37
Sycamore Creek	Reach-1	4920	55-year	3000.00	33.00	42.67	41.06	44.09	0.006137	9.57	313.41	0.73
Sycamore Creek	Reach-1	4553	55-year	3000.00	29.30	39.15	39.15	42.02	0.012184	13.58	220.87	1.01
Sycamore Creek	Reach-1	4552	55-year	3000.00	26.00	39.19	30.96	39.42	0.000480	3.88	772.60	0.21
Sycamore Creek	Reach-1	4518	Bridge									
Sycamore Creek	Reach-1	4475	55-year	3000.00	25.69	38.62	33.93	39.22	0.004026	6.20	483.89	0.40
Sycamore Creek	Reach-1	4291	55-year	3000.00	25.10	34.70	34.70	37.40	0.011940	13.20	227.32	1.01
Sycamore Creek	Reach-1	4031	55-year	3000.00	22.96	31.05	27.40	31.63	0.001691	6.09	492.29	0.40
Sycamore Creek	Reach-1	3990	Bridge									
Sycamore Creek	Reach-1	3924	55-year	3000.00	22.28	29.56	26.80	30.43	0.003021	7.49	400.32	0.49
Sycamore Creek	Reach-1	3750	55-year	3000.00	21.80	26.61	26.61	29.01	0.013321	12.42	241.49	1.00
Sycamore Creek	Reach-1	3465	55-year	3000.00	18.56	25.05	22.81	25.97	0.003532	7.70	389.39	0.53
Sycamore Creek	Reach-1	3441	Soledad Br	Bridge								
Sycamore Creek	Reach-1	3423	55-year	3000.00	17.50	25.12	21.77	25.79	0.002151	6.56	457.39	0.42
Sycamore Creek	Reach-1	3381	55-year	3000.00	17.22	25.06	21.49	25.69	0.001972	6.38	470.57	0.40
Sycamore Creek	Reach-1	3333	Cacique (R)	Bridge								
Sycamore Creek	Reach-1	3287	55-year	3000.00	17.18	24.79	21.45	25.46	0.002163	6.57	456.78	0.42
Sycamore Creek	Reach-1	3261.57*	55-year	3000.00	17.06	24.70	21.31	25.36	0.002132	6.49	462.21	0.42
Sycamore Creek	Reach-1	3236.14*	55-year	3000.00	16.95	24.62	21.17	25.26	0.002054	6.39	469.20	0.41
Sycamore Creek	Reach-1	3210.71*	55-year	3000.00	16.83	24.54	21.04	25.16	0.001956	6.29	476.77	0.41
Sycamore Creek	Reach-1	3185.29*	55-year	3000.00	16.71	24.46	20.90	25.06	0.001867	6.20	483.92	0.40
Sycamore Creek	Reach-1	3159.86*	55-year	3000.00	16.59	24.39	20.76	24.97	0.001797	6.12	489.97	0.39
Sycamore Creek	Reach-1	3134.43*	55-year	3000.00	16.48	24.31	20.62	24.89	0.001758	6.07	493.89	0.38
Sycamore Creek	Reach-1	3109	55-year	3000.00	16.36	24.24	20.48	24.80	0.001739	6.04	496.57	0.38
Sycamore Creek	Reach-1	3077	Bridge									
Sycamore Creek	Reach-1	3032	55-year	3000.00	16.48	23.07	21.44	24.34	0.004973	9.04	331.75	0.65
Sycamore Creek	Reach-1	3004.00*	55-year	3000.00	16.19	22.88	21.10	24.06	0.004560	8.73	343.57	0.62
Sycamore Creek	Reach-1	2976.00*	55-year	3000.00	15.89	22.71	20.77	23.80	0.004121	8.37	358.22	0.59
Sycamore Creek	Reach-1	2948.00*	55-year	3000.00	15.60	22.58	20.42	23.56	0.003617	7.94	377.85	0.56
Sycamore Creek	Reach-1	2920.00*	55-year	3000.00	15.30	22.47	20.05	23.34	0.003065	7.50	400.19	0.51
Sycamore Creek	Reach-1	2892.00*	55-year	3000.00	15.01	22.38	19.60	23.16	0.002631	7.10	422.62	0.47
Sycamore Creek	Reach-1	2864.00*	55-year	3000.00	14.71	22.30	19.14	23.00	0.002279	6.73	445.49	0.44
Sycamore Creek	Reach-1	2836	55-year	3000.00	14.42	22.22	18.69	22.86	0.002002	6.41	468.28	0.40
Sycamore Creek	Reach-1	2806	Indio Muerto	Bridge								
Sycamore Creek	Reach-1	2770	55-year	3000.00	14.40	21.58	18.67	22.33	0.002586	6.96	430.80	0.46
Sycamore Creek	Reach-1	2744.46*	55-year	3000.00	14.16	21.42	18.53	22.20	0.002648	7.10	422.80	0.47
Sycamore Creek	Reach-1	2718.91*	55-year	3000.00	13.93	21.26	18.41	22.07	0.002722	7.23	415.04	0.48
Sycamore Creek	Reach-1	2693.36*	55-year	3000.00	13.69	21.09	18.29	21.93	0.002790	7.35	408.25	0.48
Sycamore Creek	Reach-1	2667.82*	55-year	3000.00	13.45	20.92	18.14	21.79	0.002863	7.46	401.97	0.49
Sycamore Creek	Reach-1	2642.27*	55-year	3000.00	13.21	20.76	18.01	21.65	0.002942	7.57	396.09	0.50
Sycamore Creek	Reach-1	2616.73*	55-year	3000.00	12.98	20.58	17.89	21.50	0.003026	7.68	390.55	0.51
Sycamore Creek	Reach-1	2591.18*	55-year	3000.00	12.74	20.41	17.75	21.35	0.003103	7.77	386.02	0.51
Sycamore Creek	Reach-1	2565.64*	55-year	3000.00	12.50	20.24	17.59	21.20	0.003160	7.84	382.66	0.52
Sycamore Creek	Reach-1	2540.09*	55-year	3000.00	12.26	20.08	17.42	21.04	0.003202	7.89	380.22	0.52
Sycamore Creek	Reach-1	2514.55*	55-year	3000.00	12.03	19.92	17.26	20.89	0.003210	7.92	378.88	0.52
Sycamore Creek	Reach-1	2489	55-year	3000.00	11.79	19.77	17.07	20.74	0.003154	7.91	379.30	0.52
Sycamore Creek	Reach-1	2439.80*	55-year	3000.00	11.54	19.20	17.23	20.37	0.004007	8.68	345.71	0.59
Sycamore Creek	Reach-1	2390.60*	55-year	3000.00	11.29	18.51	17.08	19.91	0.005002	9.47	316.84	0.67
Sycamore Creek	Reach-1	2341.40*	55-year	3000.00	11.03	17.70	16.71	19.34	0.006140	10.27	292.33	0.76
Sycamore Creek	Reach-1	2292.20*	55-year	3000.00	10.78	17.17	16.05	18.80	0.005883	10.24	293.15	0.74
Sycamore Creek	Reach-1	2243	55-year	3000.00	10.53	16.69	15.40	18.19	0.006420	9.82	305.41	0.70
Sycamore Creek	Reach-1	2213	Puente Gorda	Bridge								
Sycamore Creek	Reach-1	2180	55-year	3000.00	8.87	15.53	13.76	16.82	0.005082	9.10	329.52	0.63
Sycamore Creek	Reach-1	2039	55-year	3000.00	8.75	14.19	13.03	15.51	0.006155	9.21	325.61	0.70
Sycamore Creek	Reach-1	1911	55-year	3000.00	7.39	14.14	10.75	14.50	0.001045	4.78	627.14	0.34
Sycamore Creek	Reach-1	1715	Bridge									
Sycamore Creek	Reach-1	1565	55-year	3000.00	5.75	13.44	9.26	13.80	0.000883	4.80	627.76	0.31
Sycamore Creek	Reach-1	1486	55-year	3000.00	5.50	13.44	10.41	13.61	0.000745	4.25	1376.55	0.27
Sycamore Creek	Reach-1	1438	55-year	3000.00	5.20	13.42	9.98	13.56	0.000589	3.81	1456.23	0.24
Sycamore Creek	Reach-1	1385	55-year	3000.00	4.67	13.19	9.49	13.44	0.000936	4.82	1101.00	0.29
Sycamore Creek	Reach-1	1350	Bridge									
Sycamore Creek	Reach-1	1318	55-year	3000.00	4.67	13.05	9.50	13.28	0.000871	4.66	1135.92	0.28
Sycamore Creek	Reach-1	1227	55-year	3000.00	4.10	12.98	8.92	13.16	0.000662	4.18	1203.84	0.25
Sycamore Creek	Reach-1	1190	Bridge									
Sycamore Creek	Reach-1	1150	55-year	3000.00	4.10	12.94	8.93	13.05	0.000439	3.40	1412.58	0.20
Sycamore Creek	Reach-1	1005	55-year	3000.00	4.33	12.27	9.16	12.76	0.001596	6.15	651.08	0.38
Sycamore Creek	Reach-1	814	55-year	3000.00	3.76	10.49	8.58	11.72	0.003995	8.92	336.26	0.61
Sycamore Creek	Reach-1	783	Bridge									
Sycamore Creek	Reach-1	749	55-year	3000.00	3.75	9.76	8.57	11.31	0.005650	9.99	300.30	0.72
Sycamore Creek	Reach-1	513	55-year	3000.00	2.00	8.73	6.34	9.45	0.002189	6.84	438.66	0.49
Sycamore Creek	Reach-1	452	Bridge									
Sycamore Creek	Reach-1	403	55-year	3000.00	1.90	6.57	6.57	8.65	0.010202	11.58	259.13	1.00

Sycamore Creek Reach-1













RS = 6446




RS = 6219










RS = 6167




RS = 5490









RS = 4920





RS = 4553




RS = 4552









RS = 4475





RS = 4291




RS = 4031












RS = 3750




RS = 3465




Legend	
EG 55-year	-----
WS 55-year	—————
Crit 55-year+
Ground	—■—
Bank Sta	●








RS = 3423




RS = 3381









RS = 3287





RS = 3261.57*





RS = 3236.14*

























RS = 3032































RS = 2770















RS = 2642.27*




RS = 2616.73*









Legend	
EG 55-year	Green dashed line
WS 55-year	Blue solid line
Crit 55-year	Red dotted line with cross
Ground	Grey line with square markers
Levee	Pink line with square markers
Ineff	Green triangle with vertical arrow
Bank Sta	Red circle







RS = 2489





RS = 2439.80*







RS = 2341.40*







RS = 2243









RS = 2180




RS = 2039




RS = 1911




RS = 1715 BR







RS = 1565




RS = 1486





RS = 1438




RS = 1385










RS = 1318




RS = 1227














RS = 1005





















RS = 403





Appendix B – Soil Investigation Logs and Testing

The purpose of the compilation of soils data and testing is for maintaining a record for projects that occurred within close proximity to Sycamore Creek.





Cabrillo Blvd





Log of Test Boring Plan Sheet



DIST.	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
05	SB	225	6.3/6.7	44	44

R.W. Fox
 CERTIFIED ENGINEERING GEOLOGIST
 No. 78
 Exp. 8-15-95
 REGISTERED GEOLOGIST
 STATE OF CALIFORNIA

11-20-95
 PLANS APPROVAL DATE

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.



PLAN
 1" = 20'



AS BUILT

CORRECTIONS BY GREG CHELINI

CONTRACT NO. 05-339104

DATE 11-21-97
 D.P. 11-30-98

NOTE:
 UNCONFINED COMPRESSIVE STRENGTH APPROXIMATED BY HAND PENETROMETER TEST.



LEGEND OF BORING OPERATIONS

LEGEND OF EARTH MATERIALS

CONSISTENCY CLASSIFICATION FOR SOILS

LEGEND OF BORING OPERATIONS (continued):
 2 1/4" CORE PENETROMETER
 SAMPLE (DRY)
 BORING (WET)
 ALBER
 TEST PIT
 DIAMOND CORE BORING
 JET BORING
 ELECTRONIC CORE PENETROMETER

LEGEND OF EARTH MATERIALS (continued):
 CLAYEY SILT
 SILT
 SAND
 GRAVEL
 ORGANIC MATTER
 FILL MATERIAL
 IGNEOUS ROCK
 SEDIMENTARY ROCK
 METAMORPHIC ROCK

CONSISTENCY CLASSIFICATION FOR SOILS (continued):
 According to the Standard Penetration Test
 Penetration Index (Blows / Ft)
 Cohesive
 Granular
 Very soft
 Soft
 Slightly compact
 Compact
 Dense
 Very dense
 Very hard

OFFICE OF TRANSPORTATION MATERIALS & RESEARCH ENGINEERING GEOLOGY BRANCH

FIELD INVESTIGATION BY: B. KOMORNICZAK

State of CALIFORNIA DEPARTMENT OF TRANSPORTATION

DIVISION OF STRUCTURES STRUCTURE DESIGN 6

BRIDGE NO. 51-132
 POST MILE 6.51

SYCAMORE CREEK BRIDGE (REPLACE)
 LOG OF TEST BORINGS

ORIGINAL SCALE IN INCHES FOR REDUCED PLANS 0 1 2 3

CU 05
 EA 339101

DISREGARD PRINTS BEARING EARLIER REVISION DATES

REVISION DATES (PRELIMINARY STAGE ONLY)

SHEET 10 OF 10



US 101





Log of Test Boring Plan Sheet






DIST	COUNTY	ROUTE	KILOMETER POST TOTAL PROJECT	SHEET No	TOTAL SHEETS
05	SB	101	17.4/20.6	510	652

3-17-05
 REGISTERED CIVIL ENGINEER
 Sara von Schwind
 No. C050789
 Exp. 9-30-05
 CIVIL
 STATE OF CALIFORNIA

9-17-07
 PLANS APPROVAL DATE

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.




LEGEND OF EARTH MATERIALS

GRAVEL	CLAY	SAND	SILT
LEAN CLAY	CLAYEY SAND	SANDY SILT	SILTY SAND
POORLY GRADED SAND	CLAYEY SILT	SANDY CLAY	SILTY CLAY
CLAYEY SAND WITH GRAVELS	CLAYEY SILT WITH SAND	SANDY CLAY WITH SILT	SILTY CLAY WITH SAND


CONSISTENCY CLASSIFICATION FOR SOILS

Very Loose	Loose	Medium Dense	Dense
Very Compressible	Compressible	Non-Compressible	Very Non-Compressible

BENCH MARK
 SB101 pm12.30 = NAVD88 4.962 m
 SB101 pm12.19 = NAVD88 3.726 m



Note: Boring B1-04 was conducted using a CME Automatic Hammer.



15+80	15+84	15+88	PROFILE
ENGINEERING SERVICES		GEOTECHNICAL SERVICES	
DRAWN BY: F. Nguyen 9/04		FIELD INVESTIGATION BY: S. von Schwind, W. Hoon	
CHECKED BY: S. von Schwind		STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	

BRIDGE NO. 51-0332		SYCAMORE CREEK BR (REPLACE)	
KILOMETER POST 19.8		LOG OF TEST BORINGS 1 OF 2	



DIST	COUNTY	ROUTE	KILOMETER POST TOTAL PROJECT	SHEET No	TOTAL SHEETS
05	SB	101	17.4/20.6	511	652


3-17-05
REGISTERED CIVIL ENGINEER

9-17-07
PLANS APPROVAL DATE

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

REGISTERED PROFESSIONAL ENGINEER
Sara von Schwind
No. C050789
Exp. 9-30-05
CIVIL
STATE OF CALIFORNIA

FOR PLAN VIEW, SEE
"LOG OF TEST BORINGS" 1 OF 2



LEGEND OF EARTH MATERIALS

CONSISTENCY CLASSIFICATION FOR SOILS

Moisture content (w) and Plasticity Index (PI) classification chart.



PROFILE

HOR. 1:100 VER. 1:100

15+80 16+00 16+20 16+40

ALL DIMENSIONS ARE IN METERS UNLESS OTHERWISE SHOWN

ENGINEERING SERVICES	GEOTECHNICAL SERVICES	FIELD INVESTIGATION BY:	STATE OF CALIFORNIA	DIVISION OF STRUCTURES	BRIDGE NO. 51-0332	SYCAMORE CREEK BR (REPLACE)
DRAWN BY: F. Nguyen 9/04	S. von Schwind W. Hoon, D. Appelbaum		DEPARTMENT OF TRANSPORTATION	STRUCTURE DESIGN 6	KILOMETER POST 19.8	
CHECKED BY: S. von Schwind						LOG OF TEST BORINGS 2 OF 2




Punta Gorda Bridge Project






Log of Test Boring and Cone Penetrometer Testing








LOCATION:
SURFACE EL: 20.0ft +/- (MSL)
COMPLETION DEPTH: 48.6ft
TESTDATE: 3/31/2010

EXPLORATION METHOD: Cone Penetrometer
PERFORMED BY: Fugro Geosciences
REVIEWED BY: K Robinson

LOG OF CPT NO: CPT-2
Sycamore Creek Enhancement Project
Santa Barbara, California

N:\Projects\3037_PenfieldSmith\3037-047_SycamoreCreek\Explorations\CPT\2010\Logs\2010_04_29_Logs_Su_Fr.mxd, 04/29/2010, CDean




LOCATION:
 SURFACE EL: 17.5ft +/- (MSL)
 COMPLETION DEPTH: 59.6ft
 TESTDATE: 4/1/2010

EXPLORATION METHOD: Cone Penetrometer
 PERFORMED BY: Fugro Geosciences
 REVIEWED BY: K Robinson

LOG OF CPT NO: CPT-3
 Sycamore Creek Enhancement Project
 Santa Barbara, California

N:\Projects\3037_PenfieldSmith\3037-047_SycamoreCreek\Explorations\CPT\2010\Logs\04_29_Logs_Su_Fr.mxd, 04/29/2010, CDean




LOCATION:
 SURFACE EL: 16.0ft +/- (MSL)
 COMPLETION DEPTH: 50.5ft
 TESTDATE: 4/1/2010

EXPLORATION METHOD: Cone Penetrometer
 PERFORMED BY: Fugro Geosciences
 REVIEWED BY: K Robinson

LOG OF CPT NO: CPT-4
 Sycamore Creek Enhancement Project
 Santa Barbara, California

N:\Projects\3037_PenfieldSmith\3037-047_SycamoreCreekExplorations\CPT\2010\Logs\2010_04_29_Logs_Su_Fr\MXD\Logs_VK10C_Su_Fr.mxd, 04/29/2010, CDean

COLOR LEGEND FOR FRICTION RATIO TRACES



Zone	Soil Behavior Type	U.S.C.S.
1	Sensitive Fine-grained	OL-CH
2	Organic Material	OL-OH
3	Clay	CH
4	Silty Clay to Clay	CL-CH
5	Clayey Silt to Silty Clay	MH-CL
6	Sandy Silt to Clayey Silt	ML-MH
7	Silty Sand to Sandy Silt	SM-ML
8	Sand to Silty Sand	SM-SP
9	Sand	SW-SP
10	Gravelly Sand to Sand	SW-GW
11	Very Stiff Fine-grained *	CH-CL
12	Sand to Clayey Sand *	SC-SM

*overconsolidated or cemented

CPT CORRELATION CHART
 (Robertson and Campanella, 1988)

KEY TO CPT LOGS
 Sycamore Creek Enhancement Project
 Santa Barbara, California

N:\Projects\3037_PenfieldSmith\3037-047_SycamoreCreek\Explorations\CPT\2010\Logs\2010_04_29_Logs_Su_Fr\WXDIPlate_A5_KeytoCPT-RC88.mxd, 07/27/10, CDean



ELEVATION, ft	DEPTH, ft	MATERIAL SYMBOL	SAMPLE NO.	SAMPLERS	SAMPLER BLOW COUNT	LOCATION: See Plate 2 - Subsurface Exploration Location PlanN 1,979,586 E 6,058,062 SURFACE EL: 18 ft +/- (rel. NAVD 88 datum)	UNIT WET WEIGHT, pcf	UNIT DRY WEIGHT, pcf	WATER CONTENT, %	% PASSING #200 SIEVE	LIQUID LIMIT, %	PLASTICITY INDEX, %	UNDRAINED SHEAR STRENGTH, S _u , ksf
						MATERIAL DESCRIPTION							
-16	2	[diagonal lines]	A			ARTIFICIAL FILL (af) Sandy Lean CLAY (CL): dark brown (7.5YR3/2), moist, fine sand, with roots and some fine gravel							
-14	4	[diagonal lines]			(15)	- turns to brown (7.5YR4/2) with dark brown mottles, with yellow sand inclusions, piece of clay tile	129	112	15				
-12	6	[diagonal lines]				Silty CLAY (CL-ML) to Sandy Lean CLAY (CL) with sand and gravel lenses: stiff, brown (7.5YR4/2 to 4/3), moist, fine to medium sand							p 2.3
-10	8	[diagonal lines]				▽							
-8	10	[diagonal lines]			(10)	- becomes medium stiff at ~9-1/2', dark gray (7.5YR4/1) silty clay, wet - sand lens at ~10', silty fine sand grades to well-graded sand with gravel, fine to coarse sand, fine gravel	126	101 107	25 19	61			t 0.6
-6	12	[diagonal lines]											p 2.5
-4	14	[diagonal lines]			(17)	- clayey sand lens at ~14-1/2', medium dense, fine to coarse sand, with some fine gravel, grades to sandy clay at ~15'	133	114	17	22			
-2	16	[diagonal lines]											
0	18	[diagonal lines]				- fine gravel lense at ~20', subangular gravel							
-2	20	[diagonal lines]											
-4	22	[diagonal lines]											
-6	24	[diagonal lines]			(13)	- silty sand lens at ~24-1/2', loose, with charcoal inclusions and staining, fine to medium sand, grades to sandy clayey silt at ~26'	137 129	116 108	18 20	48			u 1.6
-8	26	[diagonal lines]											t 0.7
-10	28	[diagonal lines]				Silty SAND with gravel (SM) with sandy clay and sandy silt lenses: medium dense, brown (7.5YR4/4), wet, medium sand, some coarse, fine to coarse gravel ~1" diameter - sandy lean clay lens at ~29-1/2'	134	110	21				
-12	30	[diagonal lines]			(24)								
-14	32	[diagonal lines]											
-16	34	[diagonal lines]											
-18	36	[diagonal lines]			31				21				
-20	38	[diagonal lines]											
		[diagonal lines]			4	- more gravels in drilling at ~39'							

The log and data presented are a simplification of actual conditions encountered at the time of drilling at the drilled location. Subsurface conditions may differ at other locations and with the passage of time.

COMPLETION DEPTH: 101.0 ft

DEPTH TO WATER: 8.5 ft

BACKFILLED WITH: Grout

DRILLING DATE: April 23, 2010

GW measured in hollow-stem auger before beginning mud rotary

DRILLING METHOD: 6-inch-dia. Mud Rotary Wash

HAMMER TYPE: Automatic Trip

DRILLED BY: S/G Drilling Co.

LOGGED BY: K Robinson

CHECKED BY: G S Denlinger

LOG OF BORING NO. DH-1

Sycamore Creek Enhancement Project
Santa Barbara, California

PLATE A-6a



ELEVATION, ft	DEPTH, ft	MATERIAL SYMBOL	SAMPLE NO.	SAMPLERS	SAMPLER BLOW COUNT	LOCATION: See Plate 2 - Subsurface Exploration Location Plan N 1,979,586 E 6,058,062	UNIT WET WEIGHT, pcf	UNIT DRY WEIGHT, pcf	WATER CONTENT, %	% PASSING #200 SIEVE	LIQUID LIMIT, %	PLASTICITY INDEX, %	UNDRAINED SHEAR STRENGTH, S_u , ksf
						SURFACE EL: 18 ft +/- (rel. NAVD 88 datum)							
						MATERIAL DESCRIPTION							
-24	42					- lens of sandy silt to silt with sand at ~40-1/2', soft - gravels encountered in drilling between ~40-44'			17				
-26	44				(15)	Lean CLAY (CL): stiff, brown (7.5YR4/3), wet, with fine gravel at ~44-1/2', with charcoal inclusions, becomes sandy at ~46'	131 130	109 108	20 21		27	11	u 0.7 t 0.5 p 2.8
-28	46												
-30	48												
-32	50												
-34	52					Silty SAND (SM): medium dense, brown (7.5YR4/3), wet, medium sand, with some fine gravel and trace coarse gravel at ~56'							
-36	54				(40)								
-38	56					- ~1-1/2' gravel layer at ~57' during drilling		108	18				
-40	58												
-42	60				(44)	- grades to clayey sand (SC), gray (7.5YR5/1), with black striping ~1" thick, some iron oxide staining	128	112	15				
-44	62					Sandy Lean CLAY (CL): very stiff, dark gray to gray (7.5Y4/1 to 5/1), wet, with few fine dusky yellow gravels							p 4.5+
-46	64				(43)								
-48	66					- turns to clayey fine sand at ~65', medium dense, yellow brown (10YR5/4) with gray and olive gray (5Y5/2) pockets and lenses, some medium sand, some fine gravel	139	121	15				u 2.9
-50	68												
-52	70				(39)	Fat CLAY (CH): very stiff, greenish gray (10Y6/1), wet, with abundant iron oxide inclusions and staining	127	102	25				u 3.6 p 4.5+
-54	72												
-56	74				(61)	Clayey SAND (SC): dense, olive gray to light olive gray (5Y5/2 to 7/2), wet, with iron oxide staining and charcoal staining, very fine sand	129 133	108 112	19 19				
-58	76												
-60	78					Poorly graded SAND with silt (SP-SM) with occasional gravel lenses: very dense, light yellow brown (10YR6/4), wet, with pockets of dark yellow brown							
					79								

The log and data presented are a simplification of actual conditions encountered at the time of drilling at the drilled location. Subsurface conditions may differ at other locations and with the passage of time.

COMPLETION DEPTH: 101.0 ft

DEPTH TO WATER: 8.5 ft

BACKFILLED WITH: Grout

DRILLING DATE: April 23, 2010

GW measured in hollow-stem auger before beginning mud rotary

DRILLING METHOD: 6-inch-dia. Mud Rotary Wash

HAMMER TYPE: Automatic Trip

DRILLED BY: S/G Drilling Co.

LOGGED BY: K Robinson

CHECKED BY: G S Denlinger

LOG OF BORING NO. DH-1
Sycamore Creek Enhancement Project
Santa Barbara, California



ELEVATION, ft	DEPTH, ft	MATERIAL SYMBOL	SAMPLE NO.	SAMPLERS	SAMPLER BLOW COUNT	LOCATION: See Plate 2 - Subsurface Exploration Location Plan N 1,979,586 E 6,058,062 SURFACE EL: 18 ft +/- (rel. NAVD 88 datum)	UNIT WET WEIGHT, pcf	UNIT DRY WEIGHT, pcf	WATER CONTENT, %	% PASSING #200 SIEVE	LIQUID LIMIT, %	PLASTICITY INDEX, %	UNDRAINED SHEAR STRENGTH, S _u , ksf
						MATERIAL DESCRIPTION							
						(10YR4/6), fine to medium sand			22				
-64	82			X									
-66	84				72								
-68	86			X		- gravel lens at ~86', ~3" thick, well-graded gravel with clay, yellow brown (10YR5/8), fine gravel ~1/4" diameter, some 1/2" diameter				6			
-70	88												
-72	90			X	65	- gravel lens at ~90', ~4" thick, silty sand with fine gravel, subrounded, yellow brown (10YR5/8)							
-74	92					- ~1' gravel lens at ~92' during drilling							
-76	94												
-78	96					- with few fine gravels ~1/2" diameter at ~95'							
-80	98					- ~3' of gravels and cobbles at ~97' during drilling							
-82	100					SILT (ML): very stiff, yellow brown (10YR5/8), wet, turns to sandy silt at ~100' with silt lenses							
-84	102					- turns to gravelly silty clay (CL-ML) at ~100-1/2', fine gravel							
-86	104												
-88	106												
-90	108												
-92	110												
-94	112												
-96	114												
-98	116												
-100	118												

The log and data presented are a simplification of actual conditions encountered at the time of drilling at the drilled location. Subsurface conditions may differ at other locations and with the passage of time.

COMPLETION DEPTH: 101.0 ft

DEPTH TO WATER: 8.5 ft

BACKFILLED WITH: Grout

DRILLING DATE: April 23, 2010

GW measured in hollow-stem auger before beginning mud rotary

DRILLING METHOD: 6-inch-dia. Mud Rotary Wash

HAMMER TYPE: Automatic Trip

DRILLED BY: S/G Drilling Co.

LOGGED BY: K Robinson

CHECKED BY: G S Denlinger

LOG OF BORING NO. DH-1
Sycamore Creek Enhancement Project
Santa Barbara, California



ELEVATION, ft	DEPTH, ft	MATERIAL SYMBOL	SAMPLE NO.	SAMPLERS	SAMPLER BLOW COUNT	LOCATION: See Plate 2 - Subsurface Exploration Location Plan N 1,979,554 E 6,058,123	UNIT WET WEIGHT, pcf	UNIT DRY WEIGHT, pcf	WATER CONTENT, %	% PASSING #200 SIEVE	LIQUID LIMIT, %	PLASTICITY INDEX, %	UNDRAINED SHEAR STRENGTH, S _u , ksf
						SURFACE EL: 16 ft +/- (rel. NAVD 88 datum)							
						MATERIAL DESCRIPTION							
-14	2	[Symbol]				Silty SAND (SM): dark brown (7.5YR3/2), moist, with gravel, grades to clayey sand/sandy lean clay at ~2', fine grained, subrounded							
-12	4	[Symbol]				Sandy Lean CLAY (CL): soft, brown (7.5YR4/2), moist, fine sand, turns to silty clay, dark brown with charcoal inclusions near shoe, dark brown, with roots, wet							t 0.5
-10	6	[Symbol]		(5)			90	28	68				
-8	8	[Symbol]				Silty CLAY with sand (CL-ML): stiff, brown (7.5YR4/2), wet, fine sand							
-6	10	[Symbol]		(16)			127	104	22		26	6	t 0.5
-4	12	[Symbol]				Sandy Fat CLAY (CH): very stiff, brown (7.5YR4/4), wet, with gray brown mottles, with some fine gravel, charcoal inclusions, fine sand							
-2	14	[Symbol]		(25)			111	17					p 3.0
0	16	[Symbol]											
-2	18	[Symbol]											
-4	20	[Symbol]		(20)		Sandy Lean CLAY (CL): stiff, strong brown (7.5YR4/6), wet	99	85	17				
-6	22	[Symbol]				- poorly-graded sand with clay between 20-25'							p 2.0
-8	24	[Symbol]											
-10	26	[Symbol]		(15)		Sandy SILT (ML): stiff, strong brown (7.5YR4/6), wet, with poorly-graded sand lens at 26.25', fine sand, with charcoal staining, strong brown lean clay at 26.5'							
-12	28	[Symbol]											
-14	30	[Symbol]											
-16	32	[Symbol]											
-18	34	[Symbol]											
-20	36	[Symbol]											
-22	38	[Symbol]											

The log and data presented are a simplification of actual conditions encountered at the time of drilling at the drilled location. Subsurface conditions may differ at other locations and with the passage of time.

COMPLETION DEPTH: 26.5 ft

DEPTH TO WATER: 7.5 ft

BACKFILLED WITH: Cuttings

DRILLING DATE: April 22, 2010

GW measured ~24 hours after completion of drilling

DRILLING METHOD: 8-inch-dia. Hollow Stem Auger

HAMMER TYPE: Automatic Trip

DRILLED BY: S/G Drilling Co.

LOGGED BY: K Robinson

CHECKED BY: G S Denlinger

LOG OF BORING NO. DH-2
Sycamore Creek Enhancement Project
Santa Barbara, California



ELEVATION, ft	DEPTH, ft	MATERIAL SYMBOL	SAMPLE NO.	SAMPLERS	SAMPLER BLOW COUNT	LOCATION: See Plate 2 - Subsurface Exploration Location PlanN 1,979,793 E 6,057,896	UNIT WET WEIGHT, pcf	UNIT DRY WEIGHT, pcf	WATER CONTENT, %	% PASSING #200 SIEVE	LIQUID LIMIT, %	PLASTICITY INDEX, %	UNDRAINED SHEAR STRENGTH, S _v , ksf
						SURFACE EL: 21 ft +/- (rel. NAVD 88 datum)							
						MATERIAL DESCRIPTION							
	20					ARTIFICIAL FILL (af) Base Material: 4" asphalt concrete over approximately 7" base							
	18					Silty SAND (SM)/Clayey SAND (SC): brown (7.5YR3/3), slightly moist, fine to medium sand, some fine grained							
	16			(10)		Silty SAND (SM): firm to loose, dark brown and brown (7.5YR4/4), moist, mottled, some black inclusions, fine sand	125	108	16	48			
	14												
	12			(3)		Sandy Lean CLAY (CL): very soft, brown (7.5YR4/3), wet, fine sand, with some gravel near 10'	123	97	27	70	21	1	10.6
	10												
	8					Sandy, Silty CLAY (CL-ML): very stiff, brown (7.5YR4/2) to gray brown, wet, fine sand, fine to coarse gravel, some cobbles							
	6			(25)									
	4					Clayey SAND with gravel (SC) to Well-graded GRAVEL with clay (GW-GC): medium dense, brown, wet			11				
	2					Sandy, Silty CLAY (CL-ML): firm, brown (7.5YR4/2), wet, trace fine gravel, fine sand							
	0			(11)		Silty SAND (SM): brown, trace fine charcoal and red inclusions							
	-2												
	-4			(34)									
	-6												
	-8												
	-10												
	-12												
	-14												
	-16												
	-18												

The log and data presented are a simplification of actual conditions encountered at the time of drilling at the drilled location. Subsurface conditions may differ at other locations and with the passage of time.

COMPLETION DEPTH: 25.0 ft
 DEPTH TO WATER: 5.3 ft
 BACKFILLED WITH: Cuttings, patched with concrete dyed black
 DRILLING DATE: April 23, 2010
 GW measured in adjacent CPT

DRILLING METHOD: 8-inch-dia. Hollow Stem Auger
 HAMMER TYPE: Automatic Trip
 DRILLED BY: S/G Drilling Co.
 LOGGED BY: K Robinson
 CHECKED BY: G S Denlinger

LOG OF BORING NO. DH-3
 Sycamore Creek Enhancement Project
 Santa Barbara, California



ELEVATION, ft	DEPTH, ft	MATERIAL SYMBOL	SAMPLE NO.	SAMPLES	BLOW COUNT / REC'D/DRIVE"	LOCATION: The drill hole location referencing local landmarks or coordinates	General Notes										
						SURFACE EL: Using local, MSL, MLLW or other datum	Soil Texture Symbol										
						MATERIAL DESCRIPTION	Sloped line in symbol column indicates transitional boundary										
-12	2	[Symbol]	1	[Symbol]	25	Well graded GRAVEL (GW)	<p>Samplers and sampler dimensions (unless otherwise noted in report text) are as follows:</p> <p>Symbol for:</p> <ol style="list-style-type: none"> SPT Sampler, driven 1-3/8" ID, 2" OD CA Liner Sampler, driven 2-3/8" ID, 3" OD CA Liner Sampler, disturbed 2-3/8" ID, 3" OD Thin-walled Tube, pushed 2-7/8" ID, 3" OD Bulk Bag Sample (from cuttings) CA Liner Sampler, Bagged Hand Auger Sample CME Core Sample Pitcher Sample Lexan Sample Vibracore Sample No Sample Recovered Sonic Soil Core Sample 										
-14	4	[Symbol]	2	[Symbol]	(25)	Poorly graded GRAVEL (GP)											
-16	6	[Symbol]	3	[Symbol]	(25)	Well graded SAND (SW)											
-18	8	[Symbol]	4	[Symbol]	(25)	Poorly graded SAND (SP)											
-20	10	[Symbol]	5	[Symbol]	(25)	Silty SAND (SM)											
-22	12	[Symbol]	6	[Symbol]	18"/30"	Clayey SAND (SC)											
-24	14	[Symbol]	7	[Symbol]		Silty, Clayey SAND (SC-SM)											
-26	16	[Symbol]	8	[Symbol]		Elastic SILT (MH)											
-28	18	[Symbol]	9	[Symbol]		SILT (ML)											
-30	20	[Symbol]	10	[Symbol]	20"/24"	Silty CLAY (CL-ML)											
-32	22	[Symbol]	11	[Symbol]	(25)	Fat CLAY (CH)											
-34	24	[Symbol]	12	[Symbol]	30"/30"	Lean CLAY (CL)											
-36	26	[Symbol]	13	[Symbol]	20"/24"	CONGLOMERATE											
-38	28	[Symbol]		[Symbol]		SANDSTONE	<p>Sampler Driving Resistance</p> <p>Number of blows with 140 lb. hammer, falling 30" to drive sampler 1 ft. after seating sampler 6"; for example,</p> <table border="1"> <thead> <tr> <th>Blows/ft</th> <th>Description</th> </tr> </thead> <tbody> <tr> <td>25</td> <td>25 blows drove sampler 12" after initial 6" of seating</td> </tr> <tr> <td>86/11"</td> <td>After driving sampler the initial 6" of seating, 36 blows drove sampler through the second 6" interval, and 50 blows drove the sampler 5" into the third interval</td> </tr> <tr> <td>50/6"</td> <td>50 blows drove sampler 6" after initial 6" of seating</td> </tr> <tr> <td>Ref/3"</td> <td>50 blows drove sampler 3" during initial 6" seating interval</td> </tr> </tbody> </table> <p>Blow counts for California Liner Sampler shown in ()</p> <p>Length of sample symbol approximates recovery length</p> <p>Classification of Soils per ASTM D2487 or D2488</p> <p>Geologic Formation noted in bold font at the top of interpreted interval</p> <p>Strength Legend</p> <ul style="list-style-type: none"> Q = Unconfined Compression u = Unconsolidated Undrained Triaxial t = Torvane p = Pocket Penetrometer m = Miniature Vane <p>Water Level Symbols</p> <ul style="list-style-type: none"> ▽ Initial or perched water level ∇ Final ground water level ↕ Seepages encountered <p>Rock Quality Designation (RQD) is the sum of recovered core pieces greater than 4 inches divided by the length of the cored interval.</p>	Blows/ft	Description	25	25 blows drove sampler 12" after initial 6" of seating	86/11"	After driving sampler the initial 6" of seating, 36 blows drove sampler through the second 6" interval, and 50 blows drove the sampler 5" into the third interval	50/6"	50 blows drove sampler 6" after initial 6" of seating	Ref/3"	50 blows drove sampler 3" during initial 6" seating interval
Blows/ft	Description																
25	25 blows drove sampler 12" after initial 6" of seating																
86/11"	After driving sampler the initial 6" of seating, 36 blows drove sampler through the second 6" interval, and 50 blows drove the sampler 5" into the third interval																
50/6"	50 blows drove sampler 6" after initial 6" of seating																
Ref/3"	50 blows drove sampler 3" during initial 6" seating interval																
-40	30	[Symbol]		[Symbol]		SILTSTONE											
-42	32	[Symbol]		[Symbol]		MUDSTONE											
-44	34	[Symbol]		[Symbol]		CLAYSTONE											
-46	36	[Symbol]		[Symbol]		BASALT											
-48	38	[Symbol]		[Symbol]		ANDESITE BRECCIA											
		[Symbol]		[Symbol]		Paving and/or Base Materials											

KEY TO TERMS & SYMBOLS USED ON LOGS




Laboratory Testing






DRILL HOLE	DEPTH, ft	SAMPLE NUMBER	MATERIAL DESCRIPTION	UWW/UDW MC FINES %		ATTERBERG LIMITS		COMPACTION TEST		DIRECT SHEAR		COMPRESSIVE STRENGTH TESTS		CORROSIIVITY TESTS				R-VALUE	EXPANSION INDEX	SAND EQUIVALENT (SE)	SPECIFIC GRAVITY
				pct	%	LL	PI	MAX DD pct	OPT MC %	C ksf	PHI deg	Qu _v ksf	S _{ph} (cell P _{rs.}) ksf	R	pH	Cl	So ₄ (%)				
DH-1	5.0	1A	Sandy Lean CLAY (CL)	129	112	15															
DH-1	6.0	1B	Lean CLAY (CL) to Silty CLAY (CL-ML)																		
DH-1	9.0																				
DH-1	10.0		Sandy Lean CLAY (CL)	126	101	25	61														
DH-1	10.5		Silty SAND (SM)	107	19				0.5	31											
DH-1	11.0																				
DH-1	15.0	3A	Clayey SAND (SC)			22															
DH-1	15.5	3B	Clayey SAND (SC)	133	114	17															
DH-1	25.0	4A	Silty SAND (SM)	137	116	18						1.6(3)									
DH-1	25.5	4B	Silty SAND (SM)	129	108	20															
DH-1	26.0	4C	Silty SAND (SM)			48															
DH-1	27.0																				
DH-1	30.0	5A	Sandy Lean CLAY (CL)	134	110	21															
DH-1	30.5	5B	Silty SAND (SM)																		
DH-1	35.0	6A	Silty SAND with gravel (SM)			21															
DH-1	40.0	7A	Silty SAND with gravel (SM)			17															
DH-1	45.0	8A	Lean CLAY (CL)	131	109	20							0.7(5.4)								
DH-1	45.5	8B	Lean CLAY (CL)	130	108	21		27	11												
DH-1	46.0																				
DH-1	55.5		Silty SAND (SM)	108	18					0.2	38										
DH-1	60.0	10A	Clayey SAND (SC)	128	112	15															
DH-1	61.0																				
DH-1	65.0	11A	Sandy Lean CLAY (CL)	139	121	15															
DH-1	70.0	12A	Fat CLAY (CH)	127	102	25															
DH-1	71.0																				
DH-1	75.0	13A	Clayey SAND (SC)	129	108	19															
DH-1	75.5	13B	Clayey SAND (SC)	133	112	19															
DH-1	80.0	14	Poorly-graded SAND with silt (SP-SM)			22															
DH-1	85.0	15A	Poorly-graded SAND with silt (SP-SM)				6														
DH-2	5.0																				

SUMMARY OF LABORATORY TEST RESULTS
Sycamore Creek Enhancement Project
Santa Barbara, California



LEGEND			CLASSIFICATION	ATTERBERG LIMITS TEST RESULTS		
	location	depth, ft		LIQUID LIMIT(LL)	PLASTIC LIMIT(PL)	PLASTICITY INDEX (PI)
○	DH-1	45.5	Lean CLAY (CL)	27	16	11
●	DH-2	10.5	Silty CLAY with sand (CL-ML)	26	20	6
△	DH-3	9.5	Sandy SILT (ML)	21	20	1


PLASTICITY CHART
 Sycamore Creek Enhancement Project
 Santa Barbara, California



GRAVEL		SAND			SILT or CLAY
Coarse	Fine	Coarse	Medium	Fine	

LEGEND			CLASSIFICATION		<u>C_c</u>	<u>C_u</u>
Symbol	(location)	(depth,ft)				
○	DH-1	15.0	Clayey SAND (SC)			
●	DH-1	85.0	Poorly-graded SAND with silt (SP-SM)	0.9	2.1	
△	DH-3	9.5	Sandy SILT (ML)			


GRAIN SIZE CURVES
 Sycamore Creek Enhancement Project
 Santa Barbara, California



GRAVEL		SAND			SILT or CLAY
Coarse	Fine	Coarse	Medium	Fine	


LEGEND			CLASSIFICATION	Cc	Cu
(location)	(depth,ft)				
○	G-1	0.0	Poorly graded SAND (SP)	1.2	3.1
●	G-2	0.0	Poorly graded SAND with silt (SP-SM)	0.9	3.1
△	G-3	0.0	Poorly graded SAND (SP)	1.0	3.2
▲	G-4	0.0	Poorly graded SAND with silt (SP-SM)	1.0	3.7
⊙	G-5	0.0	Poorly graded SAND with silt (SP-SM)	1.6	5.0
⊛	G-6	0.0	Poorly graded SAND with silt (SP-SM)	1.2	3.3

GRAIN SIZE CURVES
Sycamore Creek Enhancement Project
Santa Barbara, California




SAMPLE ID	Boring Number: DH-01	CLASSIFICATION	Sieve Size	% Passing	Other Parameters	
	Sample Number: #4A		3/8-in. (9.5mm)	---	Liquid Limit	---
Sample Depth: 25.0ft	No. 4 (4.75mm)		---	Plastic Limit	---	
USCS Classification: Silty SAND (SM); brown, wet	No. 10 (2.0mm)		---	Plasticity Index	---	
Sample Type: Ring	No. 30 (0.6mm)		---	Estimated Gs	2.81	
	No. 100 (0.150mm)		---			
	No. 200 (0.075mm)		---			
SAMPLE PROPERTIES	Water Content, %		18.2	TEST SUMMARY	Strain Rate, %/min	1.01
	Wet Density, pcf		137.1		Cell Pressure, ksf	3.0
	Dry Density, pcf	116.0	Deviator Stress at Failure, ksf		3.2	
	Saturation, %	100	Undrained Shear Strength, ksf		1.6	
	Void Ratio	0.51	Axial Strain at Failure, %		15.0	
	Diameter, in	2.367	Tested By:		JC	
	Height, in	4.950	Date Tested:		05.17.10	
	Height/Diameter	2.1				
SAMPLE IMAGES			REMARKS	Test Method: ASTM 2850.		


UNCONSOLIDATED, UNDRAINED TRIAXIAL TEST
 Sycamore Creek Enhancement Project
 Santa Barbara, California




SAMPLE ID	Boring Number: DH-01	CLASSIFICATION	Sieve Size	% Passing	Other Parameters		
	Sample Number: #8A		3/8-in. (9.5mm)	---	Liquid Limit	---	
SAMPLE PROPERTIES	Sample Depth: 45.0ft	TEST SUMMARY	No. 4 (4.75mm)	---	Plastic Limit	---	
	USCS Classification: Lean CLAY (CL): dark brown, wet		No. 10 (2.0mm)	---	Plasticity Index	---	
SAMPLE IMAGES	Sample Type: Ring	REMARKS	No. 30 (0.6mm)	---	Estimated Gs	2.7	
	Water Content, %		20.1	No. 100 (0.150mm)	---		
	Wet Density, pcf		131.4	No. 200 (0.075mm)	---		
	Dry Density, pcf		109.5	Strain Rate, %/min	1.00		
	Saturation, %		100	Cell Pressure, ksf	5.4		
	Void Ratio		0.54	Deviator Stress at Failure, ksf	1.5		
	Diameter, in		2.388	Undrained Shear Strength, ksf	0.7		
	Height, in		5.020	Axial Strain at Failure, %	15.0		
Height/Diameter	2.1	Tested By:	JC				
			Date Tested:	05.18.10			
			Test Method: ASTM 2850.				


UNCONSOLIDATED, UNDRAINED TRIAXIAL TEST
Sycamore Creek Enhancement Project
Santa Barbara, California




SAMPLE ID	Boring Number: DH-01	CLASSIFICATION	Sieve Size	% Passing	Other Parameters	
	Sample Number: #11A		3/8-in. (9.5mm)	---	Liquid Limit	---
SAMPLE PROPERTIES	Sample Depth: 65.0ft	TEST SUMMARY	No. 4 (4.75mm)	---	Plastic Limit	---
	USCS Classification: Sandy Lean CLAY (CL): dark yellowish brown, wet		No. 10 (2.0mm)	---	Plasticity Index	---
SAMPLE IMAGES	Sample Type: Ring	REMARKS	No. 30 (0.6mm)	---	Estimated G _s	2.71
			No. 100 (0.150mm)	---	S _u from T _v , ksf	---
			No. 200 (0.075mm)	---	S _u from PP, ksf	2.8
	Water Content, % 14.8				Strain Rate, %/min	1.00
	Wet Density, pcf 138.5				Cell Pressure, ksf	7.8
	Dry Density, pcf 120.6				Deviator Stress at Failure, ksf	5.9
	Saturation, % 100				Undrained Shear Strength, ksf	2.9
	Void Ratio 0.40				Axial Strain at Failure, %	15.0
	Diameter, in 2.404				Tested By:	JC
	Height, in 4.940				Date Tested:	05.20.10
	Height/Diameter 2.1					
					Test Method: ASTM 2850.	

UNCONSOLIDATED, UNDRAINED TRIAXIAL TEST
Sycamore Creek Enhancement Project
Santa Barbara, California



SAMPLE ID	Boring Number: DH-01	CLASSIFICATION	Sieve Size	% Passing	Other Parameters
	Sample Number: #12A		3/8-in. (9.5mm)	---	Liquid Limit ---
SAMPLE PROPERTIES	Sample Depth: 70.0ft	TEST SUMMARY	No. 4 (4.75mm)	---	Plastic Limit ---
	USCS Classification: Fat CLAY (CH): olive gray with FeO ₂ mottling, wet		No. 10 (2.0mm)	---	Plasticity Index ---
SAMPLE IMAGES	Sample Type: Ring	REMARKS	No. 30 (0.6mm)	---	Estimated G _s 2.74
			No. 100 (0.150mm)	---	S _u from T _v , ksf ---
	Water Content, % 24.7		No. 200 (0.075mm)	---	S _u from PP, ksf 4.5+
	Wet Density, pcf 127.2				
	Dry Density, pcf 102.0				
	Saturation, % 100				
	Void Ratio 0.68				
	Diameter, in 2.396				
	Height, in 5.030				
	Height/Diameter 2.1				
					
					Test Method: ASTM 2850. Effective stress lower than requested: test run at overburden for 65.0ft.

UNCONSOLIDATED, UNDRAINED TRIAXIAL TEST
Sycamore Creek Enhancement Project
Santa Barbara, California



COHESION, ksf 0.5

ANGLE OF INTERNAL FRICTION, deg 31

LOCATION DH-1

DEPTH, ft 10.5

MOISTURE CONTENT, % 19


UNIT DRY WEIGHT, pcf 107

MATERIAL DESCRIPTION Silty SAND (SM)

SAMPLE CONDITION Driven Ring


DIRECT SHEAR TEST RESULTS
 Sycamore Creek Enhancement Project
 Santa Barbara, California

PLATE B-5a




COHESION, ksf	0.2
ANGLE OF INTERNAL FRICTION, deg	38
LOCATION	DH-1
DEPTH, ft	55.5
MOISTURE CONTENT, %	18
UNIT DRY WEIGHT, pcf	108
MATERIAL DESCRIPTION	Silty SAND (SM)
SAMPLE CONDITION	Driven Ring

DIRECT SHEAR TEST RESULTS
 Sycamore Creek Enhancement Project
 Santa Barbara, California




COHESION, ksf	0.1
ANGLE OF INTERNAL FRICTION, deg	34
LOCATION	DH-2
DEPTH, ft	5.5
MOISTURE CONTENT, %	28
UNIT DRY WEIGHT, pcf	90
MATERIAL DESCRIPTION	Clayey SAND (SC)
SAMPLE CONDITION	Driven Ring

DIRECT SHEAR TEST RESULTS
 Sycamore Creek Enhancement Project
 Santa Barbara, California




COHESION, ksf	0.5
ANGLE OF INTERNAL FRICTION, deg	23
LOCATION	DH-2
DEPTH, ft	15.5
MOISTURE CONTENT, %	17
UNIT DRY WEIGHT, pcf	111
MATERIAL DESCRIPTION	Sandy Fat CLAY (CH)
SAMPLE CONDITION	Driven Ring

DIRECT SHEAR TEST RESULTS
 Sycamore Creek Enhancement Project
 Santa Barbara, California



COHESION, ksf	0.0
ANGLE OF INTERNAL FRICTION, deg	37
LOCATION	DH-3
DEPTH, ft	9.5
MOISTURE CONTENT, %	27
UNIT DRY WEIGHT, pcf	97
MATERIAL DESCRIPTION	Sandy SILT (ML)
SAMPLE CONDITION	Ring Sample

DIRECT SHEAR TEST RESULTS
 Sycamore Creek Enhancement Project
 Santa Barbara, California



COHESION, ksf 0.2

ANGLE OF INTERNAL FRICTION, deg 31

LOCATION DH-3

DEPTH, ft 10

MOISTURE CONTENT, %

UNIT DRY WEIGHT, pcf

MATERIAL DESCRIPTION Sandy Lean CLAY (CL)

SAMPLE CONDITION Driven Ring

DIRECT SHEAR TEST RESULTS
 Sycamore Creek Enhancement Project
 Santa Barbara, California



Cacique and Soledad Bicycle and Pedestrian Bridges Project





Log of Test Boring Plan Sheet





Bengal Engineering
 250 Big Sur Drive
 Goleta CA 93117
 Telephone: (805) 563-0788

BORING NUMBER B-1

PAGE 1 OF 2

CLIENT City of Santa Barbara **PROJECT NAME** Cacique & Soledad Ped Bridges

PROJECT NUMBER _____ **PROJECT LOCATION** Cacique St @ Sycamore Creek

DATE STARTED 3/12/15 **COMPLETED** 3/12/15 **GROUND ELEVATION** 29.5 ft NAVD 88 **HOLE SIZE** 8" inches

DRILLING CONTRACTOR Choice Drilling **GROUND WATER LEVELS:**

DRILLING METHOD HSA - CME 75 **AT TIME OF DRILLING** 16.00 ft / Elev 13.50 ft

LOGGED BY E. Pongracz **CHECKED BY** _____ **AT END OF DRILLING** ---

NOTES Drill Road and Auto Hammer Used **AFTER DRILLING** ---

BENGAL GEOTECH BH V5 - BENGAL MOD GINT STD US LAB 2-10-10.GDT - 10/13/15 21:15 - C:\PROGRAM FILES (X86)\GINT\PROJECTS\CACIQUE-SOLEDAD.GPJ

ELEV (ft)	DEPTH (ft)	SAMPLE TYPE NUMBER	BLOW COUNTS (N VALUE)	GRAPHIC LOG	MATERIAL DESCRIPTION	UNDRAINED SHR STRENGTH (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ATTERBERG LIMITS			FINES CONTENT (%)	OTHER TESTS
									LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX		
0					3" Asphalt Concrete (AC) over 11" Aggregate Base (AB)								
					Earth Fill (ef) Alluvium (Qal)		11						
	5	AU 1											
		MC 2	5-7		Sandy Silt to Silty Sand (SM/ML) - brown to grayish brown, medium dense, slightly moist to moist, scattered charcoal fragments (alluvium)		13	101					
	10	SPT 3	2-3-5 (8)		Silt with some Sand (ML) - light brown, medium stiff, moist		10						
	15				Cuttings are finer-grained with increased moisture content								
		MC 4	11-12		Clayey Sand (SC) - orange to reddish brown, stiff, very moist to wet		15	117			48	SV	
	20	SPT 5	7-5-10 (15)		Beds (4"-6" thick) of mottled Silty Clay (CL) and fine-grained Clayey Sand (SC) - orange-brown, medium stiff to medium dense, very moist to wet		17						
	25	MC 6	6-11		Silty Clay (CL) to fine-grained Sandy Clay (SC) - reddish brown, medium stiff, very moist, mottled, occasional gravel clast		18	115	29	15	14		ATT
	30	SPT 7	1-2-2 (4)		Silty Sand (SM), Silty Clay (CL) and Clayey Sand with Gravel - light orange brown to dark brown, loose to slightly stiff, very moist to wet		24				55	SV	
	35	MC 8	30-50/5"		Silty Clay (CL) - rust orange to brown orange, hard, slightly moist, mottled								
	40				*Begin to add water to augers at 40' bg.								

(Continued Next Page)



Bengal Engineering
 250 Big Sur Drive
 Goleta CA 93117
 Telephone: (805) 563-0788

BORING NUMBER B-1

PAGE 2 OF 2

CLIENT City of Santa Barbara PROJECT NAME Cacique & Soledad Ped Bridges
 PROJECT NUMBER _____ PROJECT LOCATION Cacique St @ Sycamore Creek

C:\PROGRAM FILES (X86)\GINT\PROJECTS\CACIQUE-SOLEDAD.GPJ

ELEV (ft)	DEPTH (ft)	SAMPLE TYPE NUMBER	BLOW COUNTS (N VALUE)	GRAPHIC LOG	MATERIAL DESCRIPTION	UNDRAINED SHR STRENGTH (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ATTERBERG LIMITS			FINES CONTENT (%)	OTHER TESTS
									LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX		
40		SPT 9	2-4-7 (11)		Beds of fine-grained Silty Sand (SM/ML), Silty Clay (CL) and Clayey Silt (ML) - light brown to light orange brown, medium stiff to medium dense, very moist to wet		14 25	122					DS
-15	45	MC 10	6-8		Clayey Sand (SC) and Silty Clay (CL) - light orange brown, slightly dense to medium stiff, very moist to wet		20	110				58	SV
-20	50	SPT 11	10-12-17 (29)		4" to 6" thick beds of Sandy Clay (SC), Sandy Silt (ML) and Silty Clay (CL) with scattered gravel - light orange brown, stiff/dense, moist to very moist		17						
-25	55				*Rougher drilling to 60' bg. Probable gravels and cobbles (?)								
-30	60	MC 12	30-50/5"		Gravelly Clay (GC) with occasional small SS cobble - brown, very stiff, moist		13						
-35	65				*Driller notes continued rough drilling to ~66' bg, eases to botton of boring.								
-40	70	SPT 13	7-8-10 (18)		Silty, Sandy Clay (SC) with scattered small gravel - orange brown, stiff, moist, mottled in areas		22						

Boring backfilled with native materials, sealed with bentonite pellets and capped with cold-mix asphalt at surface.
 Bottom of borehole at 70.5 feet.



Bengal Engineering
 250 Big Sur Drive
 Goleta CA 93117
 Telephone: (805) 563-0788

BORING NUMBER B-2

PAGE 1 OF 1

CLIENT City of Santa Barbara **PROJECT NAME** Cacique & Soledad Ped Bridges

PROJECT NUMBER _____ **PROJECT LOCATION** Cacique St @ Sycamore Creek

DATE STARTED 3/12/15 **COMPLETED** 3/12/15 **GROUND ELEVATION** 29 ft NAVD 88 **HOLE SIZE** 8" inches

DRILLING CONTRACTOR Choice Drilling **GROUND WATER LEVELS:**

DRILLING METHOD HSA - CME 75 **AT TIME OF DRILLING** 18.00 ft / Elev 11.00 ft

LOGGED BY E. Pongracz **CHECKED BY** _____ **AT END OF DRILLING** ---

NOTES Drill Road and Auto Hammer Used **AFTER DRILLING** ---

BENGAL GEOTECH BH V5 - BENGAL MOD GINT STD US LAB 2-10-10.GDT - 10/13/15 21:15 - C:\PROGRAM FILES (X86)\GINT\PROJECTS\CACIQUE-SOLEDAD.GPJ

ELEV (ft)	DEPTH (ft)	SAMPLE TYPE NUMBER	BLOW COUNTS (N VALUE)	GRAPHIC LOG	MATERIAL DESCRIPTION	UNDRAINED SHR STRENGTH (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ATTERBERG LIMITS			FINES CONTENT (%)	OTHER TESTS
									LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX		
0					4" Asphalt Concrete (AC) over 9" Aggregate Base (AB)								
					Earth Fill (ef)								
					Alluvium (Qal)								
	5	MC 1	8-10		Sandy Silt / Silty Sand (ML/SM) with occasional rootlet and scattered charcoal fragments - brown, medium dense, slightly moist (alluvium)		7	106					DS
	10	SPT 2	3-5-6 (11)		same as above (ML/SM), medium stiff / medium dense, slightly moist to moist, occasional root		16						
	15	MC 3	7-8		Clayey fine Sand to Sandy Clay (SC) - reddish brown, medium stiff, very moist to wet		17	115					DS
	20	SPT 4	3-4-5 (9)		same as above (SC), slightly to medium stiff, wet to very moist, occasionally mottled		18						CHEM
	25	MC 5	9-10		Beds of Clayey Silt (ML), Silty Clay (CL), and fine-grained Sandy Clay / Clayey Sand (SC) - orange brown, medium stiff, very moist		19	115					
	30	SPT 6	6-11-18 (29)		Clayey Sand (SC) grading to Silty Clay (CL) - reddish brown, medium dense to hard (clay), moist to slightly moist, mottled		19		35	17	18		ATT
	35	MC 7	8-7		Sandy, Silty Clay (CL) - orange brown, stiff, moist, varicolored and mottled		19	114					
	40	SPT 8	6-8-10 (18)		Clayey Sand to Sandy Clay (SC) with occasional gravel and Silty Clay (CL) with trace Sand - orange brown to reddish brown, stiff, moist to very moist, mottled		21						
Boring backfilled with native materials, sealed with bentonite pellets and capped with cold-mix asphalt at surface. Bottom of borehole at 41.5 feet.													



Bengal Engineering
 250 Big Sur Drive
 Goleta CA 93117
 Telephone: (805) 563-0788

BORING NUMBER B-3

PAGE 1 OF 2

CLIENT City of Santa Barbara **PROJECT NAME** Cacique & Soledad Ped Bridges

PROJECT NUMBER _____ **PROJECT LOCATION** Cacique St @ Sycamore Creek

DATE STARTED 3/12/15 **COMPLETED** 3/12/15 **GROUND ELEVATION** 30 ft NAVD 88 **HOLE SIZE** 8" inches

DRILLING CONTRACTOR Choice Drilling **GROUND WATER LEVELS:**

DRILLING METHOD HSA - CME 75 **AT TIME OF DRILLING** 18.00 ft / Elev 12.00 ft

LOGGED BY E. Pongracz **CHECKED BY** _____ **AT END OF DRILLING** ---

NOTES Drill Road and Auto Hammer Used **AFTER DRILLING** ---

BENGAL GEOTECH BH V5 - BENGAL MOD GINT STD US LAB 2-10-10.GDT - 10/13/15 21:15 - C:\PROGRAM FILES (X86)\GINT\PROJECTS\CACIQUE-SOLEDAD.GPJ

ELEV (ft)	DEPTH (ft)	SAMPLE TYPE NUMBER	BLOW COUNTS (N VALUE)	GRAPHIC LOG	MATERIAL DESCRIPTION	UNDRAINED SHR STRENGTH (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ATTERBERG LIMITS			FINES CONTENT (%)	OTHER TESTS
									LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX		
30	0				Asphalt Concrete (AC) - 3" thick, no base below Earth Fill (ef) Alluvium (Qa)								
25	5	SPT 1	3-3-4 (7)		Sandy Silt/Silty Sand (SM/ML) with widely scattered root and charcoal fragments - brown, slightly dense, slightly moist		9						
		BULK AU 2					8				44	SV	
20	10	MC 3	6-9		Silty Sand to Sandy Silt (SM/ML) to Clayey Silt (ML) - light brown, medium dense / medium stiff, moist to wet		15	114					
15	15	SPT 4	5-6-10 (16)		Clayey Silt (ML) - reddish brown, stiff, moist, occasional mottles		16		28	17	11		ATT
10	20	MC 5	6-7		Clayey Silt (ML) to Silty Clay (CL) - reddish brown, medium stiff, moist to very moist		18	113					CONS
5	25	SPT 6	4-5-6 (11)		Silty Clay (CL) to Clayey Silt (ML) - orange brown, medium stiff to stiff, moist		21		30	19	11		ATT
0	30	MC 7	30-50/4"		*Free water probably encountered for first time while drilling to 30' below grade. Clay with Silt (CL) - brown, very stiff to hard, moist; in sharp contact with Silty Clay with Gravel (CL) - orange brown, very stiff, moist		13	125	34	20	14		CONS, ATT
-5	35	SPT 8	5-12-14 (26)		Silty Clay (CL) with scattered small gravel - light brown, very stiff, moist; in sharp contact with fine-grained Sand with Silt (SP) - brownish orange, dense, wet		22						
-10	40												

(Continued Next Page)



Bengal Engineering
 250 Big Sur Drive
 Goleta CA 93117
 Telephone: (805) 563-0788

BORING NUMBER B-3

PAGE 2 OF 2

CLIENT City of Santa Barbara PROJECT NAME Cacique & Soledad Ped Bridges
 PROJECT NUMBER _____ PROJECT LOCATION Cacique St @ Sycamore Creek

C:\PROGRAM FILES (X86)\GINT\PROJECTS\CACIQUE-SOLEDAD.GPJ

ELEV (ft)	DEPTH (ft)	SAMPLE TYPE NUMBER	BLOW COUNTS (N VALUE)	GRAPHIC LOG	MATERIAL DESCRIPTION	UNDRAINED SHR STRENGTH (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ATTERBERG LIMITS			FINES CONTENT (%)	OTHER TESTS
									LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX		
-10	40	MC 9	18-50/3"		Fine- to coarse-Sand with some silt (SW) grading to Gravelly Clay (GC) with fine sand and occasional small cobble - brownish orange, dense / stiff, moist to wet *Rougher drilling from 40' to 50' below grade.		15	122					
-15	45												
-20	50	SPT 10	12-30-32 (62)		Beds of Sand with Silt (SP), Gravelly Sand (SW), and Silty Clay with Gravel (CL/GC) - light brown, stiff / very dense, moist		14						
-25	55				*Driller notes hard drilling @ 55' below grade.								
-30	60	SPT 11	5-10-19 (29)		Bedded Silty Clay (CL), Clayey Silt with Gravel (ML) and fine-grained Sand with Silt (SP/SM) - orange brown to reddish brown, very stiff to dense, moist *Driller notes easier drilling on way to 70' bg.		20						
-35	65												
-40	70	SPT 12	18-27-34 (61)		4" to 6" thick beds of Gravelly Clay (GC), Gravelly Sand (SW) and Silty Sand (SM) with gravel - brownish orange, very dense / very stiff, moist, occasional small cobble of sandstone		14						

Boring backfilled with native materials, sealed with bentonite pellets and capped with cold-mix asphalt at surface.
 Bottom of borehole at 71.5 feet.



Laboratory Testing



SubSurface Designs Inc.

12848 Foothill Boulevard • Sylmar, California 91342
(818) 898-1595 • (Fax) 898-4003

April 14, 2015

PIN# 7000X

Bengal Engineereing, Inc.
250 Big Sur Drive
Goleta, California 93117

Subject: Cacique-Soledad Pedestrian Bridges
Results of Laboratory Testing

Dear Sirs:

Pursuant to your request please find attached hereto the results of soil engineering laboratory testing on the soil samples you provided. Sampling techniques, subsurface conditions, and other factors may vary across the subject site. Therefore, the test results may or may not be representative of the overall site conditions and care should be taken accordingly in interpreting the testing data provided. Interpretation of the laboratory test results and applications of the results on the design and construction of the project are beyond the scope of our work.

Services performed by this facility were conducted in a manner consistent with that level of care and skill ordinarily exercised by members of the profession currently practicing in the same locality under similar conditions. No other warranties are either expressed or implied.

If you have any questions, please do not hesitate to contact this office.

Respectfully submitted:
SUBSURFACE DESIGNS, INC.

Jon Mahn
Principal Engineer
RCE 60293



JEM/mm: 7000X

Dist: (2) Addressee
(1) File

LABORATORY TESTING RESULTS

Laboratory Testing Method

Laboratory Recapitulation - Table I-1

Chemical Test Results - Table I-2

Atterberg Limits

Sieve Analysis

Shear Strength Diagram

Consolidation Diagram

LABORATORY TESTING METHODS

Soil Classification

Soils are visually classified in accordance with the latest version of ASTM D 2488. Soils are classified in accordance with the latest version of ASTM D 2487 when testing, such as laboratory determination of particle-size characteristics, liquid limit, and plasticity index, is performed.

Moisture and Density Tests

The moisture content and in-place dry density of all undisturbed samples obtained were determined. The test results are presented in the Laboratory Recapitulation - Table I. Tests are performed in accordance with the latest version of ASTM D 2216.

Direct Shear Tests

Direct single-shear tests were performed on representative undisturbed samples to determine their strength characteristics. The desired normal load was applied to the specimen and allowed to come to equilibrium. The rate of deflection on the sample was between 0.01 and 0.005 inches per minute. All samples were saturated prior to shear testing. The results are plotted on the Shear Test Diagrams. Tests are performed in accordance with the latest version of ASTM D 3080.

Consolidation

Consolidation tests were performed on undisturbed samples to predict the soils behavior under a specific load. Loads are applied in increasing load increments and the results are recorded. The samples are usually inundated at a designated load to determine the effect of water contacting the bearing soil. The results are plotted on the "Consolidation Pressure Curve," figures. The load at which the water is added is noted on the drawing. Tests are performed in accordance with the latest version of ASTM D 2435.

Sieve Analysis

Dry Method:

A group of fourteen (14) sieves are assembled, with the sieve having the largest opening at the top, and the one having the smallest at the bottom. A solid collecting pan is placed below the bottom sieve. A 3000 gram specimen is weighed to within ± 0.1 g and placed in the topmost sieve. The assembly is completed by placing a solid cover over the top sieve. The sieve assembly is securely fastened into a mechanical sieve-shaking device. The group of assembled sieves is subjected to the action of the sieve shaker for a period of 300 seconds. Each sieve and the pan is weighed to within ± 0.1 g to determine the portion of the specimen retained. Tests are performed in accordance with the latest version of ASTM D 421.

Sieve Series	
Sieve #	Opening (mm)
3"	75.00
2"	50.00
1.5"	38.10
1"	25.40
¾"	19.00
⅜"	9.50
4	4.75
10	2.00
20	0.85
30	0.60
50	0.30
80	0.18
100	0.15
200	0.075
Pan	-

Atterberg Limits

This test covers the determination of the liquid limit, plastic limit, and the plasticity index of soils. Tests are performed in accordance with the latest version of ASTM D 4318.

LABORATORY RECAPITULATION - TABLE I-1

PIN 7000X / Cacique-Soledad Pedestrian Bridges

Location	Depth	Material Description	In Situ Dry Density (P.C.F.)	In Situ Water (%)	Liquid Limit (%)	Plastic Limit (%)	Plasticity Index (%)	% Passing #200 Sieve	Max. Dry Density (pcf)	Optimum Moisture (%)	Expansion Index
B - 1	1.5	Sandy Silt / Silty Sand (SM/ML)	111.0								
B - 1	5.0	Sandy Silt / Silty Sand (SM/ML)	101.4	13.1							
B - 1	10.0	Silty Sand (ML)		9.8							
B - 1	15.0	Clayey Sand (SC)	117.3	15.1			47.7				
B - 1	20.0	Silty Clay (CL) Clayey Sand (SC)		16.6							
B - 1	25.0	Silty Clay (CL) Clayey Sand (SC)	114.9	18.3	28.9	15.4	10				
B - 1	30.0	Silty Sand (SM) Silty Clay (CL) Clayey Sand		24.4				54.9			
B - 1	35.0	Silty Clay (CL)									
B - 1	40.0	Silty Sand (SM/ML) Silty Clay (CL) Clayey Silt (ML)		24.9							
B - 1	40.1	Silty Sand (SM/ML) Silty Clay (CL) Clayey Silt (ML)	122.1	14.4							
B - 1	45.0	Clay Sand (SC) Silty Clay (CL) Sandy Clay (SC) Sandy Silt (ML) Silty Clay (CL)	110.0	20.4				58.1			
B - 1	50.0	Sandy Clay (SC) Sandy Silt (ML) Silty Clay (CL)		17.3							
B - 1	60.0	Gravelly Clay (GC)		13.1							
B - 1	69.0	Silty Sandy Clay (SC)		21.9							
B - 2	5.0	Sandy Silt / Silty Sand (ML/SM)	106.4	6.6							
B - 2	10.0	Sandy Silt / Silty Sand (ML/SM)		15.7							
B - 2	15.0	Clayey Sand / Sandy Clay (ML/SM)	114.9	17.1							
B - 2	20.0	Clayey Sand / Sandy Clay (ML/SM)		17.6							
B - 2	25.0	Clayey Silt (ML) Silty Clay (CL)	115.1	19.0							
B - 2	30.0	Clayey Sand (SC) Silty Clay (CL)		19.4	35.3	16.8	20				
B - 2	35.0	Sandy Silty Clay (CL)		19.2							
B - 2	40.0	Clayey Sand / Sandy Clay (SC)	113.7	21.4							
B - 3	5.0	Sandy Silt (SM/ML)		9.0							
B - 3	7.0	Silty Sand / Sandy Silt (SM/ML) Clayey Silt (ML)		8.0							
B - 3	10.0	Silty Sand / Sandy Silt (SM/ML) Clayey Silt (ML)	113.6	15.1							43.7
B - 3	15.0	Clayey / Silt (ML) Silty Clay (CL)		16.2	28.2	17.1	10				
B - 3	20.0	Clayey / Silt (ML) Silty Clay (CL)	113.4	18.3							
B - 3	25.0	Silty Clay (CL) Clayey Silt (CL)		20.9	29.6	18.9	10				
B - 3	30.0	Clayey Silt (CL) Silty Clay with Gravels (CL)	125.3	12.9	34.0	19.6	10				
B - 3	35.0	Silty Clay (CL) Sandy Silt (SP)		21.9							
B - 3	40.0	Sand with Silt (SW) Gravelly Clay (GC)	121.9	15.3							
B - 3	50.0	Sandy with Silt (SP) Silty Clay with Gravels (CL/GC)		14.2							
B - 3	60.0	Silty Clay (CL) Clayey Silt		19.9							

SubSurface Designs, Inc.

LABORATORY RECAPITULATION - TABLE I-1

PIN 7000X / Cacique-Soledad Pedestrian Bridges

Location	Depth	Material Description	In Situ Dry Density (P.C.F.)	In Situ Water (%)	Liquid Limit (%)	Plastic Limit (%)	Plasticity Index (%)	% Passing # 200 Sieve	Max. Dry Density (pcf)	Optimum Moisture (%)	Expansion Index
B - 3	70.0	with Gravels (ML) Gravelly Sand (SW) Silty Sand (SM)									
				14.2							


CHEMICAL TEST RESULTS

Table C-2					
Location	Depth (ft)	Sulfate (ppm)	Chloride (ppm)	pH	Resistivity (Ohms-cm)
B-2	20.0	112	30	7.14	1200

ATTERBERG LIMITS

PROJECT NAME: *Cacique-Soledad Pedestrian Bridges*

PROJECT NUMBER: *PIN 7000X*



Sample Identification	Material Description	LL	PL	PI
● B - 1 25.0'	Silty Clay (CL) Clayey Sand (SC)	29	15	14
○ B - 2 30.0'	Clayey Sand (SC) Silty Clay (CL)	35	17	18
⊗ B - 3 15.0'	Clayey Silt (ML)	28	17	11
★ B - 3 25.0'	Silty Clay (CL) Clayey Silt (CL)	30	19	11
⊙ B - 3 30.0'	Clayey Silt (CL) Silty Clay With Gravels (CL)	34	20	14

SubSurface Designs, Inc.


GEOTECHNICAL ENGINEERS & ENGINEERING GEOLOGISTS

Figure A.1

SIEVE ANALYSIS

PROJECT NAME: *Cacique-Soledad Pedestrian Bridges*

PROJECT NUMBER: *PIN 7000X*



Sample Identification			Material Description				LL	PL	PI	Cc	Cu
●	B - 1	15.0'	Calyey Sand (SC)								
○	B - 1	30.0'	Silty Sand (SM) Silty Clay (CL) Clayey Sand								
⊗	B - 1	45.0'	Clay Sand (SC) Silty Clay (CL)								
★	B - 3	7.0'	Silty Sand / Sandy Silt (SM/ML) Clayey Silt (ML)								
Sample Identification			D100	D60	D30	D10	%Gravel	%Sand	%Silt	%Clay	
●	B - 1	15.0'	4.75	0.128				52.1	47.7		
○	B - 1	30.0'	4.75	0.096				44.5	54.9		
⊗	B - 1	45.0'	9.5	0.085			0.4	40.6	58.1		
★	B - 3	7.0'	9.5	0.15			1.0	54.9	43.7		


SubSurface Designs, Inc.

GEOTECHNICAL ENGINEERS & ENGINEERING GEOLOGISTS

Figure SV.1

S H E A R T E S T

PROJECT NAME: <i>Cacique-Soledad Pedestrian Bridges</i>	SAMPLE ID: <i>B - 1 @ 40.00'</i>
PROJECT NUMBER: <i>PIN 7000X</i>	MATERIAL DESCRIPTION: <i>Silty Sand (SM/ML) Silty Clay (CL) Clayey Silty</i>
TEST METHOD: <i>Ultimate Saturated Shear</i>	



MOISTURE CONTENT (%)	DENSITY (pcf)	RESULTS
In Situ: <i>24.9</i>	Dry Density:	Phi (deg.):
Saturated: <i>19.7</i>		Cohesion (ksf):


SubSurface Designs, Inc.

GEOTECHNICAL ENGINEERS & ENGINEERING GEOLOGISTS

Figure S.1

S H E A R T E S T

PROJECT NAME: <i>Cacique-Soledad Pedestrian Bridges</i>	SAMPLE ID: <i>B - 2 @ 5.00'</i>
PROJECT NUMBER: <i>PIN 7000X</i>	MATERIAL DESCRIPTION: <i>Sandy Silt / Silty Sand (ML/SM)</i>
TEST METHOD: <i>Ultimate Saturated Shear</i>	



MOISTURE CONTENT (%)	DENSITY (pcf)	RESULTS
In Situ: <i>6.6</i>		Phi (deg.):
Saturated: <i>24.7</i>	Dry Density: <i>106.4</i>	Cohesion (ksf):


SubSurface Designs, Inc.

GEOTECHNICAL ENGINEERS & ENGINEERING GEOLOGISTS

Figure S.2

S H E A R T E S T

PROJECT NAME: <i>Cacique-Soledad Pedestrian Bridges</i>	SAMPLE ID: <i>B - 2 @ 15.00'</i>
PROJECT NUMBER: <i>PIN 7000X</i>	MATERIAL DESCRIPTION: <i>Clayey Sand / Sandy Clay (ML/SM)</i>
TEST METHOD: <i>Ultimate Saturated Shear</i>	



MOISTURE CONTENT (%)	DENSITY (pcf)	RESULTS
In Situ: <i>17.1</i>		Phi (deg.):
Saturated: <i>19.4</i>	Dry Density: <i>114.9</i>	Cohesion (ksf):

SubSurface Designs, Inc.

GEOTECHNICAL ENGINEERS & ENGINEERING GEOLOGISTS


Figure S.3

CONSOLIDATION TEST

PROJECT NAME: <i>Cacique-Soledad Pedestrian Bridges</i>	SAMPLE ID: <i>B - 3 @ 20.00'</i>
---	----------------------------------

PROJECT NUMBER: <i>PIN 7000X</i>	MATERIAL DESCRIPTION: <i>Clayey / Silt (ML) Silty Clay (CL)</i>
----------------------------------	---

Load (psf) water added to test at: 100



MOISTURE CONTENT (%)	DRY DENSITY (pcf)	
In Situ: <i>18.3</i>	Before Test: <i>113.4</i>	

SubSurface Designs, Inc.


GEOTECHNICAL ENGINEERS & ENGINEERING GEOLOGISTS

Figure C.1

CONSOLIDATION TEST

PROJECT NAME: <i>Cacique-Soledad Pedestrian Bridges</i>	SAMPLE ID: <i>B - 3 @ 30.00'</i>
PROJECT NUMBER: <i>PIN 7000X</i>	MATERIAL DESCRIPTION: <i>Clayey Silt (CL) Silty Clay With Gravels (CL)</i>

Load (psf) water added to test at: 100



MOISTURE CONTENT (%)	DRY DENSITY (pcf)	
In Situ: <i>12.9</i>	Before Test: <i>125.3</i>	

SubSurface Designs, Inc.

GEOTECHNICAL ENGINEERS & ENGINEERING GEOLOGISTS

Figure C.2



Mason Street Pedestrian Bridge Project





Log of Test Boring Plan Sheet





ELEVATION, ft	DEPTH, ft	MATERIAL SYMBOL	SAMPLE NO.	SAMPLERS	SAMPLER BLOW COUNT	LOCATION: Southwest side of Bridge SURFACE EL: 48.00 ft +/- (rel. datum)	MATERIAL DESCRIPTION	UNIT WET WEIGHT, pcf	UNIT DRY WEIGHT, pcf	WATER CONTENT, %	% PASSING #200 SIEVE	LIQUID LIMIT, %	PLASTICITY INDEX, %	UNDRAINED SHEAR STRENGTH, S_u , ksf
-46	2		1				ARTIFICIAL FILL (af) - 9" of AC over 5" base							
-44	4		2		4		Silty SAND (SM): very loose, dusky yellowish brown, slightly moist	92	88	18	27			
-42	6		3		(4)		Clayey SAND (SC): very loose, dark yellowish brown, slightly moist			5	39			
-40	8		4		5		Silty SAND (SM): very loose, moderate yellowish brown, slightly moist	96	93	4	12			
-38	10		5		(8)		Clayey SAND (SC): loose, dark yellowish brown, moist			11				
-36	12		6		4		Silty SAND (SM): loose, dark yellowish brown, moist	109	99	10	32			
-34	14		7		(7)		- mottled, trace gravel, at 9'							
-32	16		8		4		Silty SAND (SM): loose, dark yellowish brown, moist			17				
-30	18		9		(15)		Clayey SAND with gravel (SC): very loose, dark yellowish brown, moist, possible Alluvium - loose, slightly porous rootlets	132	107	23	12			
-28	20		10		19		ALLUVIUM (Qal) Clayey SAND (SC): very loose, dark yellowish brown, moist			20				
-26	22		11		(16)		- 4" layer of Lean CLAY (CL), oxidation staining, at 20'	133	113	17	37			
-24	24		12		39		- loose, wet, at 25' - medium dense, some gravel, 1 foot of heaving sand, at 30' - loose, 35'			23				
-22	26		13		(50/3")		FANGLOMERATE DEPOSITS (Qfg) Silty SAND (SM): yellowish orange, moist, with gravel and cobbles - very dense			9				
-20	28		14		50		Clayey SAND (SC) with gravel: dark yellowish brown	135	113	19	20			
-18	30		15		(REF)		Silty SAND (SM): very loose, moderate yellowish brown, wet, medium to fine grained - possible heaving sand, at 60'			21	22			
-16	32		16		WOH		- very dense, lens of Lean CLAY (CL), at 65'	130	107	22				
-14	34		17		(50/2")		Sandy Lean CLAY (CL): very stiff, dark yellowish brown, moist			19				
-12	36		18		22									
-10	38													
-8	40													
-6	42													
-4	44													
-2	46													
0	48													
-2	50													
-4	52													
-6	54													
-8	56													
-10	58													
-12	60													
-14	62													
-16	64													
-18	66													
-20	68													
-22	70													
-24	72													
-26	74													
-28	76													
-30	78													
-32	80													
-34	82													
-36	84													

COMPLETION DEPTH: 71.5 ft
 DEPTH TO WATER: 24.0 ft
 BACKFILLED WITH: Cuttings
 DRILLING DATE: December 10, 2001

The log and data presented are a simplification of actual conditions encountered at the time of drilling at the drilled location. Subsurface conditions may differ at other locations and with the passage of time.

DRILLING METHOD: 8-in. dia. Hollow Stem Auger
 HAMMER TYPE: Automatic Trip
 DRILLED BY: S/G Testing
 LOGGED BY: CWelke
 CHECKED BY: GSDenlinger

LOG OF DRILL HOLE NO. DH-1
 Mason Street Bridge
 Santa Barbara, California



January 2002
Project No. 01-42-0941

ELEVATION, ft	DEPTH, ft	MATERIAL SYMBOL	SAMPLE NO.	SAMPLERS	SAMPLER BLOW COUNT	LOCATION: Northeast side of Bridge SURFACE EL: 48.00 ft +/- (rel. datum)	UNIT WET WEIGHT, pcf	UNIT DRY WEIGHT, pcf	WATER CONTENT, %	% PASSING #200 SIEVE	LIQUID LIMIT, %	PLASTICITY INDEX, %	UNDRAINED SHEAR STRENGTH, S_u , ksf
						MATERIAL DESCRIPTION							
-46	2					ARTIFICIAL FILL (af) 8.5" AC over 5.5" base							
-44	4		1		(7)	Silty SAND (SM): loose, dusky yellowish brown, slightly moist	107	97	10				
-42	6		2		2	fine grained sand			6				
-40	8		3			- very loose				27			
-38	10		4		(5)	- slightly darker	101	91	11				
-36	12		5		4	- 3" lens of Lean CLAY (CL), thick			12				
-34	14		6		(7)	Clayey SAND (SC): loose, dusky yellowish brown, moist, roots up to 1/8" in diameter, oxidation zones, possible Alluvium	105	96	10				
-32	16		7		4	Sandy Lean CLAY (CL): soft, dark yellowish brown, moist, roots up to 1/8" in diameter, possible Alluvium			25				
-30	18		8		(57)		292	277	6				
-28	20		9		5	ALLUVIUM (Qal)			10				
-26	22		10		10	Clayey SAND (SC) with gravel and cobbles: dense, dark yellowish brown, moist			18	15			
-24	24					- loose, moist to wet, at 25'							
-22	26					- moderate yellowish brown, wet, at 30'							
-20	28												
-18	30												
-16	32												
-14	34												
-12	36				(17)	- medium dense, at 30'	129	105	23				
-10	38												
-8	40				(50/4")	FANGLOMERATE DEPOSITS (Qfg)							
-6	42					Clayey SAND with gravel (SC): very dense, dusky yellowish brown, moist, cobbles	131	106	24				
-4	44												
-2	46					- medium dense, at 45'			25				
0	48												
-2	50												
-4	52				(41)	Sandy lean CLAY (CL) to Clayey SAND (SC): very stiff, dark yellowish orange, moist, sandy	128	106	21	35			
-6	54					- lenses of Clayey SANDY (SC), fine grained sand			19	24			
-8	56				23								
-10	58												
-12	60												
-14	62				(50/5")		136	116	18				
-16	64					- harder drilling from 62' to 63'							
-18	66								18				
-20	68												
-22	70					Sandy Lean CLAY (CL): hard, dark yellowish brown, moist, lenses of Sandy CLAY (SC)	129	103	24				
-24	72				(52)								
-26	74												
-28	76					Clayey GRAVEL with sand (GC): dense, dark yellowish brown, moist							
-30	78					subrounded							
-32	80					- very dense							
-34	82				(83)								
-36	84												

COMPLETION DEPTH: 80.5 ft
DEPTH TO WATER: 25.0 ft
BACKFILLED WITH: Cuttings
DRILLING DATE: December 11, 2001

The log and data presented are a simplification of actual conditions encountered at the time of drilling at the drilled location. Subsurface conditions may differ at other locations and with the passage of time.

DRILLING METHOD: 8-in. dia. Hollow Stem Auger
HAMMER TYPE: Automatic Trip
DRILLED BY: S/G Testing
LOGGED BY: CWelke
CHECKED BY: GSDenfinger

LOG OF DRILL HOLE NO. DH-2
Mason Street Bridge
Santa Barbara, California

PLATE A-2



January 2002
 Project No. 01-42-0941

ELEVATION, ft	DEPTH, ft	MATERIAL SYMBOL	SAMPLE NO.	SAMPLES	BLOW COUNT / REC'D/DRIVE"	LOCATION: The drill hole location referencing local landmarks or coordinates SURFACE EL: Using local, MSL, MLLW or other datum	General Notes										
							<p>Soil Texture Symbol</p> <p>Sloped line in symbol column indicates transitional boundary</p> <p>Samplers and sampler dimensions (unless otherwise noted in report text) are as follows:</p> <p>Symbol for:</p> <ol style="list-style-type: none"> SPT Sampler, driven 1 3/8" ID, 2" OD CA Liner Sampler, driven 2 3/8" ID, 3" OD CA Liner Sampler, disturbed 2 3/8" ID, 3" OD Thin-walled Tube, pushed 2 7/8" ID, 3" OD Bulk Bag Sample (from cuttings) Hand Auger Sample CME Core Sample Lexan Sample Pitcher Sample Vibracore Sample No Sample Recovered <p>Sampler Driving Resistance</p> <p>Number of blows with 140 lb. hammer, falling 30-in. to drive sampler 1-ft. after seating sampler 6-in.; for example,</p> <table border="1"> <thead> <tr> <th>Blows/ft</th> <th>Description</th> </tr> </thead> <tbody> <tr> <td>25</td> <td>25 blows drove sampler 12" after initial 6" of seating</td> </tr> <tr> <td>86/11"</td> <td>After driving sampler the initial 6" of seating, 36 blows drove sampler through the second 6" interval, and 50 blows drove the sampler 5" into the third interval</td> </tr> <tr> <td>50/6"</td> <td>50 blows drove sampler 6" after initial 6" of seating</td> </tr> <tr> <td>Ref/3"</td> <td>50 blows drove sampler 3" during initial 6" seating interval</td> </tr> </tbody> </table> <p>Blow counts for California Liner Sampler shown in ()</p> <p>Length of sample symbol approximates recovery length</p> <p>Classification of Soils per ASTM D2487 or D2488</p> <p>Geologic Formation noted in bold font at the top of interpreted interval</p> <p>Strength Legend</p> <p>Q = Unconfined Compression u = Unconsolidated Undrained Triaxial t = Torvane p = Pocket Penetrometer m = Miniature Vane</p> <p>Water Level Symbols</p> <p>☼ Initial or perched water level ☼ Final ground water level ☼ Seepages encountered</p> <p>Rock Quality Designation (RQD) is the sum of recovered core pieces greater than 4 inches divided by the length of the cored interval.</p>	Blows/ft	Description	25	25 blows drove sampler 12" after initial 6" of seating	86/11"	After driving sampler the initial 6" of seating, 36 blows drove sampler through the second 6" interval, and 50 blows drove the sampler 5" into the third interval	50/6"	50 blows drove sampler 6" after initial 6" of seating	Ref/3"	50 blows drove sampler 3" during initial 6" seating interval
Blows/ft	Description																
25	25 blows drove sampler 12" after initial 6" of seating																
86/11"	After driving sampler the initial 6" of seating, 36 blows drove sampler through the second 6" interval, and 50 blows drove the sampler 5" into the third interval																
50/6"	50 blows drove sampler 6" after initial 6" of seating																
Ref/3"	50 blows drove sampler 3" during initial 6" seating interval																
-12	2	[Symbol]	1	X	25	Well graded GRAVEL (GW)											
		[Symbol]		X	(25)	Poorly graded GRAVEL (GP)											
-14	4	[Symbol]	2	X	(25)	Well graded SAND (SW)											
		[Symbol]		X	(25)	Poorly graded SAND (SP)											
-16	6	[Symbol]	3	X	(25)	Silty SAND (SM)											
		[Symbol]		X	(25)	Clayey SAND (SC)											
-18	8	[Symbol]	4	X	(25)	Silty, Clayey SAND (SC-SM)											
-20	10	[Symbol]	5	X	18"/30"	Elastic SILT (MH)											
-22	12	[Symbol]	6	X	(25)	SILT (ML)											
-24	14	[Symbol]	7	X	20"/24"	Silty CLAY (CL-ML)											
-26	16	[Symbol]	8	X	(25)	Fat CLAY (CH)											
-28	18	[Symbol]	9	X	(25)	Lean CLAY (CL)											
-30	20	[Symbol]	10	X	30"/30"	CONGLOMERATE											
-32	22	[Symbol]	11	X	20"/24"	SANDSTONE											
-34	24	[Symbol]				SILTSTONE											
-36	26	[Symbol]				MUDSTONE											
-38	28	[Symbol]				CLAYSTONE											
-40	30	[Symbol]				SHALE											
-42	32	[Symbol]				GRANITE											
-44	34	[Symbol]				Paving and/or Base Materials											
-46	36	[Symbol]															
-48	38	[Symbol]															

KEY TO TERMS & SYMBOLS USED ON LOGS



Laboratory Testing





LOCATION	SAMPLE CLASSIFICATION							COMPACTION TEST	DIRECT SHEAR TEST	COMPRESSIVE STRENGTH TESTS	CORROSIVITY TESTS	R-VALUE	EXPANSION INDEX	TEST LISTING						
	SAMPLE NUMBER	UWW pcf	UDW pcf	MC %	FINES %	LL %	PI %								MAX DD pcf	OPT MC %	C ksf	PHI deg	Q _y ksf	S _i Cell P's ksf
DH-1		Silty SAND (SM)																	S, R	
	3.0				27									33						
DH-1		Clayey SAND (SC)																		M, S, H
	2			18	39															
DH-1		Silty SAND (SM)																		T, D, F
	3																			
	6.0	92	88	5	21					0.33	26									
DH-1		Clayey SAND (SC)																		M
	4																			
	8.5			11																
DH-1		Silty SAND (SM)																		T, F
	5																			
	11.0	96	93	4	12															
DH-1		Clayey SAND (SC)																		M
	6																			
	13.5			10																
DH-1		Clayey SAND (SC)																		T, D, F
	7									0.20	33									
	16.0	109	99	10	32															
DH-1		Clayey SAND (SC)																		M, Co
	8																			
	20.0			17																
DH-1		Clayey SAND (SC)																		T, F
	9																			
	25.0	132	107	23	12															
DH-1		Clayey SAND (SC)																		M
	10																			
	30.0			20																

Classification Tests
 UWW = Unit Wet Weight
 UDW = Unit Dry Weight
 MC = Moisture Content
 Fines = % passing #200 Sieve
 LL = Liquid Limit
 PI = Plasticity Index

Compaction Test
 MAX DD = Maximum Dry Density
 OPT MC = Optimum Moisture Content

Direct Shear Test
 C = Assigned Cohesion, ksf
 PHI = Assigned Friction Angle, degrees

Compressive Strength Tests
 Qu = Unconfined Compression
 Su = Undrained Shear Strength
 u = Unconsolidated Undrained
 p = Pocket Penetrometer
 t = Torvane
 m = Miniature Vane

Corrosivity Tests
 R = Resistivity, ohm-cm, satur.
 pH = pH
 Cl = Chloride, ppm
 SO₄ = Sulfate, ppm

Test Listing Abbreviations
 M = Moisture Content
 T = Total Density
 S = Sieve Analysis
 F = % Passing #200 Sieve
 H = Hydrometer Analysis
 A = Atterberg Limits
 P = Compaction Test

Test Listing Abbreviations
 D = Direct Shear Test
 C = Consolidation Test
 CU = Consolid. Test
 U = UU, Triaxial
 R = R-value
 E = Expansion

SUMMARY OF LABORATORY TEST RESULTS

Mason Street Bridge, Santa Barbara, California



LOCATION	SAMPLE CLASSIFICATION								COMPACTION TEST	DIRECT SHEAR TEST	COMPRESSIVE STRENGTH TESTS	CORROSIIVITY TESTS	R-VALUE	EXPANSION INDEX	TEST LISTING				
	SAMPLE NUMBER	DEPTH, ft	UWW pcf	UDW pcf	MC %	FINES %	LL %	PI %								MAX DD pcf	OPT MC %	C ksf	PHI deg
DH-2	4										0.26	29							T, D, F
DH-2	8.5	101	91	11	27														M
DH-2	5																		T
DH-2	11.0																		M
DH-2	6																		T
DH-2	13.5	105	96	10															M
DH-2	7																		T
DH-2	16.0																		M
DH-2	8																		T
DH-2	20.0	292	277	6															M
DH-2	9																		M
DH-2	25.0																		M, F
DH-2	10																		T
DH-2	30.0																		T
DH-2	11																		T
DH-2	35.0	129	105	23															T
DH-2	12																		T
DH-2	39.0	131	106	24															M
DH-2	13																		M
DH-2	45.0																		M

Classification Tests
UWW = Unit Wet Weight
UDW = Unit Dry Weight
MC = Moisture Content
Fines = % passing #200 Sieve
LL = Liquid Limit
PI = Plasticity Index

Compaction Test
MAX DD = Maximum Dry Density
OPT MC = Optimum Moisture Content
Direct Shear Test
C = Assigned Cohesion, ksf
PHI = Assigned Friction Angle, degrees

Compressive Strength Tests
Qu = Unconfined Compression
Su = Undrained Shear Strength
p = Pocket Penetrometer
l = Torvane
m = Miniature Vane

Corrosivity Tests
R = Resistivity, ohm-cm, satur.
pH = pH
Cl = Chloride, ppm
SO₄ = Sulfate, ppm

Test Listing Abbreviations
M = Moisture Content
T = Total & Dry Density
S = Sieve Analysis
F = % Passing #200 Sieve
H = Hydrometer Analysis
A = Atterberg Limits
P = Compaction Test

Test Listing Abbreviations
D = Direct Shear Test
C = Consolidation Test
Co = Consolivity Tests
CU = CU Triaxial
U = UU Triaxial
R = R-value
E = Expansion

SUMMARY OF LABORATORY TEST RESULTS

Mason Street Bridge, Santa Barbara, California



LOCATION	SAMPLE CLASSIFICATION							COMPACTION TEST	DIRECT SHEAR TEST	COMPRESSIVE STRENGTH TESTS	CORROSIIVITY TESTS				EXPANSION INDEX	TEST LISTING			
	SAMPLE NUMBER	DEPTH, ft	UWW pcf	UDW pcf	MC %	FINES %	LL %				PI %	MAX DD pcf	OPT MC %	C ksf			PHI deg	Q _u ksf	S _u Cell P's ksf
DH-2		14									0.42	35							T, D, F
		50.0	128	106	21	35													
DH-2		15																	M, F
		55.0			19	24													
DH-2		16																	T
		60.0	136	116	18														
DH-2		17																	M, Co
		65.0			18														
DH-2		18																	T
		70.0	129	103	24														

SUMMARY OF LABORATORY TEST RESULTS

Mason Street Bridge, Santa Barbara, California

Classification Tests
 UWW = Unit Wet Weight
 UDW = Unit Dry Weight
 MC = Moisture Content
 Fines = % passing #200 Sieve
 LL = Liquid Limit
 PI = Plasticity Index

Compaaction Test
 MAX DD = Maximum Dry Density
 OPT MC = Optimum Moisture Content

Direct Shear Test
 C = Assigned Cohesion, ksf
 PHI = Assigned Friction Angle, degrees


Compressive Strength Tests
 Qu = Unconfined Compression
 Su = Undrained Shear Strength
 u = Unconsolidated Undrained
 p = Pocket Penetrometer
 t = Torvane
 m = Miniature Vane

Corrosivity Tests
 R = Resistivity, ohm-cm, satur.
 pH = pH
 Cl = Chloride, ppm
 SO₄ = Sulfate, ppm

Test Listing Abbreviations
 M = Moisture Content
 T = Total & Dry Density
 S = Sieve Analysis
 F = % Passing #200 Sieve
 H = Hydrometer Analysis
 A = Atterberg Limits
 P = Compaction Test
 D = Direct Shear Test
 C = Consolidation Test
 Co = Corrosivity Tests
 CU = CU Triaxial
 U = UU Triaxial
 R = R-value
 E = Expansion



January 2002
 Project No. 01-42-0941



GRAVEL		SAND			SILT or CLAY
Coarse	Fine	Coarse	Medium	Fine	


LEGEND	
(location)	(depth, ft)
○	DH-1 3.0
●	DH-1 3.5

CLASSIFICATION	C _c	C _u
Silty SAND (SM)		
Clayey SAND (SC)		

GRAIN SIZE CURVES
 Mason Street Bridge
 Santa Barbara, California



January 2002
Project No. 01-42-0941




	● PEAK
COHESION, ksf	0.3
ANGLE OF INTERNAL FRICTION, deg	25.6
LOCATION	DH-1
DEPTH, ft	6
MOISTURE CONTENT, %	5
UNIT DRY WEIGHT, pcf	88
MATERIAL DESCRIPTION	Silty SAND (SM)
SAMPLE CONDITION	Ring Driven

DIRECT SHEAR TEST RESULTS

Mason Street Bridge
Santa Barbara, California

PLATE B-3a



	● PEAK
COHESION, ksf	0.2
ANGLE OF INTERNAL FRICTION, deg	32.7
LOCATION	DH-1
DEPTH, ft	16
MOISTURE CONTENT, %	10
UNIT DRY WEIGHT, pcf	99
MATERIAL DESCRIPTION	Clayey SAND (SC)
SAMPLE CONDITION	Ring Driven


DIRECT SHEAR TEST RESULTS

Mason Street Bridge
 Santa Barbara, California

PLATE B-3b



January 2002
Project No. 01-42-0941




	● PEAK
COHESION, ksf	0.5
ANGLE OF INTERNAL FRICTION, deg	31.9
LOCATION	DH-1
DEPTH, ft	35
MOISTURE CONTENT, %	17
UNIT DRY WEIGHT, pcf	113
MATERIAL DESCRIPTION	Clayey SAND (SC)
SAMPLE CONDITION	Ring Driven

DIRECT SHEAR TEST RESULTS

Mason Street Bridge
Santa Barbara, California

PLATE B-3c



	● PEAK
COHESION, ksf	0.3
ANGLE OF INTERNAL FRICTION, deg	29.4
LOCATION	DH-2
DEPTH, ft	8.5
MOISTURE CONTENT, %	11
UNIT DRY WEIGHT, pcf	91
MATERIAL DESCRIPTION	Silty SAND (SM)
SAMPLE CONDITION	Ring Driven


DIRECT SHEAR TEST RESULTS

Mason Street Bridge
 Santa Barbara, California

PLATE B-3d



January 2002
 Project No. 01-42-0941



	● PEAK
COHESION, ksf	0.4
ANGLE OF INTERNAL FRICTION, deg	35.2
LOCATION	DH-2
DEPTH, ft	50
MOISTURE CONTENT, %	21
UNIT DRY WEIGHT, pcf	106
MATERIAL DESCRIPTION	Sandy Lean CLAY (CL) to Clayey SAND (SC)
SAMPLE CONDITION	Ring Driven

DIRECT SHEAR TEST RESULTS
 Mason Street Bridge
 Santa Barbara, California

PLATE B-3e



Quinientos Street Bridge Replacement Project





Log of Test Boring and Cone Penetrometer Testing





Bengal Engineering
 250 Big Sur Drive
 Goleta CA 93117
 Telephone: (805) 685-6511

BORING NUMBER B-1

CLIENT City of Santa Barbara **PROJECT NAME** Quinientos St Bridge Replacement

PROJECT NUMBER _____ **PROJECT LOCATION** King Sycamore Creek

DATE STARTED 7/15/14 **COMPLETED** 7/15/14 **GROUND ELEVATION** _____ **HOLE SIZE** 8" inches

DRILLING CONTRACTOR Choice Drilling **GROUND WATER LEVELS:**

DRILLING METHOD HSA - Track Rig CME 75 **▽ AT TIME OF DRILLING** 41.70 ft

LOGGED BY E. Pongracz **CHECKED BY** _____ **AT END OF DRILLING** ---

NOTES _____ **AFTER DRILLING** ---

BENGAL GEOTECH BH V5 - BENGAL MOD GINT STD US LAB 2-10-10.GDT - 7/17/14 09:05 - C:\PROGRAM FILES (X86)\GINT\PROJECTS\QUINIENTOS ST BRIDGE.GPJ

ELEV (ft)	DEPTH (ft)	SAMPLE TYPE NUMBER	BLOW COUNTS (N VALUE)	GRAPHIC LOG	MATERIAL DESCRIPTION	UNDRAINED SHR STRENGTH (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ATTERBERG LIMITS			FINES CONTENT (%)	OTHER TESTS
									LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX		
0					Asphalt Concrete (AC) 3" thick								
					Aggregate Base (AB) Gravelly Sand - light yellowish brown, dense								
					Earth Fill (ef)								
	5	GB 1 MC 2	7-11		Fine-grained Silty Sand/Sandy Silt (SM/ML) - brown, dense/stiff, slightly moist								
	10	SPT 3	15-19-20 (39)		Alluvium (Qal) Sandy Silt (ML) - light brown, very stiff, slightly moist, occ. slightly porous								
	15	MC 4	15-33		Fine-grained Silty Sand (SM) - reddish to orange-brown, dense, moist; contains lens of dark brown Silty Clay (CL) with scattered roots (alluvium)								
	20	SPT 5	15-29-40 (69)		Clayey Gravel w/ Sand to Clayey Sand w/Gravel (GC/SC) - dark brown to orange brown, stiff to very stiff, very moist; in sharp contact with Sand with Silt (SM) - tan to light yellowish brown								
	25	MC 6	12-23		Fine-grained Sandy Silt (ML) with Clay and occ. small gravel - reddish brown, stiff, moist								
	30	SPT 7	35-39-26 (65)		@29' - Driller notes harder drilling Clayey, Gravelly Sand (SC) - orange brown; in sharp contact with Clayey Sand (SC) - orange brown, very stiff, moist								
	35	MC 8	8-17		Sandy Clay (SC) with widely scatt. gravel in sharp contact with mottled Silty Clay (CL) - orange brown to yellow gray, stiff, very moist, water on sampler (probable perched water)								
	40												

(Continued Next Page)



Bengal Engineering
 250 Big Sur Drive
 Goleta CA 93117
 Telephone: (805) 685-6511

BORING NUMBER B-1

CLIENT City of Santa Barbara PROJECT NAME Quinientos St Bridge Replacement
 PROJECT NUMBER _____ PROJECT LOCATION ing Sycamore Creek

ELEV (ft)	DEPTH (ft)	SAMPLE TYPE NUMBER	BLOW COUNTS (N VALUE)	GRAPHIC LOG	MATERIAL DESCRIPTION	UNDRAINED SHR STRENGTH (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ATTERBERG LIMITS			FINES CONTENT (%)	OTHER TESTS
									LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX		
	40	▲ SPT 9	7-11-15 (26)		▽ Bedded Sandy, Clayey Silt (ML) wit scatt. gravel in sharp contact with Gravelly Sand w/ Clay (SW) - brownish orange to orange brown, stiff/dense, very moist to wet								
	45	⊗ MC 10	34-50/3"		same as above								
	50	▲ SPT 11	9-11-12 (23)		2"-3" thick beds of Silty Sand (SM), Sandy Silt (SM/ML), Gravelly Sand (SW) and Clayey Gravel (GC) - orange brown, stiff/dense, moist								
	55				@55'-60' - Driller notes easier drilling								
	60	▲ SPT 12	6-6-7 (13)		Beds of Silty Sand (SM), medium-grained Sand with Silt (SW), and Clayey Silt (ML/CL) - orange brown to brown orange, very dense to very stiff, very moist								
	65												
	70												
		13	7-11-18 (29)		Gravelly Sand with Clay (SP/SC), Silty Sand with Gravel (SM); in sharp contact with fine-grained Sandy Silt (ML) with occ. gravel and Clayey Silt (ML) - orange brown to reddish brown, very dense to medium stiff, moist to very moist								

Boring terminated at 71.5' below grade. Boring backfilled with native materials. Asphalt cold patch applied at surface. Bottom of borehole at 71.5 feet.



Bengal Engineering
 250 Big Sur Drive
 Goleta CA 93117
 Telephone: (805) 685-6511

BORING NUMBER B-2

PAGE 1 OF 2

CLIENT City of Santa Barbara **PROJECT NAME** Quinientos St Bridge Replacement

PROJECT NUMBER _____ **PROJECT LOCATION** ving Sycamore Creek

DATE STARTED 7/15/14 **COMPLETED** 7/15/14 **GROUND ELEVATION** _____ **HOLE SIZE** 8" inches

DRILLING CONTRACTOR Choice Drilling **GROUND WATER LEVELS:**

DRILLING METHOD HSA - Track Rig CME 75 **▽ AT TIME OF DRILLING** 39.60 ft

LOGGED BY E. Pongracz **CHECKED BY** _____ **AT END OF DRILLING** ---

NOTES _____ **AFTER DRILLING** ---

BENGAL GEOTECH BH V5 - BENGAL MOD GINT STD US LAB 2-10-10.GDT - 7/17/14 09:05 - C:\PROGRAM FILES (X86)\GINT\PROJECTS\QUINIENTOS ST BRIDGE.GPJ

ELEV (ft)	DEPTH (ft)	SAMPLE TYPE NUMBER	BLOW COUNTS (N VALUE)	GRAPHIC LOG	MATERIAL DESCRIPTION	UNDRAINED SHR STRENGTH (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ATTERBERG LIMITS			FINES CONTENT (%)	OTHER TESTS
									LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX		
0					Asphalt Concrete (AC) 3" thick Aggregate Base (AB) Gravelly Sand - light yellowish brown, dense Earth Fill (ef)								
	5	SPT 1	2-2-2 (4)		Fine-grained Silty Sand (SM) - light brown, slightly dense, slightly moist, scattered rootlets								
	10	MC 2	12-15		Fine-grained Silty Sand (SM) with scatt. gravel - brown, dense, slightly moist, mottled								
	15	SPT 3	2-2-3 (5)		same as above (SM)								
	20	MC 4	23-25		Sandy Gravel to Gravelly Sand (GW to SW) grading to Clayey Sand (SC) - brown to reddish brown, very dense to stiff, moist, mottled (alluvium)								
	25	SPT 5	7-10-11 (21)		Sandy, Clayey Silt (ML) grading to Clayey Sand/Sandy Clay (SC) - gray to light brown to orange brown, stiff, moist to very moist, sample contained ~4" thick cobble								
	30	MC 6	50		Driller notes hard drilling to 30' below grade. Sand to Silty Sand (SM) - light yellow to yellowish brown, dense, moist (probable weathered boulder) Driller notes drilling continues to be hard.								
	35												

(Continued Next Page)



Bengal Engineering
 250 Big Sur Drive
 Goleta CA 93117
 Telephone: (805) 685-6511

BORING NUMBER B-2


CLIENT City of Santa Barbara PROJECT NAME Quinientos St Bridge Replacement
 PROJECT NUMBER _____ PROJECT LOCATION ing Sycamore Creek


ELEV (ft)	DEPTH (ft)	SAMPLE TYPE NUMBER	BLOW COUNTS (N VALUE)	GRAPHIC LOG	MATERIAL DESCRIPTION	UNDRAINED SHR STRENGTH (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ATTERBERG LIMITS			FINES CONTENT (%)	OTHER TESTS
									LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX		
35		SPT 7	24-28-36 (64)		<p>Fanglomerate (Qf) (continued) Fractured Silt/Sand (ML/SP) - light brownish yellow to light yellowish brown, very dense, wet, weathered zone of brown silty clay (CL) (cobbles/boulders?)</p> <p>Very hard drilling from 38' to 40' below grade.</p>								
40		SPT 8	7-17-19 (36)		<p>Silty Sand (SM) to Clayey Sand (SC) with small gravel - orange brown, dense/stiff, very moist</p> <p>Driller notes continued hard drilling.</p>								
45		SPT 9	4-7-9 (16)		<p>Beds of Clayey Silt (ML), Clayey Sand (SC) to Silty, Clayey Sand with scattered Gravel (SC) - orange brown, stiff to very stiff, very moist</p>								
50		SPT 10	6-9-13 (22)		<p>Silty Sand (SM) to Sandy Silt (ML) - orange brown, stiff to very stiff, moist</p>								
55													
60		SPT 11	9-21-29 (50)		<p>Sand with Silt (SP) grading to Silty Sand (SM) with Clay - orange brown, very dense, moist to very moist</p>								

Boring terminated at 61.5' below grade. Boring backfilled with native materials. Asphalt cold patch applied at surface.
 Bottom of borehole at 61.5 feet.

LOGS OF CPT









Laboratory Testing



August 25, 2014

PIN# 7000U

Bengal Engineereing, Inc.
250 Big Sur Drive
Goleta, California 93117

Subject: Quinientos Street Bridge
 Results of Laboratory Testing

Dear Sirs:

Pursuant to your request please find attached hereto the results of soil engineering laboratory testing on the soil samples you provided. Sampling techniques, subsurface conditions, and other factors may vary across the subject site. Therefore, the test results may or may not be representative of the overall site conditions and care should be taken accordingly in interpreting the testing data provided. Interpretation of the laboratory test results and applications of the results on the design and construction of the project are beyond the scope of our work.

Services performed by this facility were conducted in a manner consistent with that level of care and skill ordinarily exercised by members of the profession currently practicing in the same locality under similar conditions. No other warranties are either expressed or implied.

If you have any questions, please do not hesitate to contact this office.

Respectfully submitted:
SUBSURFACE DESIGNS, INC.


Jon Mahn
Principal Engineer
RCE 60293



JEM/mm: 7000U.01L

Dist: (2) Addressee
(1) File

LABORATORY TESTING RESULTS

Laboratory Testing Method

Laboratory Recapitulation - Table I-1

Atterberg Limits

Sieve Analysis

Shear Strength Diagram

LABORATORY TESTING METHODS

Soil Classification

Soils are visually classified in accordance with the latest version of ASTM D 2488. Soils are classified in accordance with the latest version of ASTM D 2487 when testing, such as laboratory determination of particle-size characteristics, liquid limit, and plasticity index, is performed.

Moisture and Density Tests

The moisture content and in-place dry density of all undisturbed samples obtained were determined. The test results are presented in the Laboratory Recapitulation - Table I. Tests are performed in accordance with the latest version of ASTM D 2216.

Direct Shear Tests

Direct single-shear tests were performed on representative undisturbed samples to determine their strength characteristics. The desired normal load was applied to the specimen and allowed to come to equilibrium. The rate of deflection on the sample is approximately 0.05 inches per minute. All samples were saturated prior to shear testing. The results are plotted on the Shear Test Diagrams. Tests are performed in accordance with the latest version of ASTM D 3080.

Sieve Analysis

A group of fourteen (14) sieves are assembled, with the sieve having the largest opening at the top, and the one having the smallest at the bottom. A solid collecting pan is placed below the bottom sieve. A 3000 gram specimen is weighed to within ± 0.1 g and placed in the topmost sieve. The assembly is completed by placing a solid cover over the top sieve. The sieve assembly is securely fastened into a mechanical sieve-shaking device. The group of assembled sieves is subjected to the action of the sieve shaker for a period of 300 seconds. Each sieve and the pan is weighed to within ± 0.1 g to determine the portion of the specimen retained. Tests are performed in accordance with the latest version of ASTM D 421.

Sieve Series	
Sieve #	Opening (mm)
3"	75.00
2"	50.00
1.5"	38.10
1"	25.40

Sieve Series	
¾"	19.00
⅜"	9.50
4	4.75
10	2.00
20	0.85
30	0.60
50	0.30
80	0.18
100	0.15
200	0.075
Pan	-

Atterberg Limits

This test covers the determination of the liquid limit, plastic limit, and the plasticity index of soils. Tests are performed in accordance with the latest version of ASTM D 4318.

CHEMICAL TEST RESULTS

Table I-2					
Location	Depth (ft)	Sulfate (ppm)	Chloride (ppm)	pH	Resistivity (Ohms-cm)
B-1	40.0	58	30	7.50	1400

LABORATORY RECAPITULATION - TABLE I-1

PIN 7000U / Quinientos Street Bridge Replacement


Location	Depth	Material Description	In Situ Dry Density (P.C.F.)	In Situ Water (%)	Liquid Limit (%)	Plastic Limit (%)	Plasticity Index (%)	% Passing # 200 Sieve	Max. Dry Density (pcf)	Optimum Moisture (%)	Expansion Index
B - 1	3.0	Silty Sand (SM)		4.4	NP	NP	NP	46.6			
B - 1	5.0	Silty Sand (SM)	103.6	6.0							
B - 1	10.0	Silty Sand (SM)		6.8	18.6	15.8	3				
B - 1	15.0	Silty Sand (SM)	123.8	11.4							
B - 1	20.0	Clayey Sand (SC)		11.4							
B - 1	25.0	Clayey Sand (SC)	120.6	14.0							
B - 1	30.0	Clayey Sand (SC)		12.5							
B - 1	35.0	Clayey Sand (SC)	126.7	8.8							
B - 1	40.0	Clayey Sand (SC)		13.5							
B - 1	45.0	Clayey Sand (SC)	119.5	13.3							
B - 1	50.0	Clayey Sand (SC)		15.1							
B - 1	60.0	Clayey Sand (SC)		16.0							
B - 1	70.0	Clayey Sand (SC)		14.6							
B - 2	5.0	Silty Sand (SM)		5.9							
B - 2	10.0	Silty Sand (SM)	120.9	7.4							
B - 2	15.0	Silty Sand (SM)		7.8							
B - 2	20.0	Poorly Graded Sand with Gravel (SP)	129.0	8.6							
B - 2	25.0	Clayey Sand (SC)		12.9	25.3	16.7	8	36.9			
B - 2	30.0	Silty Sand (SM)		9.8							
B - 2	35.0	Clayey Sand (SC)	909.1	7.2							
B - 2	40.0	Clayey Sand (SC)		15.1							
B - 2	45.0	Sandy Silty Clay (CL-ML)		18.0	25.7	19.0	7	60.3			
B - 2	50.0	Sandy Silty Clay (CL-ML)		13.7							
B - 2	60.0	Sandy Silty Clay (CL-ML)		13.5							
TP - 1	0.5	Poorly Graded Sand with Gravel (SP)		1.9				1.0			

SubSurface Designs, Inc.

ATTERBERG LIMITS

PROJECT NAME: *Quinientos Street Bridge Replacement*

PROJECT NUMBER: *PIN 7000U*



Sample Identification			Material Description	LL	PL	PI
●	B - 1	3.0'	Silty Sand (SM)	NP	NP	NP
○	B - 1	10.0'	Silty Sand (SM)	19	16	3
⊕	B - 2	25.0'	Clayey Sand (SC)	25	17	8
★	B - 2	45.0'	Sandy Silty Clay (CL-ML)	26	19	7


SubSurface Designs, Inc.

GEOTECHNICAL ENGINEERS & ENGINEERING GEOLOGISTS

SIEVE ANALYSIS

PROJECT NAME: *Quinientos Street Bridge Replacement*

PROJECT NUMBER: *PIN 7000U*




Sample Identification			Material Description				LL	PL	PI	Cc	Cu
●	B - 1	3.0'	Silty Sand (SM)				NP	NP	NP		
○	B - 2	25.0'	Clayey Sand (SC)				25	17	8		
⊙	B - 2	45.0'	Sandy Silty Clay (CL-ML)				26	19	7		
★	TP - 1	0.5'	Poorly Graded Sand with Gravel (SP)							0.35	13.70
Sample Identification			D100	D60	D30	D10	%Gravel	%Sand	%Silt	%Clay	
●	B - 1	3.0'	9.5	0.132			1.7	49.4	46.6		
○	B - 2	25.0'	19	0.185			4.3	50.3	36.9		
⊙	B - 2	45.0'	4.75					39.6	60.3		
★	TP - 1	0.5'	38.1	4.725	0.751	0.345	17.8	59.0	1.0		

SubSurface Designs, Inc.

GEOTECHNICAL ENGINEERS & ENGINEERING GEOLOGISTS

S H E A R T E S T

PROJECT NAME: <i>Quinientos Street Bridge Replacement</i>	SAMPLE ID: <i>B - 1 @ 5.00'</i>
PROJECT NUMBER: <i>PIN 7000U</i>	MATERIAL DESCRIPTION: <i>Silty Sand (SM)</i>
TEST METHOD: <i>Ultimate Saturated Shear</i>	




MOISTURE CONTENT (%)	DENSITY (pcf)	RESULTS
In Situ: <i>6.0</i>		Phi (deg.):
Saturated: <i>23.7</i>	Dry Density: <i>103.6</i>	Cohesion (ksf):

SubSurface Designs, Inc.

GEOTECHNICAL ENGINEERS & ENGINEERING GEOLOGISTS

S H E A R T E S T

PROJECT NAME: <i>Quinientos Street Bridge Replacement</i>	SAMPLE ID: <i>B - 1 @ 45.00'</i>
PROJECT NUMBER: <i>PIN 7000U</i>	MATERIAL DESCRIPTION: <i>Clayey Sand (SC)</i>
TEST METHOD: <i>Ultimate Saturated Shear</i>	




MOISTURE CONTENT (%)	DENSITY (pcf)	RESULTS
In Situ: <i>13.3</i>		Phi (deg.):
Saturated: <i>20.7</i>	Dry Density: <i>119.5</i>	Cohesion (ksf):

SubSurface Designs, Inc.

GEOTECHNICAL ENGINEERS & ENGINEERING GEOLOGISTS

S H E A R T E S T

PROJECT NAME: <i>Quinientos Street Bridge Replacement</i>	SAMPLE ID: <i>B - 2 @ 30.00'</i>
PROJECT NUMBER: <i>PIN 7000U</i>	MATERIAL DESCRIPTION: <i>Silty Sand (SM)</i>
TEST METHOD: <i>Ultimate Saturated Shear</i>	



MOISTURE CONTENT (%)	DENSITY (pcf)	RESULTS
In Situ: <i>9.8</i>		Phi (deg.):
Saturated: <i>19.2</i>	Dry Density: <i>909.1</i>	Cohesion (ksf):

SubSurface Designs, Inc.

GEOTECHNICAL ENGINEERS & ENGINEERING GEOLOGISTS



Montecito Street Bridge Replacement Project





Log of Test Boring





ELEVATION, ft	DEPTH, ft	MATERIAL SYMBOL	SAMPLE NO.	SAMPLERS	SAMPLER BLOW COUNT	LOCATION: See Plate 2 - Subsurface Exploration Plan N 1,982,564 E 6,055,891.4 CA State Plane, Zone V, NAD83 ft SURFACE EL: 60.1 ft +/- (rel. NAVD 88 datum)	UNIT WET WEIGHT, pcf	UNIT DRY WEIGHT, pcf	WATER CONTENT, %	% PASSING #200 SIEVE	LIQUID LIMIT, %	PLASTICITY INDEX, %	UNDRAINED SHEAR STRENGTH, S_u , ksf
						MATERIAL DESCRIPTION							
						ASPHALT CONCRETE (4")							
						CONCRETE (6")							
						ARTIFICIAL FILL (af) SILTY SAND (SM); medium dense; brown; moist; mostly fine SAND; trace gravel; red and yellow speckles							
-58	2		1		(27)		131	125	5				
-56	4												
-54	6												
-52	8					ALLUVIUM (Qal) SILTY SAND (SM); medium dense; brown; moist; mostly fine SAND; little fines; with pale brown veins							
-60	10		2		14				14				
-48	12												
-46	14												
-44	16		3a 3b		(24)	- some fines; slightly clayey	113	105	8	31			
-42	18												
-40	20		4		14	- very moist; increasing clay content			13				
-38	22												
-36	24												
-34	26		5		(29)		125	113	11	34	19	1	
-32	28												
-30	30		6		14	- trace pulverized gravel and cobble in sampler			20				
-28	32					OLDER ALLUVIUM (Qol) COBBLES and BOULDERS; silty SANDSTONE; very soft; yellow; intensely weathered; in a matrix of clayey GRAVEL with SAND (GC); dense; multicolored, brown, red, yellow and gray; moist; rig chatter and loss of drilling fluid at 32'							
-26	34												
-24	36		7		33								
-22	36												

The log and data presented are a simplification of actual conditions encountered at the time of drilling at the drilled location. Subsurface conditions may differ at other locations and with the passage of time.

COMPLETION DEPTH: 76.0 ft
 DEPTH TO WATER: Not Measured
 BACKFILLED WITH: Cement Grout
 DRILLING DATE: May 6, 2015

DRILLING METHOD: 4.875-inch-dia. Mud Rotary Wash
 HAMMER TYPE: 140-lb Automatic Trip
 DRILLED BY: SoCal Drilling
 LOGGED BY: J. Martos
 CHECKED BY: L.A. Berry
 RIG TYPE: Mayhew 1000

LOG OF DRILL HOLE NO. DH-01
 Montecito Street Bridge Replacement
 Santa Barbara, California



ELEVATION, ft	DEPTH, ft	MATERIAL SYMBOL	SAMPLE NO.	SAMPLERS	SAMPLER BLOW COUNT	LOCATION: See Plate 2 - Subsurface Exploration Plan N 1,982,564 E 6,055,891.4 CA State Plane, Zone V, NAD83 ft SURFACE EL: 60.1 ft +/- (rel. NAVD 88 datum)	UNIT WET WEIGHT, pcf	UNIT DRY WEIGHT, pcf	WATER CONTENT, %	% PASSING #200 SIEVE	LIQUID LIMIT, %	PLASTICITY INDEX, %	UNDRAINED SHEAR STRENGTH, S_u , ksf
						MATERIAL DESCRIPTION							
			8	(90/10.5)		- very dense							
-18	42												
-16	44					CLAYEY SAND (SC); dense; dark yellowish brown; moist; some fines; trace GRAVEL			17	28	24	15	
-14	46		9	X	29								
-12	48												
-10	50		10	X	ref/5.5'	SILTY SAND (SM); very dense; dark yellowish brown; moist; fine SAND; strong cementation; possible boulder - rig chatter from 51' to 54'							
-8	52												
-6	54												
-4	56		11a 11b	X	40	CLAYEY SAND (SC); thickly bedded with interbeds of lean CLAY (CL), SAND (SC); very dense; dark yellowish brown; very moist; mostly fine SAND; some coarse SAND. CLAY (CL); very stiff; mottled dark yellowish brown and pale brown; moist			21				
-2	58												
0	60		12a 12b	X	(67)	CLAYEY SAND (SC); very dense; dark yellowish brown; very moist; mostly fine SAND; some fines; trace coarse GRAVEL	134 136	114 113	17 20	42			u 2.2
-2	62												
-4	64												
-6	66		13	X	ref/4"	- wet; mostly fine SAND; some coarse SAND							
-8	68												
-10	70		14	X	50/5.5'	- moist; mostly fine to medium SAND			14				
-12	72												
-14	74					- loss of drilling fluid from 73' to 75'							
-16	76		15	X	(50/5")		131	111	18				
						Boring terminated at approximately 76 feet							
-18	78												

The log and data presented are a simplification of actual conditions encountered at the time of drilling at the drilled location. Subsurface conditions may differ at other locations and with the passage of time.

COMPLETION DEPTH: 76.0 ft
DEPTH TO WATER: Not Measured
BACKFILLED WITH: Cement Grout
DRILLING DATE: May 6, 2015

DRILLING METHOD: 4,875-inch-dia. Mud Rotary Wash
HAMMER TYPE: 140-lb Automatic Trip
DRILLED BY: SoCal Drilling
LOGGED BY: J. Martos
CHECKED BY: L.A. Berry
RIG TYPE: Meyhew 1000

LOG OF DRILL HOLE NO. DH-01
Montecito Street Bridge Replacement
Santa Barbara, California



ELEVATION, ft	DEPTH, ft	MATERIAL SYMBOL	SAMPLE NO.	SAMPLERS	SAMPLER BLOW COUNT	LOCATION: See Plate 2 - Subsurface Exploration Plan N 1,982,673 E 6,055,904.7 CA State Plane, Zone V, NAD83 ft SURFACE EL: 60.8 ft +/- (rel. NAVD 88 datum)	UNIT WET WEIGHT, pcf	UNIT DRY WEIGHT, pcf	WATER CONTENT, %	% PASSING #200 SIEVE	LIQUID LIMIT, %	PLASTICITY INDEX, %	UNDRAINED SHEAR STRENGTH, S_u , ksf
						MATERIAL DESCRIPTION							
						ASPHALT CONCRETE (4")							
						CONCRETE (6")							
						ARTIFICIAL FILL (af)							
						SILTY SAND (SM); medium dense; brown; moist; mostly fine SAND; pockets of yellow and white speckles							
60	2												
58	4												
56	6		1		(23)		99	89	11				
54	8												
52	10		2		13	ALLUVIUM (Qal) SILTY SAND (SM); medium dense; brown; moist; some fines			14	43			
50	12												
48	14					Poorly-graded GRAVEL with SAND (GP); medium dense; multicolored, red, grey and yellow; wet; slight rig chatter from 13' to 16'							
46	16		3		17								
44	18					SILTY SAND (SM); medium dense; brown; moist; fine SAND							
42	20		4		12				13	32	18	NP	
40	22												
38	24												
36	26		5		(29)		120	111	9				
34	28												
32	30		6		17	- yellow			13				
30	32												
28	34					OLDER ALLUVIUM (Qal) COBBLES and BOULDERS; SANDSTONE; dark yellowish brown; in a matrix of clayey SAND (SC); very dense; dark yellowish brown; very moist; mostly medium to coarse SAND; rig chatter at 32'							
26	36												
24	38		7		50/3"	- rig chatter and very hard drilling from 37.5' to 41'							
22													

The log and data presented are a simplification of actual conditions encountered at the time of drilling at the drilled location. Subsurface conditions may differ at other locations and with the passage of time.

COMPLETION DEPTH: 86.0 ft
 DEPTH TO WATER: Not Measured
 BACKFILLED WITH: Cement Grout
 DRILLING DATE: May 7, 2015

DRILLING METHOD: 4.875-inch-dia. Mud Rotary Wash
 HAMMER TYPE: 140-lb Automatic Trip
 DRILLED BY: SoCal Drilling
 LOGGED BY: J. Martos
 CHECKED BY: L.A. Berry
 RIG TYPE: Mayhew 1000

LOG OF DRILL HOLE NO. DH-02
 Montecito Street Bridge Replacement
 Santa Barbara, California



ELEVATION, ft	DEPTH, ft	MATERIAL SYMBOL	SAMPLE NO.	SAMPLERS	SAMPLER BLOW COUNT	LOCATION: See Plate 2 - Subsurface Exploration Plan N 1,982,673 E 6,055,904.7 CA State Plane, Zone V, NAD83 ft SURFACE EL: 60.8 ft +/- (rel. NAVD 88 datum)	UNIT WET WEIGHT, pcf	UNIT DRY WEIGHT, pcf	WATER CONTENT, %	% PASSING #200 SIEVE	LIQUID LIMIT, %	PLASTICITY INDEX, %	UNDRAINED SHEAR STRENGTH, S _u , ksf
MATERIAL DESCRIPTION													
-20	42		8		(36)	CLAYEY SAND (SC); medium dense; strong brown; very moist; fine SAND	136	114	19	49			u 1.0
-18	44												
-16	46												
-14	48												
-12	50		9		64	- very dense; moist			16				
-10	52					- rig chatter from 53' to 53.5'							
-8	54					SILTY SAND (SM); very dense; mottled strong brown and brown; very moist; some fines	131	108	21	49	21	4	
-6	56		10		(100)		135	118	15	49	21	4	
-4	58												
-2	60		11		45	- mostly fine SAND; trace coarse SAND			15				
0	62												
-2	64												
-4	66		12		ref/5.5)		140	124	13				
-6	68												
-8	70		13		67	- dark yellowish brown; moist; slightly clayey			17				
-10	72												
-12	74												
-14	76		14		77				19				
-16	78												
-18													

The log and data presented are a simplification of actual conditions encountered at the time of drilling at the drilled location. Subsurface conditions may differ at other locations and with the passage of time.

COMPLETION DEPTH: 86.0 ft
 DEPTH TO WATER: Not Measured
 BACKFILLED WITH: Cement Grout
 DRILLING DATE: May 7, 2015

DRILLING METHOD: 4,875-inch-dia. Mud Rotary Wash
 HAMMER TYPE: 140-lb Automatic Trip
 DRILLED BY: SoCal Drilling
 LOGGED BY: J. Martos
 CHECKED BY: L.A. Berry
 RIG TYPE: Mayhew 1000

LOG OF DRILL HOLE NO. DH-02
 Montecito Street Bridge Replacement
 Santa Barbara, California




ELEVATION, ft	DEPTH, ft	MATERIAL SYMBOL	SAMPLE NO.	SAMPLERS	SAMPLER BLOW COUNT	LOCATION: See Plate 2 - Subsurface Exploration Plan N 1,982,673 E 6,055,904.7 CA State Plane, Zone V, NAD83 ft SURFACE EL: 60.8 ft +/- (rel. NAVD 88 datum)	UNIT WET WEIGHT, pcf	UNIT DRY WEIGHT, pcf	WATER CONTENT, %	% PASSING #200 SIEVE	LIQUID LIMIT, %	PLASTICITY INDEX, %	UNDRAINED SHEAR STRENGTH, S_u , ksf
MATERIAL DESCRIPTION													
-20	82					CLAYEY SAND (SC); very dense; dark yellowish brown; moist; mostly fine SAND; some coarse to medium SAND							
-22	84												
-24	88		15	(50/5")		Boring terminated at approximately 86 feet	136	118	16				
-26	88												
-28	88												
-30	90												
-32	92												
-34	94												
-36	96												
-38	98												
-40	100												
-42	102												
-44	104												
-46	106												
-48	108												
-50	110												
-52	112												
-54	114												
-56	118												
-58	118												

The log and data presented are a simplification of actual conditions encountered at the time of drilling at the drilled location. Subsurface conditions may differ at other locations and with the passage of time.

COMPLETION DEPTH: 86.0 ft
 DEPTH TO WATER: Not Measured
 BACKFILLED WITH: Cement Grout
 DRILLING DATE: May 7, 2015

DRILLING METHOD: 4.875-inch-dia. Mud Rotary Wash
 HAMMER TYPE: 140-lb Automatic Trip
 DRILLED BY: SoCal Drilling
 LOGGED BY: J. Martos
 CHECKED BY: L A Berry
 RIG TYPE: Mayhew 1000

LOG OF DRILL HOLE NO. DH-02
 Montecito Street Bridge Replacement
 Santa Barbara, California



KEY TO TERMS & SYMBOLS USED ON LOGS




Laboratory Testing





DRILL HOLE	DEPTH, #	SAMPLE NUMBER	MATERIAL DESCRIPTION	U _w	W _u	M _D	M _C	FINES %	ATTERBERG LIMITS		COMPACTION TEST			DIRECT SHEAR			COMPRESSIVE STRENGTH TESTS			CORROSIIVITY TESTS					R-VALUE	EXPANSION INDEX	SAND EQUIVALENT (SE)	Specific Gravity
									LL	PI	MAX DD Pcf	OPT MC %	C ksf	PHI deg	Q _u ksf	S _h (Cell Pres.) ksf	R	pH	Cl	So ₄ (ppm)								
DH-01	5.0	1	Silty SAND (SM)	131	125	5																						
DH-01	10.0	2	Silty SAND (SM)			14																						
DH-01	15.5	3	Silty SAND (SM)	113	105	8	31						0.1	37														
DH-01	20.0	4	Silty SAND (SM)			13																						
DH-01	25.5	5	Silty SAND (SM)	125	113	11	34	19	1																			
DH-01	30.0	6	Silty SAND (SM)			20																						
DH-01	45.0	9	Clayey SAND (SC)			17	28	24	15																			
DH-01	56.0	11	Sandy CLAY (CL)			21																						
DH-01	60.5	12a	Clayey SAND (SC)	134	114	17	42																					
DH-01	61.0	12b	Clayey SAND (SC)	136	113	20																						
DH-01	70.0	14	Clayey SAND (SC)			14																						
DH-01	75.5	15	Clayey SAND (SC)	131	111	18																						
DH-02	5.0	1a	Silty SAND (SM)	99	89	11																						
DH-02	5.5	1b	Silty SAND (SM)																									
DH-02	10.0	2	Silty SAND (SM)			14	43																					
DH-02	20.0	4	Silty SAND (SM)			13	32	18	NP																			
DH-02	25.5	5a	Silty SAND (SM)	120	111	9																						
DH-02	30.0	6	Silty SAND (SM)			13																						
DH-02	42.5	8a	Clayey SAND (SC)	136	114	19	49																					
DH-02	50.0	9	Clayey SAND (SC)			16																						
DH-02	55.0	10a	Silty SAND (SM)	131	108	21																						
DH-02	56.0	10b	Silty SAND (SM)	135	118	15	49	21	4																			
DH-02	60.0	11	Silty SAND (SM)			15																						
DH-02	65.0	12	Silty SAND (SM)	140	124	13																						
DH-02	70.0	13	Silty SAND (SM)			17																						
DH-02	75.0	14	Silty SAND (SM)			19																						
DH-02	85.5	15	Clayey SAND (SC)	136	118	16																						


SUMMARY OF LABORATORY TEST RESULTS
 Montecito Street Bridge Replacement
 Santa Barbara, California



LEGEND		
	location	depth, ft
○	DH-01	25.5
●	DH-01	45.0
△	DH-02	20.0
▲	DH-02	56.0




CLASSIFICATION			ATTERBERG LIMITS TEST RESULTS		
			LIQUID LIMIT(LL)	PLASTIC LIMIT(PL)	PLASTICITY INDEX(PI)
	Silty SAND (SM)		19	18	1
	Clayey SAND (SC)		24	9	15
	Silty SAND (SM)		18	18	NP
	Silty SAND (SM)		21	17	4

PLASTICITY CHART
 Montecito Street Bridge Replacement
 Santa Barbara, California



SAMPLE ID	Boring, Sample #, Depth	DH-02 , #8b , 43.0 ft		SUMMARY	Preconsolidation Pressure, ksf	---
	USCS Classification:	Clayey SAND (SC): dark yellowish brown, moist			Inundation Increment, ksf	1.11
PROPERTIES		Initial	Final		Liquid Limit	---
	Water Content, %	18.1%	14.8%		Plastic Limit	---
	Dry Unit Weight, pcf	112.5	119.7		Plasticity Index	---
	Saturation, %	102%	103%		Passing #200	---
	Void Ratio	0.47	0.38		Estimated Gs	2.65
	Diameter, in	2.42	2.42		REMARKS	Test Method: D2435
Height, in	0.82	0.77				




CONSOLIDATION
 Montecito Street Bridge Replacement
 Santa Barbara, California



SAMPLE ID	Boring Number:	DH-01			
	Sample Number:	3a			
	Sample Depth:	15.5 ft			
	USCS Classification:	Silty SAND (SM): dark yellowish brown, moist			
INITIAL	Specimen	A	B	C	D
	Water Content, %	7.8%	7.8%	7.8%	
	Dry Unit Weight, pcf	105.8	104.8	105.8	
	Saturation, %	36%	36%	36%	
	Void Ratio	0.56	0.58	0.56	
	Diameter, in	2.42	2.42	2.42	
FINAL	Water Content, %	20.2%	20.1%	19.9%	
	Dry Unit Weight, pcf	107.6	107.8	104.0	
	Void Ratio	0.54	0.53	0.59	
TEST SUMMARY	Displacement at Peak, in	0.06	0.25	0.21	
	Displacement Rate, in/min	0.001	0.001	0.001	
	Normal Stress, ksf	0.9	1.8	3.6	
	Peak Shear Stress, ksf	0.83	1.48	2.83	
	Min. Post-Peak Stress, ksf	0.79	1.48	2.80	
	Test Method: ASTM D3080				
REMARKS					

CLASSIFICATION	Sieve Size	% Passing
	3/8-in. (9.5mm)	---
	#4 (4.75mm)	---
	#16 (1.18mm)	---
	#30 (0.6mm)	---
	#100 (0.150mm)	---
	#200 (0.075mm)	---
	Atterberg Limits	
	Liquid Limit, %	---
	Plastic Limit, %	---
Plasticity Index, %	---	
Estimated Gs	2.65	
k_{avg} 20°C, cm/sec	---	


DIRECT SHEAR TEST RESULTS
 Montecito Street Bridge Replacement
 Santa Barbara, California



SAMPLE ID	Boring Number:	DH-02			
	Sample Number:	5a			
	Sample Depth:	25.5 ft			
	USCS Classification:	Silty SAND (SM): dark yellowish brown, moist			
INITIAL	Specimen	A	B	C	D
	Water Content, %	8.9%	8.9%	8.9%	
	Dry Unit Weight, pcf	110.7	110.5	112.3	
	Saturation, %	48%	48%	50%	
	Void Ratio	0.49	0.50	0.47	
	Height, in	1.00	1.00	1.00	
FINAL	Water Content, %	17.7%	17.3%	16.1%	
	Dry Unit Weight, pcf	112.5	113.6	115.9	
	Void Ratio	0.47	0.46	0.43	
TEST SUMMARY	Displacement at Peak, in	0.05	0.24	0.26	
	Displacement Rate, in/min	0.001	0.001	0.001	
	Normal Stress, ksf	1.3	2.7	5.4	
	Peak Shear Stress, ksf	1.20	1.98	4.24	
	Min. Post-Peak Stress, ksf	1.10	1.97	4.24	
	Test Method: ASTM D3080				
REMARKS					

CLASSIFICATION	Sieve Size	% Passing
	3/8-in. (9.5mm)	---
	#4 (4.75mm)	---
	#16 (1.18mm)	---
	#30 (0.6mm)	---
	#100 (0.150mm)	---
	#200 (0.075mm)	---
Atterberg Limits		
Liquid Limit, %	---	
Plastic Limit, %	---	
Plasticity Index, %	---	
Estimated Gs	2.65	
k_{avg} 20°C, cm/sec	---	


DIRECT SHEAR TEST RESULTS
 Montecito Street Bridge Replacement
 Santa Barbara, California



SAMPLE ID	Boring Number: DH-01 Sample Number: 12b Sample Depth: 61.0 ft USCS Classification: Clayey SAND (SC): yellowish brown, moist		CLASSIFICATION	Sieve Size	% Passing	Other Parameters	
				3/8-in. (9.5mm)	---	Liquid Limit	---
SAMPLE PROPERTIES	Water Content, %	19.5%	TEST SUMMARY	#4 (4.75mm)	---	Plastic Limit	---
	Dry Unit Weight, pcf	113.4		#16 (1.18mm)	---	Plasticity Index	---
			REMARKS	#30 (0.6mm)	---	Estimated Gs	2.65
Saturation, %	113%			#100 (0.150mm)	---	S _u from T _v , ksf	---
Void Ratio	0.46		#200 (0.075mm)	---	S _u from PP, ksf	---	
Diameter, in	2.42						
Height, in	5.23		Maximum Deviator Stress, ksf	4.4			
			Undrained Shear Strength, ksf	2.2			
			Axial Strain at Failure, %	15.0			
			Strain Rate, %/min	0.7			
			Cell Pressure, ksf	4.3			
			Tested By:	JB			
			Date Tested:	5/13/15			
SAMPLE IMAGES			Test Method: ASTM 2850				


UNCONSOLIDATED, UNDRAINED TRIAXIAL TEST

Montecito Street Bridge Replacement
 Santa Barbara, California




SAMPLE ID	Boring Number: DH-02		CLASSIFICATION	Sieve Size	% Passing	Other Parameters	
	Sample Number: 8a			#4 (4.75mm)	--	Liquid Limit	---
Sample Depth: 42.5 ft		USCS Classification: Clayey SAND (SC): yellowish brown, moist	#16 (1.18mm)	--	Plastic Limit	---	
Sample Properties			#30 (0.6mm)	--	Plasticity Index	---	
Water Content, %		19.4%	#100 (0.150mm)	--	Estimated G _s	2.65	
Dry Unit Weight, pcf		114.0	#200 (0.075mm)	--	S _u from T _v , ksf	---	
Saturation, %		114%	TEST SUMMARY	Maximum Deviator Stress, ksf		2.0	
Void Ratio		0.45		Undrained Shear Strength, ksf		1.0	
Diameter, in		2.41	Axial Strain at Failure, %		15.0		
Height, in		5.12	Strain Rate, %/min		0.9		
SAMPLE IMAGES			Cell Pressure, ksf		3.3		
			Tested By:		JB		
REMARKS		Date Tested:		5/13/15			
		Test Method: ASTM 2850					

UNCONSOLIDATED, UNDRAINED TRIAXIAL TEST
 Montecito Street Bridge Replacement Project
 Santa Barbara, California



SAMPLE ID	Boring, Sample #, Depth	DH-01, #12a, 60.5 ft		SUMMARY	Preconsolidation Pressure, ksf	---
	USCS Classification:	Clayey SAND (SC): yellowish brown			Inundation Increment, ksf	1.11
PROPERTIES		Initial	Final	REMARKS	Liquid Limit	---
	Water Content, %	17.6%	13.4%		Plastic Limit	---
	Dry Unit Weight, pcf	113.8	120.7		Plasticity Index	---
	Saturation, %	103%	96%		Passing #200	---
	Void Ratio	0.45	0.37		Estimated Gs	2.65
	Diameter, in	2.42	2.42			
	Height, in	0.82	0.77			

CONSOLIDATION
 Montecito Street Bridge Replacement
 Santa Barbara, California





SAMPLE ID	Boring, Sample #, Depth		DH-02, #5b, 26.0 ft		SUMMARY	Preconsolidation Pressure, ksf	---
	USCS Classification:		Silty SAND (SM); yellowish brown			Inundation Increment, ksf	1.11
PROPERTIES		Initial	Final		REMARKS	Liquid Limit	---
	Water Content, %	11.1%	15.4%			Plastic Limit	---
	Dry Unit Weight, pcf	109.8	113.0			Plasticity Index	---
	Saturation, %	58%	88%			Passing #200	---
	Void Ratio	0.51	0.46			Estimated Gs	2.65
	Diameter, in	2.42	2.42				
	Height, in	0.82	0.80				

CONSOLIDATION
 Montecito Street Bridge Replacement
 Santa Barbara, California














Appendix C – Right of Way Exhibits






LEGEND

-  PERMANENT ACQUISITION EASEMENT
-  EXISTING FLOOD CONTROL EASEMENT
-  MAINTENANCE EASEMENT
-  NEW TOP OF CREEK EMBANKMENT
-  EXISTING TOP OF CREEK EMBANKMENT
-  NEW CHANNEL / WING WALL
-  EXISTING BRIDGE TO REMAIN IN PLACE
-  BRIDGE CURRENTLY UNDER DESIGN/ CONSTRUCTION
-  PROPOSED BRIDGE TO BE REPLACED
-  SYCAMORE CREEK (FEMA BASELINE)
-  PARCEL LINES (GIS DATA)

REACH 1 - POR LA MAR CIRCLE TO THE PACIFIC OCEAN
 SCALE: 1" = 40'

NOTES:

1. This exhibit shows the approximate area of parcels within the project limits. Parcel lines were created from GIS data and must be verified for final project configuration.
2. See Right of Way Maps in City Office for complete R/W information.



SYCAMORE CREEK PROJECT STUDY REPORT
RIGHT OF WAY MAPPING
REACH 1 - POR LA MAR CIRCLE TO THE PACIFIC OCEAN


 Bengal Engineering
 250 Big Sur Dr.
 Goleta, CA 93117

FOR REDUCED PLANS
 ORIGINAL SCALE IS IN INCHES

3/5/2018 3:20:43 PM





Bengal Engineering
250 Big Sur Dr.
Goleta, CA 93117

FOR REDUCED PLANS
ORIGINAL SCALE IS IN INCHES

3/5/2018 3:21:18 PM

SYCAMORE CREEK PROJECT STUDY REPORT
RIGHT OF WAY MAPPING
REACH 2 - PUNTA GORDA STREET TO POR LA MAR CIRCLE



LEGEND

	PERMANENT ACQUISITION EASEMENT
	EXISTING FLOOD CONTROL EASEMENT
	MAINTENANCE EASEMENT
	NEW TOP OF CREEK EMBANKMENT
	EXISTING TOP OF CREEK EMBANKMENT
	NEW CHANNEL / WING WALL
	EXISTING BRIDGE TO REMAIN IN PLACE
	BRIDGE CURRENTLY UNDER DESIGN/ CONSTRUCTION
	PROPOSED BRIDGE TO BE REPLACED
	SYCAMORE CREEK (FEMA BASELINE)
	PARCEL LINES (GIS DATA)
	PROPOSED MAINTENANCE ACCESS

REACH 2 - PUNTA GORDA STREET POR LA MAR CIRCLE
SCALE: 1" = 40'

- NOTES:**
1. This exhibit shows the approximate area of parcels within the project limits. Parcel lines were created from GIS data and must be verified for final project configuration.
 2. See Right of Way Maps in City Office for complete R/W information.







Bengal Engineering
250 Big Sur Dr.
Goleta, CA 93117

FOR REDUCED PLANS
ORIGINAL SCALE IS IN INCHES

3/5/2018 3:21:51 PM

SYCAMORE CREEK PROJECT STUDY REPORT
RIGHT OF WAY MAPPING
REACH 3 - CACIQUE STREET TO PUNTA GORDA STREET



LEGEND

	PERMANENT ACQUISITION EASEMENT
	EXISTING FLOOD CONTROL EASEMENT
	MAINTENANCE EASEMENT
	NEW TOP OF CREEK EMBANKMENT
	EXISTING TOP OF CREEK EMBANKMENT
	NEW CHANNEL / WING WALL
	EXISTING BRIDGE TO REMAIN IN PLACE
	BRIDGE CURRENTLY UNDER DESIGN/ CONSTRUCTION
	PROPOSED BRIDGE TO BE REPLACED
	SYCAMORE CREEK (FEMA BASELINE)
	PARCEL LINES (GIS DATA)
	PROPOSED MAINTENANCE ACCESS
	EXISTING MAINTENANCE ACCESS

REACH 3 - CACIQUE STREET TO PUNTA GORDA STREET
SCALE: 1" = 40'

NOTES:

1. This exhibit shows the approximate area of parcels within the project limits. Parcel lines were created from GIS data and must be verified for final project configuration.
2. See Right of Way Maps in City Office for complete R/W information.







Bengal Engineering
250 Big Sur Dr.
Goleta, CA 93117

FOR REDUCED PLANS
ORIGINAL SCALE IS IN INCHES

3/5/2018 3:22:26 PM

SYCAMORE CREEK PROJECT STUDY REPORT
RIGHT OF WAY MAPPING
REACH 4 - QUINIENTOS STREET TO CACIQUE STREET




LEGEND

	PERMANENT ACQUISITION EASEMENT
	EXISTING FLOOD CONTROL EASEMENT
	MAINTENANCE EASEMENT
	NEW TOP OF CREEK EMBANKMENT
	EXISTING TOP OF CREEK EMBANKMENT
	NEW CHANNEL / WING WALL
	EXISTING BRIDGE TO REMAIN IN PLACE
	BRIDGE CURRENTLY UNDER DESIGN/ CONSTRUCTION
	PROPOSED BRIDGE TO BE REPLACED
	SYCAMORE CREEK (FEMA BASELINE)
	PARCEL LINES (GIS DATA)
	PROPOSED MAINTENANCE ACCESS
	EXISTING MAINTENANCE ACCESS

REACH 4 - QUINIENTOS STREET TO CACIQUE STREET
SCALE: 1" = 40'

- NOTES:**
1. This exhibit shows the approximate area of parcels within the project limits. Parcel lines were created from GIS data and must be verified for final project configuration.
 2. See Right of Way Maps in City Office for complete R/W information.







Bengal Engineering
250 Big Sur Dr.
Goleta, CA 93117

FOR REDUCED PLANS
ORIGINAL SCALE IS IN INCHES

3/5/2018 3:23:04 PM

SYCAMORE CREEK PROJECT STUDY REPORT
RIGHT OF WAY MAPPING
REACH 5 - CITRUS AVENUE TO QUINIENTOS STREET




LEGEND

	PERMANENT ACQUISITION EASEMENT
	EXISTING FLOOD CONTROL EASEMENT
	MAINTENANCE EASEMENT
	NEW TOP OF CREEK EMBANKMENT
	EXISTING TOP OF CREEK EMBANKMENT
	NEW CHANNEL / WING WALL
	EXISTING BRIDGE TO REMAIN IN PLACE
	BRIDGE CURRENTLY UNDER DESIGN/ CONSTRUCTION
	PROPOSED BRIDGE TO BE REPLACED
	SYCAMORE CREEK (FEMA BASELINE)
	PARCEL LINES (GIS DATA)
	PROPOSED MAINTENANCE ACCESS
	EXISTING MAINTENANCE ACCESS

REACH 5 - CITRUS AVENUE TO QUINIENTOS STREET
SCALE: 1" = 40'

- NOTES:**
1. This exhibit shows the approximate area of parcels within the project limits. Parcel lines were created from GIS data and must be verified for final project configuration.
 2. See Right of Way Maps in City Office for complete RW information.






Bengal Engineering
250 Big Sur Dr.
Goleta, CA 93117

FOR REDUCED PLANS
ORIGINAL SCALE IS IN INCHES

3/5/2018 3:23:39 PM




LEGEND

	PERMANENT ACQUISITION EASEMENT
	EXISTING FLOOD CONTROL EASEMENT
	MAINTENANCE EASEMENT
	NEW TOP OF CREEK EMBANKMENT
	EXISTING TOP OF CREEK EMBANKMENT
	NEW CHANNEL / WING WALL
	EXISTING BRIDGE TO REMAIN IN PLACE
	BRIDGE CURRENTLY UNDER DESIGN/ CONSTRUCTION
	PROPOSED BRIDGE TO BE REPLACED
	SYCAMORE CREEK (FEMA BASELINE)
	PARCEL LINES (GIS DATA)
	PROPOSED MAINTENANCE ACCESS
	EXISTING MAINTENANCE ACCESS

REACH 6 - YANONALI STREET TO CITRUS AVENUE
SCALE: 1" = 40'

- NOTES:**
1. This exhibit shows the approximate area of parcels within the project limits. Parcel lines were created from GIS data and must be verified for final project configuration.
 2. See Right of Way Maps in City Office for complete R/W information.




SYCAMORE CREEK PROJECT STUDY REPORT
RIGHT OF WAY MAPPING
REACH 6 - YANONALI STREET TO CITRUS AVENUE





Appendix D – Channel Configuration Exhibits





LEGEND

	NEW TOP OF CREEK EMBANKMENT
	EXISTING TOP OF CREEK EMBANKMENT
	NEW CHANNEL / WING WALL
	EXISTING BRIDGE
	BRIDGE UNDER DESIGN/ CONSTRUCTION
	PROPOSED BRIDGE TO BE REPLACED
	SYCAMORE CREEK (FEMA BASELINE)
	PARCEL LINES (GIS DATA)



PACIFIC OCEAN TO POR LA MAR CIRCLE TYPICAL SECTION
SCALE: 1" = 20' H, 1" = 10' V

REACH 1- POR LA MAR CIRCLE TO PACIFIC OCEAN
SCALE: 1" = 40'



REACH NARRATIVE:

Cabrillo Blvd. to Por La Mar Circle Bridges

- The existing channel upstream of Cabrillo Blvd will have a variety of situations. The westerly side will require a channel wall parallel to Ninos Drive (west). On the Por La Mar (east) it would vary with wall placement where the creek bank lacks room to lay back the slope.
- Both of the existing three-span Por La Mar Circle bridges will be replaced with single-span bridges designed to accommodate the 3000 CFS target conveyance.




Bengal Engineering
250 Big Sur Dr.
Goleta, CA 93117


FOR REDUCED PLANS
ORIGINAL SCALE IS IN INCHES

SYCAMORE CREEK PROJECT STUDY REPORT
CREEK CONFIGURATION
REACH 2 - PUNTA GORDA ST. TO POR LA MAR CIRCLE

3/6/2018 11:25:31 AM





HWY 101 TO PUNTA GORDA ST. TYPICAL SECTION
SCALE: 1" = 20' H, 1" = 10' V




LEGEND


- NEW TOP OF CREEK EMBANKMENT
- EXISTING TOP OF CREEK EMBANKMENT
- NEW CHANNEL / WING WALL
- EXISTING BRIDGE
- BRIDGE UNDER DESIGN/ CONSTRUCTION
- PROPOSED BRIDGE TO BE REPLACED
- SYCAMORE CREEK (FEMA BASELINE)
- PARCEL LINES (GIS DATA)



REACH 2 - PUNTA GORDA ST. TO POR LA MAR CIRCLE
SCALE: 1" = 40'



POR LA MAR CIRCLE TO HWY 101 TYPICAL SECTION
SCALE: 1" = 20' H, 1" = 10' V



REACH NARRATIVE:

Por La Mar Circle to the Zoo Bridge


- The existing three-span "Zoo Bridge" will be replaced with a single-span bridge designed to accommodate the 3000 CFS target conveyance.
- The existing channel will require walls on the west to contain the target conveyance but could retain existing sloping vegetated banks.

UPRR to Hwy 101 Bridge

- The existing channel will remain in generally the current configuration. The channel will have retain the existing sloping vegetated banks.

Hwy 101 to Punta Gorda St. Bridge



- Proceeding upstream toward the Punta Gorda St. bridge, the channel cross section will transition from vegetated slopes to vertical channel walls because of nearby buildings which restrict the project footprint.
- The downstream portion of this reach, is wider to match the upstream side of the Hwy 101 bridge. Because of the wider existing 101 bridge an opportunity for landscaping may be available within the channel.



INDIO MUERTO ST. TO SOLEDAD ST. TYPICAL SECTION
SCALE: 1" = 20' H, 1" = 10' V

LEGEND

- NEW TOP OF CREEK EMBANKMENT
- EXISTING TOP OF CREEK EMBANKMENT
- NEW CHANNEL / WING WALL
- EXISTING BRIDGE
- BRIDGE UNDER DESIGN/ CONSTRUCTION
- PROPOSED BRIDGE TO BE REPLACED
- SYCAMORE CREEK (FEMA BASELINE)
- PARCEL LINES (GIS DATA)



REACH NARRATIVE:


Punta Gorda St. Bridge to Indio Muero St. Bridge

- The east bank will be supported by a vertical wall to reduce the project footprint because of nearby buildings and roads.
- The west bank will be supported by a vertical retaining wall from the Punta Gorda St. Bridge to near Liberty St. where the channel could transition to vegetated slope, which could then continue upstream to a new wall near the Indio Muero Bridge. Where required vertical walls would contain sloped embankments.

Indio Muero St. Bridge to Soledad St. Bridge





- The Indio Muero St. Bridge will be replaced to accommodate the target conveyance.
- This greater section presents some opportunity for vegetated channel slopes. Where required vertical walls would contain sloped embankments.

REACH 3 - CACIQUE ST. TO PUNTA GORDA ST.
SCALE: 1" = 40'





LIBERTY ST. TO INDIO MUERTO ST. TYPICAL SECTION
SCALE: 1" = 20' H, 1" = 10' V






CARPINTERIA ST. TO QUIENTOS ST. TYPICAL SECTION
SCALE: 1" = 20' H, 1" = 10' V



SOLEDAD ST. TO CARPINTERIA ST. TYPICAL SECTION
SCALE: 1" = 20' H, 1" = 10' V



REACH 4 - QUIENTOS ST. TO CACIQUE ST.
SCALE: 1" = 40'

REACH NARRATIVE:


Soledad St. to Carpinteria St. Bridge

- The channel between the two new pedestrian bridges at Cacique / Soledad Sts., and a portion of the channel about 100-feet upstream of Soledad St. will be widened to accommodate design flow.
- The channel upstream from this widening will be widened in specific location and replaced vegetated slopes.
- The Carpinteria St. Bridge will be replaced to accommodate design flows.


Carpinteria St. Bridge to Quientos St. Bridge

- The channel upstream of the Carpinteria St. Bridge will be left as-is with vegetated slopes.







MASON ST. TO CITRUS AVE. TYPICAL SECTION
SCALE: 1" = 20' H, 1" = 10' V




LEGEND


- NEW TOP OF CREEK EMBANKMENT
- EXISTING TOP OF CREEK EMBANKMENT
- NEW CHANNEL / WING WALL
- EXISTING BRIDGE
- BRIDGE UNDER DESIGN/ CONSTRUCTION
- PROPOSED BRIDGE TO BE REPLACED
- SYCAMORE CREEK (FEMA BASELINE)
- PARCEL LINES (GIS DATA)



REACH 5 - CITRUS AVE. TO QUIENTOS ST.
SCALE: 1" = 40'



QUIENTOS ST. TO MASON ST. TYPICAL SECTION
SCALE: 1" = 20' H, 1" = 10' V



REACH NARRATIVE:

Quientos St. Bridge to Mason St. Bridge

- Quientos St. Bridge will be replaced (anticipated for summer of 2019) to improve roadway safety
- The channel upstream of the Quientos St. Bridge will be left as-is with vegetated slopes
- The Mason St. Bridge (steel plate arch) should be replaced with a longer span bridge to convey design flows and improve roadway safety.

Mason St. Bridge to North End of Citrus Ave.

- Immediately upstream of the Mason Street Bridge a wall will be required to protect low elevations of the surrounding ground.
- The existing channel upstream of Mason Street bridge will remain with vegetated slopes.





Bengal Engineering
250 Big Sur Dr.
Goleta, CA 93117

FOR REDUCED PLANS
ORIGINAL SCALE IS IN INCHES



SYCAMORE CREEK PROJECT STUDY REPORT
CREEK CONFIGURATION
REACH 6 - YANONALI ST. TO CITRUS AVE.

LEGEND

- NEW TOP OF CREEK EMBANKMENT
- EXISTING TOP OF CREEK EMBANKMENT
- NEW CHANNEL / WING WALL
- EXISTING BRIDGE
- BRIDGE UNDER DESIGN/ CONSTRUCTION
- PROPOSED BRIDGE TO BE REPLACED
- SYCAMORE CREEK (FEMA BASELINE)
- PARCEL LINES (GIS DATA)



DOWNSTREAM OF YANONALI ST. BRIDGE TYPICAL SECTION
SCALE: 1" = 20' H, 1" = 10' V




REACH 6 - YANONALI ST. TO CITRUS AVE.
SCALE: 1" = 40'


REACH NARRATIVE:

North End of Citrus Ave. to Alameda Padre Serra

- The existing channel upstream of the north end of Citrus Ave. will remain with vegetated slopes.
- Downstream of the new Yanonali Bridge walls will be required to protect low surrounding elevations.
- The Yanonali Bridge is proposed to be replaced in 2018. The replacement of the bridge appear to improve conditions to reduce the need for channel improvements.



CITRUS AVE. TO YANONALI ST. TYPICAL SECTION
SCALE: 1" = 20' H, 1" = 10' V





Appendix E – Project Costs



**Sycamore Creek
Project Study Report
Engineer's Estimate Summary**



	%	Quantity	Unit	Unit rate	Cost
1 Earthwork					
Subtotal Earthwork					\$1,163,050
a. Earthwork price reflect confined area and limited production. It is assumed fill of borrow can be reprocessed from excavate materials.					
2 Pavement Structural Section					
Subtotal Pavement Structural Section					\$70,300
a. Asphalt prices are costly and can fluctuate more than other materials. Staging and limited production will increase unit cost of base and paving substantially.					
3 Drainage (Modify Existing Drainage + new)					
Subtotal Drainage					\$248,000
Estimated drainage.					
4 Specialty Items					
Subtotal Specialty Items					\$8,119,420
a. Retaining wall costs can vary extensively do to complexity of structure and façade treatments.					
	%	Quantity	Unit	Unit rate	Cost
5 Traffic Items					
Subtotal Traffic Items					\$174,000
Subtotal Items 1 through 5					\$9,774,770
6 Minor Items	20%				\$1,954,954
7 Mobilization	20%				\$2,345,945
8a Supplemental Work	20%				\$2,345,945
8b Contingency	20%				\$2,345,945
8 Subtotal - Channel Improvements					\$18,767,558
9 Structures Items					
Bridge Structures	na	LS	LS	LS	\$32,300,000
Structures - Mobilization	10%				\$3,230,000
Structures - Contingency	10%				\$3,553,000
Railroad Related Costs	na	LS	LS	LS	\$100,000
Subtotal Structures Items (STS cost + 5%)					\$41,142,150
Subtotal Construction					\$53,102,246
10 Utility Reloc (Budget)					
Subtotal Utilities					\$600,000
11 Env Mitigation (Structure) (budget)	na	LS	LS	LS	
Subtotal Environmental Mitigation Structure.					\$1,000,000
12 Right of Way					
Permanent 'Creek' (Budget)		70,740	SF	\$10	\$707,400
Permanent 'Developable' (Budget)		20,175	SF	\$55	\$1,109,636
Permanent 'Maintenance' (Budget)		16,310	SF	\$35	\$570,850
TCE			LS	LS	\$300,000
Subtotal - R/W					\$2,687,886
Right of Way costs are very rough "place holders". Total Capital =Items "Subtotal Construction"+9+10+11+12					
Total Capital--Construction Cost					\$76,157,691

Sycamore Creek
 Project Study Report
 Engineer's Estimate - Reach 1- Por La Mar to Pacific Ocean



	%	Quantity	Unit	Unit rate	Cost
1 Earthwork					
Channel Excavation (see "a" below):	na	4,100	CY	\$ 35	\$143,500
Clear and Grubbing (not incl. bridge removals)	na	LS	LS	\$25,000	\$25,000
Remove existing AC and C&G	na	1,650	SF	\$5	\$8,250
Develop Water Supply	na	LS	LS	LS	\$10,000
Subtotal Earthwork					\$186,750

a. Earthwork price reflect confined area and limited production. It is assumed fill of borrow can be reprocessed from excavate materials.

2 Pavement Structural Section					
Asphalt Pavement (HMA) (see "a" below)	na	30	TON	\$300	\$9,000
Aggregate Base	na	70	CY	\$70	\$4,900
Subtotal Pavement Structural Section					\$13,900

a. Asphalt prices are costly and can fluctuate more than other materials. Staging and limited production will increase unit cost of base and paving substantially.

3 Drainage (Modify Existing Drainage + new)					
Drop Inlets ("Plain" DI's; No Special Filtering)	na	2	EA	\$20,000	\$40,000
Storm Drain (24" RCP, Class III)	na	100	LF	\$120	\$12,000
Subtotal Drainage					\$52,000

Estimated drainage

4 Specialty Items					
Bridge Removals	na	2	LS	LS	\$80,000
Retaining Walls (None: Assume Slopes are feasible)	na	700	LF	\$1,200	\$840,000
Minor Concrete (Curb and Gutter)	na	750	LF	\$30	\$22,500
Minor Concrete (Sidewalk)	na	360	SF	\$15	\$5,400
Minor Concrete (Cross gutter)	na	375	SF	\$20	\$7,500
Highway Planting (not Restoration)	na	LS	LS	LS	\$15,000
Landscape Restoration Planting	na	LS	LS	LS	\$25,000
Erosion Control	na	LS	LS	LS	\$7,000
Rock Slope/Scour Protection (budget figure)	na	LS	LS	LS	\$70,000
Water Pollution Control (prepare & implement)	na	LS	LS	LS	\$30,000
Cofferdam and Water Diversion	na	LS	LS	LS	\$260,000
Hazardous Waste Mitigation work (unknown)	na	0	na	\$0	\$0
Environmental Mitigation (budget figure)	na	LS	LS	LS	\$200,000
Permeant Fencing	na	0	na	LS	\$50,000
APE/ESA temporary Fencing	na	LS	LS	LS	\$25,000
Mitigation: Cultural Resources	na	LS	LS	LS	\$50,000
Subtotal Specialty Items					\$1,687,400

a. Retaining wall costs can vary extensively do to complexity of structure and façade treatments.

page 1

	%	Quantity	Unit	Unit rate	Cost
5 Traffic Items					
Roadside Signs	LS	1	LS	LS	\$5,000
Traffic Control System (Detours)	na	LS	LS	LS	\$35,000
Subtotal Traffic Items					\$40,000

Subtotal Items 1 through 5					\$1,980,050
-----------------------------------	--	--	--	--	--------------------

6 Minor Items	20%				\$396,010
----------------------	-----	--	--	--	------------------

7 Mobilization	20%				\$475,212
-----------------------	-----	--	--	--	------------------

8a Supplemental Work	20%				\$475,212
-----------------------------	-----	--	--	--	------------------

8b Contingency	20%				\$475,212
-----------------------	-----	--	--	--	------------------

8 Subtotal - Channel Improvements					\$3,801,696
--	--	--	--	--	--------------------

9 Structures Items					
Bridge Structures (2 x Por La Mar Cir.)	na	LS	LS	LS	\$9,000,000
Structures - Mobilization	10%				\$900,000
Structures - Contingency	10%				\$990,000
Railroad Related Costs	na	LS	LS	LS	\$0
Subtotal Structures Items (STS cost + 5%)					\$11,434,500

Subtotal Construction					\$12,801,696
------------------------------	--	--	--	--	---------------------

10 Utility Reloc (Budget)					
Utilities Exist On site: This budget is for City-Owned					
Relocate City Water	na	LS	LS	LS	\$100,000
Relocate City Sewer	na	LS	LS	LS	\$100,000
Verizon, Cox, Gas- Relocation cost paid by others					\$0
Subtotal Utilities					\$200,000

11 Env Mitigation (Structure) (budget)	na	LS	LS	LS	
Subtotal Environmental Mitigation Structure.					\$250,000

12 Right of Way					
Permanent 'Creek' (Budget)		0	SF	\$10	\$0
Permanent 'Developable' (Budget)		0	SF	\$55	\$0
Permanent 'Maintenance' (Budget)		0	SF	\$35	\$0
TCE (Budget)		LS	LS	LS	\$50,000
Subtotal - R/W					\$50,000

Right of Way costs are very rough "place holders".

Total Capital =Items "Subtotal Construction"+9+10+11+12

Total Capital--Construction Cost					\$17,103,392
---	--	--	--	--	---------------------

Sycamore Creek
 Project Study Report
 Engineer's Estimate - Reach 2 - Punta Gorda to Por La Mar



	%	Quantity	Unit	Unit rate	Cost
1 Earthwork					
Channel Excavation (see "a" below):	na	3,600	CY	\$ 35	\$126,000
Clear and Grubbing (not incl. bridge removals)	na	LS	LS	\$25,000	\$25,000
Remove existing AC and C&G	na	360	SF	\$5	\$1,800
Develop Water Supply	na	LS	LS	LS	\$10,000
Subtotal Earthwork					\$162,800

a. Earthwork price reflect confined area and limited production.

2 Pavement Structural Section					
Asphalt Pavement (HMA) (see "a" below)	na	10	TON	\$300	\$3,000
Aggregate Base	na	20	CY	\$70	\$1,400
Subtotal Pavement Structural Section					\$4,400

a. Asphalt prices are costly and can fluctuate more than other materials. Staging and limited production will increase unit cost of base and paving substantially.

3 Drainage (Modify Existing Drainage + new)					
Drop Inlets ("Plain" D's; No Special Filtering)	na	2	EA	\$20,000	\$40,000
Storm Drain (24" RCP, Class III)	na	100	LF	\$120	\$12,000
Subtotal Drainage					\$52,000

Estimated drainage

4 Specialty Items					
Bridge Removal	na	LS	LS	LS	\$40,000
Retaining Walls (None: Assume Slopes are feasible)	na	950	LF	\$1,200	\$1,140,000
Minor Concrete (Curb and Gutter)	na	120	LF	\$30	\$3,600
Minor Concrete (Sidewalk)	na	480	SF	\$18	\$8,640
Highway Planting (not Restoration)	na	LS	LS	LS	\$20,000
Landscape Restoration Planting	na	LS	LS	LS	\$40,000
Erosion Control	na	LS	LS	LS	\$10,000
Rock Slope/Scour Protection (budget figure)	na	LS	LS	LS	\$100,000
Water Pollution Control (prepare & implement)	na	LS	LS	LS	\$30,000
Cofferdam and Water Diversion	na	LS	LS	LS	\$200,000
Hazardous Waste Mitigation work (unknown)	na	0	na	\$0	\$0
Environmental Mitigation (budget figure)	na	LS	LS	LS	\$200,000
Permeant Fencing	na	0	na	LS	\$50,000
APE/ESA temporary Fencing	na	LS	LS	LS	\$25,000
Mitigation: Cultural Resources	na	LS	LS	LS	\$50,000
Subtotal Specialty Items					\$1,917,240

	%	Quantity	Unit	Unit rate	Cost
5 Traffic Items					
Roadside Signs	LS	1	LS	LS	\$5,000
Traffic Control System (Detours)	na	LS	LS	LS	\$35,000
Subtotal Traffic Items					\$40,000

Subtotal Items 1 through 5					\$2,176,440
-----------------------------------	--	--	--	--	--------------------

6 Minor Items	20%				\$435,288
----------------------	-----	--	--	--	------------------

7 Mobilization	20%				\$522,346
-----------------------	-----	--	--	--	------------------

8a Supplemental Work	20%				\$522,346
-----------------------------	-----	--	--	--	------------------

8b Contingency	20%				\$522,346
-----------------------	-----	--	--	--	------------------

8 Subtotal - Channel Improvements					\$4,178,765
--	--	--	--	--	--------------------

9 Structures Items					
Bridge Structure (S.B. Zoo)	na	LS	LS	LS	\$5,000,000
Subtotal					\$5,000,000
Structures - Mobilization	10%				\$500,000
Structures - Contingency	10%				\$550,000
Railroad Related Costs	na	LS	LS	LS	\$100,000
Subtotal Structures Items (STS cost + 5%)					\$6,457,500

Subtotal Construction					\$9,178,765
------------------------------	--	--	--	--	--------------------

10 Utility Reloc (Budget)					
Utilities Exist On site: This budget is for City-Owned					
Relocate City Water	na	LS	LS	LS	\$100,000
Relocate City Sewer	na	LS	LS	LS	\$100,000
Verizon, Cox, Gas- Relocation cost paid by others					\$0
Subtotal Utilities					\$200,000

11 Env Mitigation (Structure) (budget)	na	LS	LS	LS	
Subtotal Environmental Mitigation Structure.					\$250,000

12 Right of Way					
Permanent 'Creek' (Budget)		4,200	SF	\$10	\$42,000
Permanent 'Developable' (Budget)		0	SF	\$55	\$0
Permanent 'Maintenance' (Budget)		3,800	SF	\$35	\$133,000
TCE (Budget)		LS	LS	LS	\$50,000
Subtotal - R/W					\$225,000

Right of Way costs are very rough "place holders".

Total Capital =Items "Subtotal Construction"+9+10+11+12

Total Capital--Construction Cost					\$14,032,530
---	--	--	--	--	---------------------

Sycamore Creek
Project Study Report
Engineer's Estimate - Reach 3 - Cacique to Punta Gorda



	%	Quantity	Unit	Unit rate	Cost
1 Earthwork					
Channel Excavation (see "a" below)	na	14,000	CY	\$ 30	\$420,000
Clear and Grubbing (not incl. bridge removals)	na	LS	LS	\$40,000	\$40,000
Remove existing AC and C&G	na	100	SF	\$5	\$500
Remove existing creek walls/concrete slopes	na	LS	LS	LS	\$25,000
Develop Water Supply	na	LS	LS	LS	\$10,000
Subtotal Earthwork					\$495,500

a. Earthwork price reflect confined area and limited production.

2 Pavement Structural Section					
Asphalt Pavement (HMA) (see "a" below)	na	10	TON	\$300	\$3,000
Aggregate Base	na	20	CY	\$70	\$1,400
Subtotal Pavement Structural Section					\$4,400

a. Asphalt prices are costly and can fluctuate more than other materials. Staging and limited production will increase unit cost of base and paving substantially.

3 Drainage (Modify Existing Drainage + new)					
Drop Inlets ("Plain" DI's; No Special Filtering)	na	2	EA	\$20,000	\$40,000
Storm Drain (24" RCP, Class III)	na	100	LF	\$120	\$12,000
Subtotal Drainage					\$52,000

Estimated drainage

4 Specialty Items					
Bridge Removal	na	LS	LS	LS	\$40,000
Pedestrian Bridge Removal	na	LS	LS	LS	\$10,000
Retaining Walls (None; Assume Slopes are feasible)	na	1,057	LF	\$1,200	\$1,268,400
Minor Concrete (Curb and Gutter)	na	130	LF	\$30	\$3,900
Minor Concrete (Sidewalk)	na	360	SF	\$18	\$6,480
Highway Planting (not Restoration)	na	LS	LS	LS	\$20,000
Landscape Restoration Planting	na	LS	LS	LS	\$80,000
Erosion Control	na	LS	LS	LS	\$20,000
Rock Slope/Scour Protection (budget figure)	na	LS	LS	LS	\$240,000
Water Pollution Control (prepare & implement)	na	LS	LS	LS	\$30,000
Cofferdam and Water Diversion	na	LS	LS	LS	\$120,000
Hazardous Waste Mitigation work (unknown)	na	0	na	\$0	\$0
Environmental Mitigation (budget figure)	na	LS	LS	LS	\$200,000
Permeant Fencing	na	0	na	LS	\$50,000
APE/ ESA temporary Fencing	na	LS	LS	LS	\$25,000
Mitigation: Cultural Resources	na	LS	LS	LS	\$50,000
Subtotal Specialty Items					\$2,163,780

	%	Quantity	Unit	Unit rate	Cost
5 Traffic Items					
Roadside Signs	LS	1	LS	LS	\$2,000
Traffic Control System (Detours)	na	LS	LS	LS	\$25,000
Subtotal Traffic Items					\$27,000

Subtotal Items 1 through 5					\$2,742,680
-----------------------------------	--	--	--	--	--------------------

6 Minor Items	20%				\$548,536
----------------------	-----	--	--	--	------------------

7 Mobilization	20%				\$658,243
-----------------------	-----	--	--	--	------------------

8a Supplemental Work	20%				\$658,243
-----------------------------	-----	--	--	--	------------------

8b Contingency	20%				\$658,243
-----------------------	-----	--	--	--	------------------

8 Subtotal - Channel Improvements					\$5,265,946
--	--	--	--	--	--------------------

9 Structures Items					
Bridge Structure (Indio Muerto St.)	na	LS	LS	LS	\$5,500,000
Subtotal					\$5,500,000
Structures - Mobilization	10%				\$550,000
Structures - Contingency	10%				\$605,000
Railroad Related Costs	na	LS	LS	LS	\$0
Subtotal Structures Items (STS cost + 5%)					\$6,987,750

Subtotal Construction					\$10,765,946
------------------------------	--	--	--	--	---------------------

10 Utility Reloc (Budget)					
Utilities Exist On site: This budget is for City-Owned					
Relocate City Water	na	LS	LS	LS	\$100,000
Relocate City Sewer	na	LS	LS	LS	\$100,000
Verizon, Cox, Gas- Relocation cost paid by others					\$0
Subtotal Utilities					\$200,000

11 Env Mitigation (Structure) (budget)	na	LS	LS	LS	
Subtotal Environmental Mitigation Structure.					\$250,000

12 Right of Way					
Permanent 'Creek' (Budget)		47,640	SF	\$10	\$476,400
Permanent 'Developable' (Budget)		8,575	SF	\$55	\$471,636
Permanent 'Maintenance' (Budget)		6,610	SF	\$35	\$231,350
TCE (Budget)		LS	LS	LS	\$50,000
Subtotal - R/W					\$1,229,386

Right of Way costs are very rough "place holders"

Total Capital =Items "Subtotal Construction"+9+10+11+12

Total Capital--Construction Cost					\$17,711,277
---	--	--	--	--	---------------------

Sycamore Creek
 Project Study Report
 Engineer's Estimate - Reach 4 - Quinientos to Cacique



	%	Quantity	Unit	Unit rate	Cost
1 Earthwork					
Channel Excavation (see "a" below)	na	2,300	CY	\$ 40	\$92,000
Clear and Grubbing (not incl. bridge removals)	na	LS	LS	\$40,000	\$40,000
Remove existing AC and C&G	na	100	SF	\$5	\$0
Remove existing creek walls/concrete slopes	na	LS	LS	LS	\$25,000
Develop Water Supply	na	LS	LS	LS	\$0
Subtotal Earthwork					\$157,000

a. Earthwork price reflect confined area and limited production.

2 Pavement Structural Section					
Asphalt Pavement (HMA) (see "a" below)	na	0	TON	\$300	\$0
Aggregate Base	na	0	CY	\$70	\$0
Subtotal Pavement Structural Section					\$0

a Asphalt prices are costly and can fluctuate more than other materials. Staging and limited production will increase unit cost of base and paving substantially.

3 Drainage (Modify Existing Drainage + new)					
Drop Inlets ("Plain" DI's; No Special Filtering)	na	0	EA	\$20,000	\$0
Storm Drain (24" RCP, Class III)	na	0	LF	\$120	\$0
Subtotal Drainage					\$0

Estimated drainage

4 Specialty Items					
Bridge Removal	na	LS	LS	LS	\$40,000
Pedestrian Bridge Removal	na	LS	LS	LS	\$0
Retaining Walls (None; Assume Slopes are feasible)	na	0	LF	\$1,200	\$0
Minor Concrete (Curb and Gutter)	na	0	LF	\$30	\$0
Minor Concrete (Sidewalk)	na	0	SF	\$18	\$0
Highway Planting (not Restoration)	na	LS	LS	LS	\$0
Landscape Restoration Planting	na	LS	LS	LS	\$50,000
Erosion Control	na	LS	LS	LS	\$12,000
Rock Slope/Scour Protection (budget figure)	na	LS	LS	LS	\$120,000
Water Pollution Control (prepare & implement)	na	LS	LS	LS	\$10,000
Cofferdam and Water Diversion	na	LS	LS	LS	\$80,000
Hazardous Waste Mitigation work (unknown)	na	0	na	\$0	\$0
Environmental Mitigation (budget figure)	na	LS	LS	LS	\$200,000
Permanent Fencing	na	0	na	LS	\$0
APE/ ESA temporary Fencing	na	LS	LS	LS	\$0
Mitigation: Cultural Resources	na	LS	LS	LS	\$0
Subtotal Specialty Items					\$512,000

page 1

	%	Quantity	Unit	Unit rate	Cost
5 Traffic Items					
Roadside Signs	LS	1	LS	LS	\$2,000
Traffic Control System (Detours)	na	LS	LS	LS	\$25,000
Subtotal Traffic Items					\$27,000

Subtotal Items 1 through 5					\$696,000
-----------------------------------	--	--	--	--	------------------

6 Minor Items	20%				\$139,200
----------------------	-----	--	--	--	------------------

7 Mobilization	20%				\$167,040
-----------------------	-----	--	--	--	------------------

8a Supplemental Work	20%				\$167,040
-----------------------------	-----	--	--	--	------------------

8b Contingency	20%				\$167,040
-----------------------	-----	--	--	--	------------------

8 Subtotal - Channel Improvements					\$1,336,320
--	--	--	--	--	--------------------

9 Structures Items					
Bridge Structure (Carpinteria St.)	na	LS	LS	LS	\$6,400,000
Subtotal					\$6,400,000
Structures - Mobilization	10%				\$640,000
Structures - Contingency	10%				\$704,000
Railroad Related Costs	na	LS	LS	LS	\$0
Subtotal Structures Items (STS cost + 5%)					\$8,131,200

Subtotal Construction					\$8,131,200
------------------------------	--	--	--	--	--------------------

10 Utility Reloc (Budget)					
Utilities Exist On site: This budget is for City-Owned					
Relocate City Water	na	LS	LS	LS	\$0
Relocate City Sewer	na	LS	LS	LS	\$0
Verizon, Cox, Gas- Relocation cost paid by others					\$0
Subtotal Utilities					\$0

11 Env Mitigation (Structure) (budget)	na	LS	LS	LS	
Subtotal Environmental Mitigation Structure.					\$250,000

12 Right of Way					
Permanent 'Creek' (Budget)		11,400	SF	\$10	\$114,000
Permanent 'Developable' (Budget)		7,600	SF	\$55	\$418,000
Permanent 'Maintenance' (Budget)			SF	\$35	\$0
TCE (Budget)		LS	LS	LS	\$50,000
Subtotal - R/W					\$582,000

Right of Way costs are very rough "place holders"

Total Capital =Items "Subtotal Construction"+9+10+11+12

Total Capital--Construction Cost					\$10,299,520
---	--	--	--	--	---------------------

Sycamore Creek
 Project Study Report
 Engineer's Estimate - Reach 5 - Citrus to Quinientos



	%	Quantity	Unit	Unit rate	Cost
1 Earthwork					
Channel Excavation (see "a" below):	na	300	CY	\$ 10	\$3,000
Clear and Grubbing (not incl. bridge removals)	na	LS	LS	\$40,000	\$40,000
Remove existing AC and C&G	na	100	SF	\$5	\$0
Remove existing creek walls/concrete slopes	na	LS	LS	LS	\$30,000
Develop Water Supply	na	LS	LS	LS	\$0
Subtotal Earthwork					\$73,000

a. Earthwork price reflect confined area and limited production.

2 Pavement Structural Section					
Asphalt Pavement (HMA) (see "a" below)	na	0	TON	\$300	\$0
Aggregate Base	na	0	CY	\$70	\$0
Subtotal Pavement Structural Section					\$0

a. Asphalt prices are costly and can fluctuate more than other materials. Staging and limited production will increase unit cost of base and paving substantially.

3 Drainage (Modify Existing Drainage + new)					
Drop Inlets ("Plain" DI's; No Special Filtering)	na	0	EA	\$20,000	\$0
Storm Drain (24" RCP, Class III)	na	0	LF	\$120	\$0
Subtotal Drainage					\$0

Estimated drainage

4 Specialty Items					
Retaining Walls (None: Assume Slopes are feasible)	na	120	LF	\$1,200	\$144,000
Minor Concrete (Curb and Gutter)	na	0	LF	\$30	\$0
Minor Concrete (Sidewalk)	na	0	SF	\$18	\$0
Highway Planting (not Restoration)	na	LS	LS	LS	\$0
Landscape Restoration Planting	na	LS	LS	LS	\$10,000
Erosion Control	na	LS	LS	LS	\$10,000
Rock Slope/Scour Protection (budget figure)	na	LS	LS	LS	\$20,000
Water Pollution Control (prepare & implement)	na	LS	LS	LS	\$15,000
Hazardous Waste Mitigation work (unknown)	na	0	na	\$0	\$0
Environmental Mitigation (budget figure)	na	LS	LS	LS	\$200,000
Permanent Fencing	na	0	na	LS	\$15,000
APE/ ESA temporary Fencing	na	LS	LS	LS	\$0
Mitigation: Cultural Resources	na	LS	LS	LS	\$0
Subtotal Specialty Items					\$414,000

	%	Quantity	Unit	Unit rate	Cost
5 Traffic Items					
Roadside Signs	LS	1	LS	LS	\$1,000
Traffic Control System (Detours)	na	LS	LS	LS	\$12,000
Subtotal Traffic Items					\$13,000

Subtotal Items 1 through 5					\$500,000
-----------------------------------	--	--	--	--	------------------

6 Minor Items	20%				\$100,000
----------------------	-----	--	--	--	------------------

7 Mobilization	20%				\$120,000
-----------------------	-----	--	--	--	------------------

8a Supplemental Work	20%				\$120,000
-----------------------------	-----	--	--	--	------------------

8b Contingency	20%				\$120,000
-----------------------	-----	--	--	--	------------------

8 Subtotal - Channel Improvements					\$960,000
--	--	--	--	--	------------------

9 Structures Items					
Bridge Structure (Mason St.)	na	LS	LS	LS	\$6,400,000
Subtotal					\$6,400,000
Structures - Mobilization	10%				\$640,000
Structures - Contingency	10%				\$704,000
Railroad Related Costs	na	LS	LS	LS	\$0
Subtotal Structures Items (STS cost + 5%)					\$8,131,200

Subtotal Construction					\$9,091,200
------------------------------	--	--	--	--	--------------------

10 Utility Reloc (Budget)					
Utilities Exist On site: This budget is for City-Owned					
Relocate City Water	na	LS	LS	LS	
Relocate City Sewer	na	LS	LS	LS	
Verizon, Cox, Gas- Relocation cost paid by others					\$0
Subtotal Utilities					\$0

11 Env Mitigation (Structure) (budget)	na	LS	LS	LS	
Subtotal Environmental Mitigation Structure.					\$0

12 Right of Way					
Permanent 'Creek' (Budget)		3,000	SF	\$10	\$30,000
Permanent 'Developable' (Budget)		1,000	SF	\$55	\$55,000
Permanent 'Maintenance' (Budget)		1,100	SF	\$35	\$38,500
TCE (Budget)		LS	LS	LS	\$50,000
Subtotal - R/W					\$173,500

Right of Way costs are very rough "place holders".
 Total Capital = Items "Subtotal Construction"+9+10+11+12

Total Capital--Construction Cost					\$10,224,700
---	--	--	--	--	---------------------

Sycamore Creek
 Project Study Report
 Engineer's Estimate - Reach 6 - Yanonali to Citrus



	%	Quantity	Unit	Unit rate	Cost
1 Earthwork					
Channel Excavation (see "a" below):	na	1,200	CY	\$ 40	\$48,000
Clear and Grubbing (not incl. bridge removals)	na	LS	LS	\$40,000	\$40,000
Remove existing AC and C&G	na	100	SF	\$5	\$0
Remove existing creek walls/concrete slopes	na	LS	LS	LS	\$0
Develop Water Supply	na	LS	LS	LS	\$0
Subtotal Earthwork					\$88,000

a. Earthwork price reflect confined area and limited production.

2 Pavement Structural Section					
Asphalt Pavement (HMA) (see "a" below)	na	0	TON	\$300	\$0
Aggregate Base	na	0	CY	\$70	\$0
Subtotal Pavement Structural Section					\$0

a. Asphalt prices are costly and can fluctuate more than other materials. Staging and limited production will increase unit cost of base and paving substantially.

3 Drainage (Modify Existing Drainage + new)					
Drop Inlets ("Plain" DI's; No Special Filtering)	na	4	EA	\$20,000	\$80,000
Storm Drain (24" RCP, Class III)	na	100	LF	\$120	\$12,000
Subtotal Drainage					\$92,000

Estimated drainage

4 Specialty Items					
Bridge Removal	na	LS	LS	LS	\$0
Pedestrian Bridge Removal	na	LS	LS	LS	\$0
Retaining Walls (None: Assume Slopes are feasible)	na	750	LF	\$1,200	\$900,000
Minor Concrete (Curb and Gutter)	na	0	LF	\$30	\$0
Minor Concrete (Sidewalk)	na	0	SF	\$18	\$0
Highway Planting (not Restoration)	na	LS	LS	LS	\$0
Landscape Restoration Planting	na	LS	LS	LS	\$35,000
Erosion Control	na	LS	LS	LS	\$15,000
Rock Slope/Scour Protection (budget figure)	na	LS	LS	LS	\$100,000
Water Pollution Control (prepare & implement)	na	LS	LS	LS	\$15,000
Cofferdam and Water Diversion	na	LS	LS	LS	\$80,000
Hazardous Waste Mitigation work (unknown)	na	0	na	\$0	\$0
Environmental Mitigation (budget figure)	na	LS	LS	LS	\$200,000
Permenant Fencing	na	0	na	LS	\$80,000
APE/ ESA temporary Fencing	na	LS	LS	LS	\$0
Mitigation: Cultural Resources	na	LS	LS	LS	\$0
Subtotal Specialty Items					\$1,425,000

page 1

	%	Quantity	Unit	Unit rate	Cost
5 Traffic Items					
Roadside Signs	LS	1	LS	LS	\$2,000
Traffic Control System (Detours)	na	LS	LS	LS	\$25,000
Subtotal Traffic Items					\$27,000

Subtotal Items 1 through 5					\$1,632,000
-----------------------------------	--	--	--	--	--------------------

6 Minor Items	20%				\$326,400
----------------------	-----	--	--	--	------------------

7 Mobilization	20%				\$391,680
-----------------------	-----	--	--	--	------------------

8a Supplemental Work	20%				\$391,680
-----------------------------	-----	--	--	--	------------------

8b Contingency	20%				\$391,680
-----------------------	-----	--	--	--	------------------

8 Subtotal - Channel Improvements					\$3,133,440
--	--	--	--	--	--------------------

9 Structures Items					
Bridge Structure	na	LS	LS	LS	

Subtotal Construction					\$3,133,440
------------------------------	--	--	--	--	--------------------

10 Utility Reloc (Budget)					
Utilities Exist On site: This budget is for City-Owned					
Relocate City Water	na	LS	LS	LS	\$0
Relocate City Sewer	na	LS	LS	LS	\$0
Verizon, Cox, Gas- Relocation cost paid by others					\$0
Subtotal Utilities					

11 Env Mitigation (Structure) (budget)	na	LS	LS	LS	
Subtotal Environmental Mitigation Structure.					

12 Right of Way					
Permanent 'Creek' (Budget)		4,500	SF	\$10	\$45,000
Permanent 'Developable' (Budget)		3,000	SF	\$55	\$165,000
Permanent 'Maintenance' (Budget)		4,800	SF	\$35	\$168,000
TCE (Budget)		LS	LS	LS	\$50,000
Subtotal - R/W					\$428,000

Right of Way costs are very rough "place holders".

Total Capital =Items "Subtotal Construction"+9+10+11+12

Total Capital--Construction Cost					\$6,694,880
---	--	--	--	--	--------------------



References:

1. Department of the Army, Los Angeles District, Corps of Engineers, Los Angeles, California, June 1974. Flood Plain Information Montecito Streams vicinity of Montecito Santa Barbara, California.
2. Committee on Natural Disasters Commission on Sociotechnical Systems National Research Center and the Environmental Quality Laboratory California Institute of Technology, Sept. 17-18, 1980, Storms, Floods, and Debris Flows in Southern California and Arizona 1978 and 1980.
3. Penfield and Smith, Nov. 21, 2003, Flood Capacity Master Plan for Sycamore Creek, Santa Barbara, California.
4. Questa Engineering Corporation, August 4, 2005, Existing Conditions Study of the Arroyo Burro, Mission, Sycamore, and Laguna Creek Watersheds.

